



Imperial County Planning & Development Services Planning / Building

November 6, 2023

Jim Minnick
DIRECTOR

Subject: Request for Proposal (RFP) for an Initial Study for the Installation of a New Force Main Pipeline, Repairing Pump Station to include Telemetry Equipment.

Project Applicant: ICDPW

Project Name: Initial Study for Country Club Sewer Maintenance District (CCSMD).

- IS #23-0028

Dear Consultant:

The Imperial County Planning & Development Services Department is soliciting proposals for the preparation of Initial Study # 23-0028 for the attached project. **The Imperial County Planning & Development Services Department** will act as the "Lead Agency" for the preparation of the Initial Study pursuant to the California Environmental Quality Act (CEQA) for the project. The successful consultant will work directly for the Imperial County Planning & Development Services Director in the preparation of this CEQA document.

The COUNTRY CLUB SEWER MAINTENANCE DISTRICT (CCSMD) project includes:

1. Initial Study #23-0028

- Installation of a New Force Main Pipeline.
- Repairing Pump Station to include Telemetry Equipment.
- Eliminate the force main pipeline breaks and subsequent sewer spills.
- Installation within existing IID easement, offset and parallel to existing force main which begins at the sewer pump station.
- APN: 045-100-069-001
- Current zone S-1-U (Open Space/Recreational, Urban Overlay)

Please review attached project description.

- I. The County hereby requests the following information: for each item (as appropriate) the hourly rate and estimated total hours for the specific task must be documented.**
- a. Project scope to be utilized in the preparation of a legally adequate CEQA document.
 - b. Identified milestones representing specific tangible work products (tasks) to which payments by the County would be linked and become part of the legal contract. (Please note that all subsequent bills/invoices will be required to include both the identified milestones and percent completed).
 - c. All potential subcontractor(s) that will be utilized along with their estimated staff time and cost breakdown.

- d. An estimated "not to exceed cost" to prepare the Initial Study documents.
- e. A digital (CD) version of all documents prepared by the prime CEQA consultant and potential subcontractor(s).
- f. Also, proposals must incorporate the cost estimate for the printing of the Final environmental documents.

The proposal must provide that prior to any cost overruns, the consultant shall discuss this first and then seek written approval from the County Planning and Development Services Director, Jim Minnick before such costs are incurred. Failure to get prior written approval may result in such costs being disallowed.

We request that you provide within your cost estimate for the proposed Initial Study-including costs for the preparation of the following studies\analysis.

- Aesthetics
- Agriculture and Forest Resources
- Air Quality / Greenhouse Gas emissions
- Hydrology and Water Quality
- Biological Resources
- Cultural Resources/Historical/Archaeology
- Geology and soils
- Hazards and Hazardous Materials
- Land Use Planning
- Noise
- Public Services (Police, Fire, Schools)
- Transportation
- Tribal Cultural Resources
- Utilities and Service System
- Energy
- Wildfire
- Mineral Resources
- Population and Housing
- Recreation
- AB-52 Tribal Cultural Resources
- CEQA Findings for Project
- Mitigation, Monitoring & Reporting Program (MM&RP)

II. The following format should be used in preparing the proposal, additional information/items may be used to further bolster your proposal:

One page cover letter introducing your firm.

1. Project Understanding

2. Project Team

- Identify all company and consultant team personnel who will work on the project and short description of their education and work experience.
- Resumes of the prime and technical consultants should be included and can be attached to the proposal as an appendix.
- Organization Charts-Elaborate organization charts are not necessary.

3. Scope of Work

- Describe the proposed tasks to accomplish the scope of work.
- Include deliverables, when applicable, for each task.
- Include all applicable site visits, scoping meetings, staff meetings and public hearings.
- Be specific regarding your approach to completing the CEQA notice requirements.

4. The tasks should be presented as follows:

- a) Project Initiation
Include research, site visit, data collection, CEQA notices, scoping meetings, etc.
- b) Administrative Draft Initial Study
Include mandatory CEQA sections, required and optional technical studies, number of revisions, meetings, and coordination with County Staff.
- c) Public Review Draft Initial Study (EEC Hearing)
Include document preparation, CEQA notice, Scoping meeting, and coordination with County Staff.
- d) Final Initial Study
Include document preparation, Response to Comments, CEQA notice, meetings, coordination with County Staff and attendance at Planning Commission and Board of Supervisors hearing.
- e) Mitigation, Monitoring and Reporting Program
Include the preparation per CEQA identification of all mitigation measures, identification of all responsible parties, timing and enforcement.
- f) CEQA Findings and Notice of Determination
Include the preparation per CEQA requirements.
- g) Assumptions
Please provide a specific section for assumptions. Include your assumptions regarding travel time, mileage, public noticing, or anything else that needs clarification.
- h) Meetings
The number of meetings and hearings that are included in your proposal should be detailed under each task.

5. Proposed Schedule

Provide the number of weeks for each task in tabular form from project initiation to public hearings; there is expected to be two (2) public hearings (Environmental Evaluation Committee, and Planning Commission).

6. Cost Estimate/Milestones

- Provide a discussion of the proposed cost and any optional costs.
- Include a spread sheet that details your personnel, any subcontractors to be used, their estimated hours, and associated costs per task (can be attached as an appendix).
- A table of project milestones should be included in the Cost Estimate discussion.

7. Consultant Selection Criteria

- a) **Understanding of the project:** the proposer should demonstrate an understanding of key elements of the project and, accordingly, provide the names of personnel and their expertise.
- b) **Approach to the project:** The selection process will evaluate the extent to which the proposer has recognized and identified special circumstances on the project and whether the proposer has provided logical approach to tasks and issues of the project.

c) **Professional qualifications necessary for satisfactory performance:** The project manager and key team members should be qualified to perform the work categories on the project; and the proposer's knowledge of standards and procedures will be examined.

d) **Specialized experience and technical competence in the type of work required:** The proposal should provide information about comparable projects they have been involved with and/or successfully accomplished; past performance on contracts with government agencies and private industry will be considered together with past performance evaluations; and the capacity to accomplish the work in the required time will also be evaluated.

III. **It is requested that you disclose any conflict** or potential conflict that you may have if you are submitting a proposal. The conflict by the County envisions, at the very minimum, current/ongoing or previous contracts (within the past year) with the applicant(s); this also includes current technical studies that either are or have been prepared for the applicant(s) within the last year.

IV. **Not providing the extent of information (including hourly rate and total estimated hours per task) may negatively impact the evaluation of your proposal.**

If you are interested in submitting a proposal, please submit it to the Director at Imperial County Planning & Development Services Department, 801 Main Street, El Centro, CA, 92243, **no later than November 20, 2023, at 5:00 PM.** This must be post-marked or sent via facsimile on or before this date and time.

Please note that it is **not necessary to present us with voluminous references or individualized background data** on persons or personnel within your organization. We may require this at a later date. We look forward to receiving your RFP submittal.

Please submit a total of 2 hard copies and a CD.

If you do have any questions, please contact the assigned Planner for this project, Evelia Jimenez, Planner II at ejimenez@co.imperial.ca.us or at ext. 1747.

Sincerely,

By: 
Evelia Jimenez, Planner II

Jim Minnick, Director
Planning & Development Services Department

Attachments: Project Applications

CC:
Jim Minnick, Director of Planning and Development Services
Michael Abraham, AICP, Assistant Director of Planning & Development Services
Diana Robinson, Planning Division Manager
Project File: IS23-0028
APN 045-100-069-000
Files:10.102; 10.101; 10.104; 10.105
S:\AllUsers\APN\045\100\069\IS23-0028\RFP Letter\Country Club Sewer Maintenance.docx

BARBARA WORTH COUNTRY CLUB SEWER MAINTENANCE DISTRICT

CCSMD

PRELIMINARY ENGINEERING REPORT (PER) FOR FORCE MAIN REPLACEMENT AND PUMP STATION UPGRADES

Final

OCTOBER 2021

Prepared for:

John Gay, Public Works Director – County of Imperial

Country Club Sewer Maintenance District

Prepared By:

David Dale, PE

daviddalepe@gmail.com



CCSMD Service Area

Contents

Introduction/Executive Summary	4
History of the CCSMD	4
Description of the CCSMD.....	7
Description of the CCSMD Problems	7
Proposed System Improvements.....	10
PROPOSED IMPROVEMENTS:.....	13
Phasing Recommendations and Engineer’s Cost Estimate.....	14
Phase 1 – Engineer’s Opinion of Probable Project Quantities and Costs.....	16
Phase 2 – Engineer’s Opinion of Probable Project Quantiles and Costs.....	17
Phase 3 – Engineer’s Opinion of Probable Project Quantities and Costs.....	18
Engineer’s Opinion of Probable Total Project Costs.....	19
Discussion of Engineer’s Opinion of Probable Project Costs.....	19
References	20
Exhibit A – Bureau Veritas “Country Club Sewer Maintenance District Final Facilities Assessment Report”, December 19, 2012.....	21
Exhibit B – Colorado River Basin Regional Water Quality Control Board – NOTICE OF VIOLATION, Barbara Worth Country Club Collection System, October 5, 2021 .	22

Introduction/Executive Summary

The purpose of the Preliminary Engineering Report (PER) is to examine the Barbara Worth Country Club Sewer Maintenance District (CCSMD) force main and pump station, to respond to the Notice of Violation (NOV) dated October 5, 2021 from the Colorado River Basin Regional Water Quality Control Board (RWQCB), and to determine the most favorable method to eliminate future sanitary sewer overflows (SSO) in the future.

Another reason for this report is to recommend the diameter size of the replacement force main. As a part of this report, the existing documentation was reviewed and analyzed. There have been multiple reports over the years - starting in 1998 – recommending replacement of the existing 4-inch diameter pipe with different force main diameter sizes (6”, 8” and 10”). Currently there is a proposed new RV Park development in the CCSMD service area. Therefore, the diameter size will be determined based on existing flows and proposed flows with the RV Park. In addition, the pump station was inspected and upgrades are recommended as a part of this report.

This PER does not address the gravity sewer collection system.

History of the CCSMD

On June 16, 1970, the Board of Supervisors determined that a Sewer Maintenance District should be formed. The Country Club Sewer Maintenance District (CCSMD) was created to perform the functions authorized under Chapter 4, Part 3, Division 5, of the Health and Safety Code of 1970 to protect public health. Although the County of Imperial oversees it, this Special District is a separate agency. It was created at the request of the property owners to maintain the sewer system for the homes located at the Barbara Worth Country Club. On July 21, 1970 (minute order #7) the Imperial County Board of Supervisors authorized the Department of Public Works to perform the administration of the Country Club Sewer Maintenance District (CCSMD) and to negotiate with the City of Holtville for performance of routine maintenance and operation of the plant.

The City of Holtville assumed the responsibility for the operation and maintenance of the district's sewer system on March 31, 1976, under an agreement between the District and the City of Holtville dated December 19, 1972. This agreement gave the City of Holtville the option to opt out of providing maintenance services by giving six months written notice. The City elected this option by giving written notice in December, 2001. Effective July 1, 2002 the CCSMD was responsible for all maintenance costs associated with the sewer lines and the pump station.

This document includes information from several public sources (see references), including the "Country Club Sewer Maintenance District Informational Report", prepared by the County of Imperial, Department of Public Works in June of 2006. This information was placed here for convenience of the reader. The following 11 pages are an excerpt from this report.

On April 16, 1971 David E. Pierson, Director of Imperial County Public Works Department made the first attempt to negotiate with the City of Holtville for maintenance of the sewer system for the CCSMD. At this point the City of Holtville declined the invitation to take over maintenance of the system.

On December 19, 1972 the CCSMD and the City of Holtville entered into an agreement which stipulated that the City of Holtville would operate and maintain the District's sewer system and would establish and collect service charges and maintenance fees to operate the district. This agreement provides the ability for either party to terminate the contract effective at the end of any fiscal year provided that six (6) months prior written notice of such intention is first given. In the event of any such termination, CCSMD shall pay the city a reasonable charge for the right to continue its tie-on with city's sewerage system. If such amount cannot be mutually agreed upon, the charges shall be set through the arbitration process as outlined in paragraph 8 in the 1972 agreement.

On February 15, 1977 the City of Holtville's representatives expressed concern about the 1972 agreement between the city and the CCSMD. The representatives' concern was that the contract could be misconstrued and impose certain duties and obligations on the District to operate and maintain, on the basis or terms set forth therein, sewerage improvements installed on lands which are annexed into the CCSMD in the future; and thereby overburden facilities owned in the city.

The CCSMD was willing to amend the contract as follows:

The city's obligation, under the contract, is to operate and maintain CCSMD's sewage system and to ensure the proper functioning thereof and shall pertain only to the sewage system and works constructed within the district's current legal description. City shall not, by reason of the contract, be responsible for the operation and maintenance of sewage facilities constructed in any area which might be annexed to the legal description stipulated in October 3, 1975 agreement. On December 26, 2001 the Holtville City Council took action to officially notify the County of Imperial and the CCSMD that the City of Holtville was invoking Paragraph 10 of the 1972 agreement between the County, the CCSMD, and the city. Paragraph 10 states the following:

"10. City's agreement to operate and maintain District's sewerage system and to establish and collect service charges and fees may be terminated by either party effective at the end of any fiscal year provided that six (6) months prior written notice of such intention is first given. In the event of any such termination, District shall pay City a reasonable charge for the right to continue the tie-on with City's sewerage system. If the amount of charges cannot be mutually agreed upon, the charges shall be set through the arbitration process as outlined in paragraph 8 above".

In their letter, the Council, City Staff and the City Manager (John A. Jordan), stated their interest in bringing the project to a mutually agreeable resolution. This letter notified the County of Imperial to assume full responsibility for the operation and the maintenance of CCSMD's facilities which included the pump station and sewer force main line no later than June 30, 2002.

On December 26, 2001, the Holtville City Council took action to officially notify the County of Imperial (CCSMD) that the City of Holtville is invoking Paragraph 10 of the agreement between the County CCSMD and the city.

In his letter the City Manager (John A. Jordan) informed the county that the city is only obligated to "maintain the sewer line," it is the county's responsibility to provide funds for the replacement, and to accept any liability should the line fail in any way. The City Manager also states that the council and city staff is interested in bringing the project to a mutually agreeable

resolution. This letter notified the County of Imperial to assume full responsibility for the operation and the maintenance of the pump station and sewer line no later than June 30, 2002.

Description of the CCSMD

Sewer service is provided approximately 1.5 miles outside of the city limits to the Barbara Worth Country Club and surrounding residential community. This development is located south of the Alamo River. Wastewater is conveyed from this development to the city's wastewater treatment plant through a dedicated sewer pump station and force main system. The Barbara Worth Pump Station, located off Holton Road, conveys wastewater from the Barbara Worth Country Club and surrounding community. The Barbara Worth Pump Station is a small package type pump station. Wastewater flows from residential sewers to a PVC gravity sewer interceptor that flows underneath State Route 115 and the Holton Interurban Railroad to a sub grade manhole type wet well. Duplex end-suction pumps with automatic controls discharge to a 4-inch PVC force main. The force main parallels the Barbara Worth Canal, crosses under the Rositas Canal and the Alamo River and ultimately connects to the city's sewer outfall main located in Kamm Road near the city's wastewater treatment plant. The total length of the 4-inch force main is approximately 10,400 feet.

Description of the CCSMD Problems

The CCSMD sewer collection system is considerably old, and has experienced operational problems prior to 1998. In addition to maintenance related problems, the system has had difficulty handling high peak flows. This results in high head losses in the small 4-inch diameter, long length of force main pipe. In 1998, the pump station was considered to be at capacity under current service loads. The lift station does not have a permanent back-up power supply; however, the city's trailer-mounted generator is available to operate the lift station during extended power outages.

The 10,200 lineal foot wastewater force main extending downstream of the Barbara Worth Pump Station has been a source of pipeline ruptures, pipeline clogs, and pump maintenance problems for over three decades. The continued rupturing of the 4-inch wastewater force main results in health and safety issues in the vicinity of the Imperial Irrigation District Canal Network. It would be prudent for Imperial County to replace the existing undersized 4-inch diameter force main with a heavy wall AWWA C-900, Class 150 PVC wastewater force main as soon as possible.

On February 8, 2006, The Holt Group, Inc. prepared a report for the County of Imperial named “Barbara Worth Wastewater Forcemain Installation and Sanitary Sewer Pump Station Replacement Report”. In this report the Holt Group, Inc. concluded that during the last 10-years the existing wastewater pump station has continued to deteriorate and periodically fail. The maintenance cost, time and effort devoted to keep the pump station in a working condition is significant and far in excess of what is normally required. The electrical panels and pumping units are aged, outdated, inefficient and in a deteriorated condition. The replacement of the existing 4-inch diameter force main with a larger diameter force main would allow for the installation of the wastewater pumps at a lower total dynamic head requiring less energy to operate. The pumps would produce a greater flow at less total dynamic head (and pressure) resulting in less maintenance. The electrical costs associated with the wastewater pump station would decrease.

On December 9 2012, Bureau Veritas (BV) presented the “Country Club Maintenance District Final Facilities Assessment Report”. This report is very detailed regarding the condition of the collection system and pump station as of approximately nine years ago. In it, the flow from the pumps through the 4-inch main is 75 gpm at 34 psi (approximately 35% efficient) even though the design point is approximately 400 gpm at 26 psi (50% efficient). The BV report will not be repeated word for word in this report.

A meeting at the site occurred on 10/15/21 with the system operator. The condition of the pump station and 4-inch diameter force main was discussed. In the meeting it was determined that:

1. The most pressing need for the system at this time is to replace the first section of force main pipeline, from the pump station to Zenos Road. This section has presented numerous problems over the years with pipeline ruptures. It has ruptured at least once per year, sometimes twice a year – causing sanitary sewer overflows (SSO). There is approximately 5,814 feet of the wastewater force main to be replaced, extending from the Barbara Worth Pump Station to a point immediately south of the Rosita Lateral and Alamo River. Two recent ruptures caused Sanitary Sewer Overflow (SSO) of approximately 66,000 gallons of sewage, which resulted in a Notice of Violation dated October 5, 2021 from the Colorado River Basin Regional Water Quality Control Board.
2. There are no alarms on the pump station. At minimum there should be an alarm to notify operators of high sanitary sewer levels (i.e., pumps are inoperable or there is a clog in the system). The alarm would be based on cellular coverage, since there is no telephone service at this location. Additional alarms would be loss of power, low level and possibly temperature of the pumps (i.e., loss of prime).
3. The control panels and electrical and gauges should be all be replaced. The control panel is located inside the weather cover of the pump station (presumably for shade), causing exposure to hydrogen sulfide gas. It is also more difficult to access.
4. There should be a flow meter on the pump station. There is an hour meter. The pumps run about 10 hours per day.
5. There should be a surplus pump and motor onsite in case there is a problem with the pumps or motors.
6. There is no backup generator onsite; operators bring a portable generator when needed.

7. The pumps were replaced in 2015 and are in good condition. The pumps were replaced with the same pumps that were there as described in detail in the BV report.

Proposed System Improvements

It has been clearly shown in the above-named reports, notice of violation and site inspections that the 4-inch force main pipe is past its useful life, is structurally unsound, and is insufficiently sized for the pumps installed and the flow required from the development. The question then is what size the force main should be. Bigger is not necessarily better in this case; a pipe sized too big would result in lower than required scour velocities (need greater than 2 feet per second inside the pipe) to keep the pipe from clogs. Additionally, a long sewer force main pipe sized too big will result in the formation of hydrogen sulfide gas inside the pipe due to septic biologic processes. Therefore, the pipe should be sized appropriately, not too big and not too small.

The Bureau Veritas report (Exhibit A) did an in-depth analysis on the appropriate pipe size for the existing community. According to the report, a 6-inch diameter pipe (class 150 or higher) would adequately convey 260 gpm at 60 feet total dynamic head (TDH) or 26 psi. This would result in a pipeline velocity of 2.8 feet per second (fps), greater than the needed 2.0 fps for scour velocity.

Since there is no flowmeter, to calculate the actual flow from the pump station:

The operator states that the pump station runs approximately 10 hours per day. The BV report indicates that the pump station in its current condition runs at about 75 gallons per minute:

$10 \text{ hours per day} \times 60 \text{ min./hour} \times 75 \text{ gallons/min} = \underline{45,000 \text{ gallons per day of sewer flow generated per day.}}$

The *average* flow would then be $45,000 \text{ gal} / 24 \text{ hour} / 60\text{min./hr} = 31 \text{ gal per min.}$

Actual Peak flow based on these calculations is: $31 \text{ gpm} \times 4.0 = \underline{124 \text{ gpm.}}$

$45,000 \text{ gal per day} / 215 \text{ EDU} = \mathbf{209 \text{ gal. per EDU}}$ per day generated on average.

The *theoretical average peak flow* from the development is 215 gpm per the BV Report or 0.31024 million gallons per day (MGD). Peak flow was estimated using a 4.0 multiplier against the calculated average daily flow.

Consideration is now needed for the potential development for the RV Park at the Barbara Worth Country Club. Again, this report is not taking into consideration the existing gravity flow collection system, only the pump station and force main.

There are 215 EDUs connected to the CCSMD collection system. Theoretical Peak flow is 215 gpm as stated above. Therefore, there is 1 gpm average peak flow per EDU. The RV Park is proposing to have 116 RV spaces. Typically, an RV Space is allocated to 0.25 EDU for calculating water demand and sewer flows. Therefore, the RV park would increase the peak sewer flows by $0.25 \text{ EDU/Space} * 1\text{gpm/EDU} * 116 \text{ spaces} = \mathbf{29 \text{ gpm}}$. If 0.50 EDU is used, the theoretical peak flow would be 58 gpm; using 1.0 EDU it would be 116 gpm.

The total theoretical average peak flow is therefore $215 + 29 = 244 \text{ gpm}$. The pumps would be able to keep up with the peak flow at 260 gpm as stated in the BV report, even with the RV Park added to the system. This is backed up by calculations based on hourly pumping of 124 gpm peak flow of existing connections (shown above).

Therefore, even with the proposed RV Park (116 spaces), a 6-inch diameter force main pipeline class 150 pipe is recommended. An 8-inch diameter pipe would be sized for 400 gpm; however, the theoretical peak flow is not more than the 260 gpm at 60 feet total head as described in the BV Report. Installing a pipe with a larger-than-needed diameter would result in undesirable conditions: (1) a scour velocity less than 2.0 ft/sec, (2) the retention time in the 2-mile-long force main pipe would be increased causing hydrogen sulfide gasses to form, and (3) higher project costs. One benefit of installing the 8-inch force main would be that it would be beneficial for future development resulting in a system capable of serving more than 800 EDU at the current flow of 209 gallons per day per EDU.

Barbara Worth Country Club			
Existing Residential EDU	111		
Existing Hotel EDU	104		
Total Existing EDU	215		
1 EDU capacity	209	Average Gallons per Day (as measured based on 10 hours pump station operation and 75gpm per BV Report)	
Pumping Capacity (with 4-inch diameter force main)	75	Gallons per Minute (Per BV Report)	
Pumping Capacity (with 6-inch diameter force main)	260	Gallons per Minute (Per BV Report)	
Existing Sanitary Sewer Flow	45,000	Gallons per Day	
Pumping Capacity (with 4-inch diameter force main)	54,000	Gallons per Day (50% Operation time)	
Pumping Capacity (with 6-inch diameter force main)	187,200	Gallon per Day (50% operation time)	
Pumping Capacity (with 8-inch diameter force main)	288,000	Gallon per Day (50% operation time)	
Total EDU Capacity of pump station (with 4-inch diameter force main)	258	EDU	(Existing 215 EDU)
Total EDU Capacity of pump station (with 6-inch diameter force main)	895	EDU	
Total EDU Capacity of pump station (with 8-inch diameter force main)	1378	EDU	

CCSMD EDU Capacity

PROPOSED IMPROVEMENTS:

Recommended Force Main Improvements:

1. Replace the existing 4-inch diameter force main pipeline with a **6-inch diameter pipeline** in phases as described in the next section. Use long sweep elbows in lieu of 90-degree bends, as stated in the BV report.

Recommended Pump Station Improvements:

2. Install alarms. At minimum there should be an alarm to notify operators of high sanitary sewer levels (i.e., pumps are inoperable or there is a clog in the system). The alarm would be based on cellular coverage since there is no telephone available. Additional alarms could include temperature of the pumps and low level conditions.
3. Replace the electrical, control panels and distribution switchboard which will include the installation of new electrical service per I.I.D requirement. The new control panel should be located outside the weather cover of the pump station. A small shade structure will be necessary.
4. Install a flow meter on the pump station.
5. Clean the wet well. Repair the bottom surface of the wet well and coat all interior surfaces with a protective coating.
6. There should be a surplus pump and motor onsite in case there is a problem with the pumps or motors.
7. Sandblast and coat piping of the pump station.
8. Remove and replace the pump station above grade P.C.C. slab.
9. Install emergency power generator set for the Barbara Worth Pump Station


Phasing Recommendations and Engineer's Cost Estimate

A detailed Engineer's Opinion of Probable Cost was prepared regarding the replacement of the existing 4-inch diameter force main with a 6-inch diameter line. The phased installation of the force main would allow for the inclusion of the costs relative to a given phase to be placed in an agency's budget for a given fiscal year. The phased improvements would also increase local contractors' participation with regard to the bidding of the project. The installation of segments of the force main would eliminate the pipeline ruptures along the length of the wastewater force main which was replaced and decrease the pressure exerted by the Barbara Worth Lift Station pumps.

Phase 1 Improvements include 5,814 feet of the wastewater force main extending between the Barbara Worth Pump Station and a point immediately south of the Rosita Lateral and Alamo River. Ruptures and blockages of the wastewater force main have been noted to be most prevalent along this section of the pipeline in the past five years. There have been at least one to two ruptures per year along this section. It has been repaired numerous times over the past 20 plus years.

Phase 2 would entail the replacement of the approximately 300 feet of pipeline section which presently passes beneath the Alamo River and Rosita Lateral. This is considered higher priority than Phase 3 because of the proximity to the river. The pipe would be directional drilled beneath said river and lateral, to be installed inside a larger 12" dia. protective casing pipe.

Phase 3 improvements recommend that an approximate 4,086 – foot section of the wastewater force main be replaced between a point immediately north of the Alamo River and the termination point of the wastewater force main at the manhole located along the gravity outfall sewer pipeline at the intersection of Gowling Road and Kamm Road immediately upstream of the Holtville Wastewater Treatment Plant. The installation of the majority of the wastewater force main per Phases I and II would drastically reduce the frictional loss along the length of the pipeline and consequently reduce the maintenance associated with the Barbara Worth Pump Station.



PROPOSED PHASING MAP

Phase 1 – Engineer’s Opinion of Probable Project Quantities and Costs

ITEM	QUA	UNIT	ITEM	UNIT COST	AMOUNT
1	1	LS	Mobilization of equipment and material, Bonds, Insurances, project signs, and fees, Restroom Facilities, Business license, and Similar expenses and other costs.	\$ 32,000.00	\$ 32,000.00
2	1	LS	Preparation and Implementation of Dust Control Plan Per Imperial County Air Pollution Control District	\$ 1,500.00	\$ 1,500.00
3	1	LS	Preparation of Traffic Control Plan, Implementation of Traffic Control and Construction Area Signs	\$ 5,500.00	\$ 5,500.00
4	1	LS	Potholing of the Existing Underground Utilities and Pipelines as indicated on Improvement Plans.	\$ 4,000.00	\$ 4,000.00
5	5,814	LF	Furnish and Install New 6-inch Dia. AWWA C-900 DR 18 - Pressure Class 150 PVC Force Main Pipeline, Including all Fittings, magnetic tape, Backfill and Compaction.	\$ 50.00	\$ 290,700.00
6	12	EA	Install force main cleanouts	\$ 3,500.00	\$ 42,000.00
7	180	CYD	Furnish and install Import sand material for backfilling the forcemain pipe.	\$ 100.00	\$ 18,000.00
8	40	LF	Sawcut AC Pavement at Pipeline Trench Crossing Zeons Road	\$ 50.00	\$ 2,000.00
9	0.5	CYD	Remove and Dispose of AC Pavement	\$ 2,700.00	\$ 1,350.00
10	50	SF	Install 4-inches of AC over 10 inches Class 2 Base Zenos Road	\$ 100.00	\$ 5,000.00
11	1	LS	Contractor to Complete Hydrostatic Pressure Testing per Specifications.	\$ 5,000.00	\$ 5,000.00
12	1	LS	Imperial County Encroachment Permit Fee Allowance.	\$ 5,000.00	\$ 5,000.00
13	1	LS	Repair Wet Well Floor, Clean and Line Wet Well with Epoxy Coating	\$ 20,000.00	\$ 20,000.00
14	1	LS	Replace Electrical, Control Panels and Gauges.	\$ 27,000.00	\$ 27,000.00
15	1	LS	Install Screen on Wet Well Opening	\$ 3,500.00	\$ 3,500.00
16	1	LS	Install 6-inch flowmeter	\$ 5,000.00	\$ 5,000.00
17	1	EA	Furnish (1) surplus pump and (1) surplus motor	\$ 10,000.00	\$ 10,000.00
18	1	LS	Install and Program Alarms	\$ 4,500.00	\$ 4,500.00
				Total Bid Items:	\$ 482,050.00
				Contingencies @10%	\$ 48,205.00
				Total Construction Phase I	\$ 530,255
SOFT COSTS					
			Research right of ways and easements along pipeline route, topographic survey, engineering design, preparation of plans, meetings @ 7%		\$ 37,118
			Bidding of Project		\$ 4,000.00
			Construction Administration and Management @ 7%		\$ 37,118
			Total Soft Costs		\$ 78,236
			Total Project Costs Phase 1		\$ 608,491

Phase 3 – Engineer’s Opinion of Probable Project Quantities and Costs

ITEM	QUA	UNIT	ITEM	UNIT COST	AMOUNT
1	1	LS	Mobilization of equipment and material, Bonds, Insurances, project signs, and fees, Restroom Facilities, Business license, and Similar expenses and other costs.	\$ 21,000.00	\$ 21,000.00
2	1	LS	Preparation and Implementation of Dust Control Plan Per Imperial County Air Pollution Control District	\$ 1,500.00	\$ 1,500.00
3	1	LS	Preparation of Traffic Control Plan, Implementation of Traffic Control and Construction Area Signs	\$ 5,500.00	\$ 5,500.00
4	1	LS	Potholing of the Existing Underground Utilities and Pipelines as indicated on Improvement Plans.	\$ 4,000.00	\$ 4,000.00
5	4,086	LF	Furnish and Install New 6-inch Dia. AWWA C-900 DR 18 - Pressure Class 150 PVC Force Main Pipeline, Including all Fittings, magnetic tape, Backfill and Compaction.	\$ 50.00	\$ 204,300.00
6	8	EA	Install force main cleanouts	\$ 3,500.00	\$ 28,000.00
7	120	CYD	Furnish and install Import sand material for backfilling the forcemain pipe.	\$ 100.00	\$ 12,000.00
8	1	LS	Connect to existing manhole along Kamm Road.	\$ 3,500.00	\$ 3,500.00
9	1	LS	Contractor to Complete Hydrostatic Pressure Testing per Specifications.	\$ 5,000.00	\$ 5,000.00
10	1	LS	Imperial County Encroachment Permit Fee Allowance.	\$ 5,000.00	\$ 5,000.00
11	1	LS	Furnish and Install Backup Generator for Pump Station	\$ 100,000.00	\$ 100,000.00
				Total Bid Items:	\$ 389,800.00
				Contingencies @10%	\$ 38,980.00
				Total Construction Phase 3	\$ 428,780
SOFT COSTS					
			Research right of ways and easements along pipeline route, topographic survey, engineering design, preparation of plans, meetings @ 7%		\$ 30,015
			Bidding of Project		\$ 4,000.00
			Construction Administration and Management @ 7%		\$ 30,015
			Total Soft Costs		\$ 64,029
			Total Project Costs Phase 3		\$ 492,809

Engineer's Opinion of Probable Total Project Costs

As of 10/19/21:

Construction		Soft Costs		Subtotal
Phase 1	\$ 530,255	Phase 1	\$ 78,236	\$ 608,491
Phase 2	\$ 132,000	Phase 2	\$ 22,480	\$ 154,480
Phase 3	\$ 428,780	Phase 3	\$ 64,029	\$ 492,809
Totals	\$ 1,091,035		\$ 164,745	\$ 1,255,780

Discussion of Engineer's Opinion of Probable Project Costs

Project costs have risen drastically in the past 12 months. The costs for pipe have increased 300% since March 2020. Costs for fittings, parts and equipment have increased. The pre-pandemic cost estimate for this project, based on bids received for similar projects, was approximately **\$826,024**. The cost estimates for this project are based on conversations with local contractors who do this type of work and are familiar with current pricing. The engineer's estimate of probable project cost is now **\$1,255,780**.

This represents a 52% increase from March 2020.

** Prices are very unstable at this time. Prices may come back down, or may continue to increase. For this reason, it is important that the cost estimate should be updated at the time of budgeting and project funding.

References

County of Imperial, Department of Public Works Country Club Sewer Maintenance District Informational Report, June 2006

County of Imperial, Clerk of the Board of Supervisors office, “1972 Agreement between the City of Holtville and CCSMD”, December 1972

The Holt Group, Inc., “Barbara Worth Forcemain Installation and Sanitary Sewer Pump Station Replacement Report”, February 2006

The Holt Group, Inc., “Barbara Worth Wastewater Forcemain Installation”, June 16, 1998

Bureau Veritas, “Country Club Sewer Maintenance District Final Facilities Assessment Report”, December 19, 2012

Exhibit A – Bureau Veritas “Country Club Sewer Maintenance District Final Facilities Assessment Report”, December 19, 2012

Country Club Sewer Maintenance District Final Facilities Assessment Report



December 19, 2012

Prepared For:



Imperial County Department of Public Works
155 South 11th Street
El Centro, CA 92243
William S. Brunet PE, Director

Prepared By:



Bureau Veritas North America, Inc.
10620 Treena Street, Suite 200
San Diego, CA 92131
Phone: 858.451.6100 Fax: 858.451.2846
www.us.bureauveritas.com

Move Forward with Confidence.

BVNA JN 18020.06



Table of Contents

Table of Contents.....	1
Executive Summary.....	2
Background and Overview.....	4
Pipeline Inspections.....	5
Manhole Inspections.....	9
Pump Station Inspection.....	13
Comparison with Previous Pump Station Studies.....	16
Force Main Inspection.....	19
Conclusions and Recommendations.....	23
References.....	26
Credits.....	26
Appendix A – Pump Station Calculations.....	A-1
Appendix B – CCSMD Sewer Study.....	B-1
Appendix C – CCSMD System Map.....	C-1
Appendix D – Repair Cost Estimates.....	D-1
Appendix E – Manhole Inspection Logs.....	E-1
Appendix F – Pipeline and Force Main Inspection Logs.....	F-1
CD with Digital Inspection Files and Site Photographs.....	Rear Pocket

Prepared Under the Supervision of:

Phil Kern, PE RCE 40831 Registration Expires 3/29/13

Change of Project Manager since January 2013:

Carlos Larios, PE RCE 68543 Registration Expires 3/30/13





Executive Summary

Bureau Veritas North America, Inc.'s (Bureau Veritas') division of Public Works Services was retained by the Imperial County Department of Public Works, acting on behalf of the Country Club Sewer Maintenance District (CCSMD), to evaluate the condition of the wastewater conveyance facilities serving CCSMD. The facilities that were evaluated included gravity sewer mains, sewer manholes, a wastewater pump station, and a sewer force main. CCSMD facilities include the following:

- Approximately 8,830 feet of 8-inch vitrified clay pipe (VCP) and 1,450 feet of 10-inch polyvinyl chloride (PVC) gravity sewer main
- 34 manholes, identified as MH 1 through MH 11, MH 13 through 33, MH 12 North, and MH 12 South
- 9,963 feet of four-inch PVC sewer force main
- Duplex pumps and motors housed in a fiberglass enclosure above the wet well of the pump station

The gravity sewage collection system serving CCSMD was found to be in poor condition due a lack of regular maintenance and large amounts of debris found in the system. Most of the system had to be pumped or cleaned out before being inspected. The pipeline segments that were cleaned and inspected were in generally in good condition with the typical minor issues such as cracked pipes, root intrusions, and offset pipe joints. The original sewer pipelines were installed with slopes and sags that are too flat to be self-cleaning; it is not economical to completely remedy this issue and needs to be addressed through a long-term maintenance program. The sewer system also has inherent problems with maintenance access, as most of the manholes are located in the front and back yards of residences. A preliminary estimate of the capital repairs required for the collection system is \$450,000, including contingencies.



Vactor truck cleaning operations.




24 of the 34 total manholes within the CCSMD system were inspected and were found to be in fair to very poor condition, depending on location. The remaining manholes were *not found*, buried, or otherwise inaccessible when the inspections were performed. The lower, base portions of most manholes were found to be in good condition, with the upper portions suffering from concrete corrosion, damaged grade rings, poorly fitted frames and covers, and obstructions blocking access to the manhole opening. Most of the manholes had concentric cones and steel rungs, features no longer considered acceptable for safety reasons. A total of \$460,000 in capital improvements is recommended for the CCSMD manholes, including contingencies.



Manhole 5 showing corrosion.

The pump station was last upgraded in 2004, and is considered to be in fair condition. The duplex motors, pumps, controls, wet well, and enclosure were evaluated and found to be in acceptable condition. Relatively minor upgrades to the pump station are recommended, totaling approximately \$20,000 with contingencies.

The sewer force main from the pump station was evaluated and found to be undersized from a hydraulic perspective, not allowing the pumps to function in their optimum operating range. The existing force main has also ruptured at least three times in the past several years, most likely due to the marginal strength rating of the original pipe, poor quality control during the initial construction, heat degradation of the pipe material, and pressure spikes from the newer, more powerful pumps. A preliminary estimate of \$740,000 in improvements, including contingencies, are recommended for the sewer force main, the bulk of which is replacement of the existing four-inch force main with a six-inch pipeline.



Existing 4-inch force main pipe removed from the trench.



Background and Overview

The land around the Barbara Worth Country Club was developed in the early 1970s, and included single family residences and a number of duplexes. The country club and the golf course were the only commercial properties in the CCSMD. The CCSMD was originally served by a collection system conveying wastewater to a small package treatment plant located on Barbara Worth Drive, which treated the effluent and discharged it into the Barbara Worth Drain. It is not known to what level the effluent was treated at that time. This arrangement proved unworkable over the long term and, in 1974, a new 10-inch gravity sewer main was constructed and connected to a new wastewater pump station located on Holton Road near the Barbara Worth Drain. The existing treatment plant was then removed from service. Concurrently, a 1.9-mile force main was constructed from the pump station north along Imperial Irrigation District and County rights-of-way to a manhole at the intersection of Kamm Road and Gowling Road. At this manhole the effluent was discharged into the City of Holtville's outfall sewer and conveyed west via gravity to the City's wastewater plant for treatment.



Wastewater pump station



Barbara Worth Drain



Barbara Worth Country Club golf course





Pipeline Inspections

Gravity sewer pipeline inspections were initially performed from September 24 to September 27, 2012 by Affordable Pipeline Services. The inspections were completed using a Cues Inc. OZII Pan-Tilt Optical Zoom II camera mounted on an Ultra Shorty tracked, self-propelled camera transporter. The camera was connected via video cable to a mobile CCTV van that was specially equipped for inspecting underground pipelines.



Image taken directly from CCTV camera shows an 8-inch pipeline between MH 19 and 21 that is 25%+ full of silt and debris.

Initially access to the system was difficult because of several factors. It was quickly determined that portions of the system were not constructed according to the plans; many manholes were buried under dirt or asphalt; several manholes were located within private yards; and other manholes were not found at all. Several of the manholes were later found by using a tracking device attached to the video camera, which could then be electronically located from the surface. Other manholes could not be located using the camera without clearing the main of debris, nor could they be located on the surface with a metal detector because of the access issues described above.

Portions of the sewer system as constructed did not match the record drawings provided by the County, particularly along Murray Drive. The residences on the east side of Murray Drive appear to be served by a sewer main running through their backyards along the west side of the golf course. Pending full cleaning, inspection, and additional investigation of the system it is still not clear precisely how the block bounded by Murray Drive, Barbara Worth Drive, and Country Club Drive receives sewer service. MH 28 has a small four-inch pipe coming from the west, the direction where MH 33 should be located;



Video inspection operations at MH 26. Note the location of the manhole and sewer line at the rear of the van within private backyards; this is one of the more accessible locations.



however, a four-inch main is totally inadequate to serve the 10 residences within that block. MH 33 was not found during the inspections, but it is believed to be located in the backyard of 2093 Murray Drive. This block may be served by wye lateral connections across Murray Drive to the east; via a main paralleling Murray Drive along the rear property lines and connecting to MH 28; or connecting to the newer 10-inch sewer north of Barbara Worth Drive. No trench cuts were observed in Barbara Worth Drive to support this latter alternative.

When the actual inspection effort began on September 24, it was quickly apparent that the pipelines were suffering from a lack of regular maintenance. It was not possible to get the camera into many of the sewer mains due to extensive accumulations of silt, dirt, grease, and other debris. Nearly all of the sewer mains were found to be as much as 90% full of silt and debris; others had blockages from large clumps of grease and tree roots; and others were surcharged with effluent, preventing inspection. Imperial County Department of Public Works (ICDPW) staff arranged to pump out the surcharged mains between MH 1 and MH 5 for inspection, revealing that they were also mostly blocked by debris. Attempted flushing of the lines with a water truck only served to move the debris to the next section of pipe. Following this effort a solid clump of grease and debris was observed in MH 1 that was approximately 6 inches by 6 inches by 24 inches and is illustrative of the debris issues with the system.

As a result of the poor conditions, only 2,703 feet of the 12,000 feet of gravity sewer were inspected during the initial mobilization. Only 6 of the 34 gravity sewer main segments were initially inspected due to debris problems. The portions of the VCP that could be inspected were generally in good condition, with the typical cracks, misaligned/open joints, sags, small roots, projecting laterals, and other relatively minor issues. Unusual conditions that were found include a massive taproot intrusion near MH 25; sharp horizontal bends in the main south of MH 31 that prevented inspection by the camera; and undesirable drop manhole plumbing at MH 31.

A second mobilization to the site on October 25 was accompanied by a Vactor truck, which was used to clean the debris out of the north section of the system along Barbara Worth Drive to allow for inspection. With camera access to the system the lines could not only be inspected but several additional buried manholes were located, including MHs 7, 11 and 29. It should be noted that inspections were not performed on the newly located manholes. Once the debris was removed the pipelines were found to be in generally good condition. A four-inch lateral coming from the west into MH 28 was also inspected by push camera as far as the centerline of Murray Drive. It is presumed, but not confirmed, that this pipe continues west to MH 33 as noted above.



The CCSMD system has several inherent conditions that contribute to long-term maintenance issues. Although the system has not been surveyed it appears that the pipeline slopes are all less than 0.5 percent, and it is believed that most are in the 0.2 to 0.3 percent range. Several sags and adverse slopes were noted in the inspections. These very mild slopes do not provide for cleansing velocities even at peak flows, so the solids are deposited in the pipelines and are unremoved by subsequent flows, even during peak periods. Eight-inch sewer lines should be sloped at a minimum of 0.4 percent to provide cleansing velocities at peak flow rates (refer to Appendix B for the CCSMD Sewer Study estimated flows and velocities).



Vactor truck cleaning operations at newly located MH 7 within the golf course. Note the size of the equipment required to efficiently maintain the system.

The pipeline sections that cross the golf course were found to be nearly full of silt that prevented access for inspections. The heavy irrigation of the golf course can carry fine material from the soil into the sewer pipeline through small cracks or open joints, eventually filling the pipe with silt. Replacing the entire gravity collection system at the proper minimum slope is not economically feasible, and would in turn require replacement of the pump station and likely the force main. Instead, CCSMD should institute a program of regular annual maintenance to address these issues, as well as a capital repair program to address the existing operational issues that have been identified.

Right-of-way preservation and maintenance access is also a major issue with the CCSMD system. The existing sewer mains are located in the parkways of the streets - which is not desirable as most homeowners consider that strip as part of their front yards - and along rear property lines, which places them in resident's backyards. No maintenance or utility easements were noted in the documents that were reviewed; it appears maintenance access rights are prescriptive within CCSMD. The backyard sewer locations are very problematic as maintenance access for the proper equipment (i.e., a large Vactor truck) is extremely difficult. In many locations the residents have constructed patios, landscaping, building structures, walls, and fences over the sewer mains and manholes, apparently without knowledge of the facilities' presence or regard for maintenance access. Some of the most serious examples are a large tree





planted directly over the main north of MH 25, which has created a taproot intrusion almost blocking the main, and an enclosed patio structure built over the main behind a residence on Anderholt Road.

In addition to the siltation problems noted above, grease clogs were found to be a recurring issue within the system. Cooking grease, fats, and oils discharged into the system eventually congeal and collect other debris, forming large, solid clumps that block flows. Residents can be educated to avoid discharging large quantities of grease into the sewer, and any commercial kitchens connected to the system should have a grease trap installed.

Another maintenance issue related to the pump station is that the float switches in the wet well are set so high that the collection system was surcharged or backwatered more than 2,000 feet, all the way up to MHs 5, 6, and 28. This is also an undesirable situation, because as noted previously it causes the solids to drop out of suspension and be deposited in the pipelines. It also causes floating debris, including grease, to congeal and clog the pipeline rather than be conveyed to the pump station. The system cannot be properly inspected or maintained when it is under a constant surcharge.

Video logs from the pipeline inspections are included as Appendix F, and the related digital files are included on compact disks in the rear pocket of this report.



Location of MH 25 within a private patio, as located by the video camera with a tracking device.



Manhole Inspections

Bill Grigsby, PE, performed inspections on 24 of the 34 manholes within the CCSMD system on September 24 and September 25, 2012. Following the initial reconnaissance, one additional manhole was located on the golf course between manholes 11 and 12, so they are delineated as manholes 12 North and 12 South. Most of the manholes are relatively shallow, at less than eight feet deep, with a 24-inch diameter manhole opening expanding to 48-inches at the base. Most manholes appear to have concentric cones and steel rungs for access, features not typically seen in



The worker is holding the probe at the center of MH 29, which is in a private backyard underneath the decorative wall on the left and the wrought iron fence on the right.

current installations for safety reasons. Several of the manholes were located within the yards of private residences (MHs 24 through 27 and MHs 29 through 33); some were accessible for inspection while many others were not. ICDPW management asked that Bureau Veritas inspectors not enter private yards to perform inspections.


Many other manholes are located in the parkway of the public street, which residents typically consider part of their front yard. As a result, residents have placed soil, paving landscaping, or decorative walls over the tops of the manholes. After several days of work at the site, Bureau Veritas, Affordable Pipeline Services, and ICDPW crews were able to locate all manholes except MHs 31 and 33. MH 31 is believed to be located in the backyard of 2068 or 2070 Country Club Drive; it was not able to be located by tracing the tractor camera because of sharp horizontal bends in the pipe to the south and the lack of camera access to MH 30 immediately to the north. MH 33 is suspected to be located in the backyard of 2093 Murray Drive and was not accessible to the tractor camera or locating crews for similar reasons.

Crews were not able to obtain access to MHs 10, 11, 25, 27, 29, and 30 for inspection as they are located in private yards or are otherwise obstructed by private improvements. Typical situations include MHs 11 and 25, which are covered by homeowner's brick patio paving; MH 10, which is behind a small retaining wall under 1 to 2 feet of earth in the front yard of 1345 Barbara Worth Drive; and the most



extreme case of MH 29, which is under a small decorative wall and a wrought iron fence in the backyards of 2090/2092 Murray Drive.

As with the sewer mains, the manholes are also suffering from lack of regular maintenance. The interior surfaces of many of the manholes were originally lined with a bituminous coating. This coating has now largely flaked and peeled off to such a point that it is ineffective, exposing the concrete rings and cone to corrosion from hydrogen sulfide sewer gases. Many cases of concrete corrosion were observed in the field due to the trapped gas, high temperatures, and confined atmosphere. Many of the manhole troughs and shelves were deteriorating in a similar manner.



Typical concrete corrosion found within the cone of many of the CCSMD manholes. The concrete cone on the right should be smooth with no exposed aggregate, similar to the section below.

Rebar was observed in broken grade rings during the manhole inspections, indicating that the manhole rings and cones are precast reinforced concrete. As no exposed rebar or evidence of rebar corrosion was observed inside the manholes it is probable that all manholes inspected can be rehabilitated in place, as opposed to being completely replaced. Bureau Veritas recommends replacing and coating all manhole shelves, troughs, and rings internally with a corrosion resistant coating such as epoxy.

Manholes 8 and 15 had nonstandard channels that were originally constructed with such a tight angle that inspection and maintenance of the connecting sewer main is difficult to perform with modern equipment. These nonstandard angles also create increased flow resistance and increase the need for maintenance. Bureau Veritas recommends reforming the channels to reduce flow restrictions and improve accessibility for inspection and maintenance.

Other maintenance and repair issues include some damaged and/or detached manhole frames and covers (a few were replaced during the field work). These conditions pose a public safety concern and allow vandals to deposit debris in the system. A total of 21 manholes are recommended to be either raised (15) or have repairs made (6) to the frame and cover as a first order of work. Adjusting the buried manholes will make them accessible to perform other work needed on the system. Manholes with unsecured





frames should also be repaired.


At least four different sizes of manhole rings and covers were observed during the inspections. Bureau Veritas recommends using one standard size manhole frame and cover throughout the system. A standard size for manhole frames and covers increases maintenance efficiency and reduces storage of repair parts.

Manhole locations (northings and eastings) were collected with a Garmin Etrex Vista HCx handheld GPS unit with a <10 meter 95% degree of accuracy, and locations are considered approximate. We recommend surveying the location, rim, and invert elevations for all manholes in the system as one of the first orders of work in the rehabilitation of the system.

Photographs from the manhole inspections, such as those shown below, are included on compact disks in the rear pocket of this report, and the field manhole inspection logs are included as Appendix E.



Manhole 12 North



Manhole 28



Manhole 13



Manhole 9



MANHOLE (MH) SUMMARY

MH No.	Northing	Easting	Depth (ft)	Condition Issues
1	32° 48.231'	115° 25.371'	10.5	FC
2	32° 48.236'	115° 25.304'	10.5	FC
3	32° 48.242'	115° 25.234'	9.5	
4	32° 48.247'	115° 25.166'	10	FC
5	32° 48.237'	115° 25.166'	8	FC
6	32° 48.231'	115° 25.164'	Unknown	NI, BUR, ADJ
7	32° 48.188'	115° 25.151'	Unknown	NI, BUR, ADJ
8	32° 48.177'	115° 25.125'	5.5	CH
9	32° 48.185'	115° 25.098'	5	
10	32° 48.209'	115° 25.069'	Unknown	NI, BUR, ADJ
11	32° 48.167'	115° 25.147'	Unknown	NI, BUR, ADJ
12N	32° 48.132'	115° 25.091'	6	
12S	32° 48.110'	115° 25.059'	6	
13	32° 48.079'	115° 25.008'	9	FC, CGR
14	32° 48.037'	115° 24.944'	7	
15	32° 47.995'	115° 24.871'	6.5	ADJ, CH
16	32° 47.950'	115° 24.900'	6	
17	32° 47.964'	115° 24.913'	5	
18	32° 47.959'	115° 24.956'	4	ADJ
19	32° 47.925'	115° 24.895'	5.5	
20	32° 47.922'	115° 24.929'	5	
21	32° 47.881'	115° 24.890'	6	
22	32° 47.848'	115° 24.885'	5	
23	32° 48.002'	115° 24.858'	6.5	ADJ
24	32° 47.986'	115° 24.834'	6.5	ADJ
25	32° 47.928'	115° 24.838'	Unknown	NI, BUR, ADJ
26	32° 47.862'	115° 24.831'	4.5	ADJ
27	32° 47.800'	115° 24.834'	Unknown	NI, BUR, ADJ
28	32° 48.235'	115° 25.196'	8	CC, FC
29	Not Available	Not Available	Unknown	NI, BUR, ADJ
30	32° 48.140'	115° 25.284'	Unknown	NI, BUR, ADJ
31	Not Available	Not Available	Unknown	NF, NI, ADJ
32	32° 48.033'	115° 25.279'	6	
33	Not Available	Not Available	Unknown	NF, NI, ADJ

Manhole Condition Codes:

NF = Manhole Not Found
 BUR = Manhole Buried
 FC = Frame/Cover Needs Repair
 CGR = Replace Cone/Grade Rings

NI = Manhole Not Inspected
 CC = Concrete Corrosion
 CH = Manhole Channel Needs Repair
 ADJ = Adjust MH to grade





Pump Station Inspections

The inspection and evaluation of the pump station was performed by Carl Sepponen, PE, on September 25, with the assistance of John Burnworth of ICDPW. The Country Club pump station features duplex Gorman Rupp model T4A3-B suction-lift sewage pumps powered by two (2) 1740-RPM electrical motors with belt drives and controls housed in a fiberglass enclosure. From the information available, the current pumps and motors were installed as an upgrade in 2004 to a 1994 Gorman Rupp pump station. This is at least the second replacement pump system installed at this location since the pump station and wet well were originally constructed in 1974. The newer 2004 pumps continue to use the original wet well, inlet piping, force main, and electrical service.



Performance of pump station data collection and operational tests. The pump station was last upgraded in 2004 and was found to be in acceptable condition, with only minor modifications required.

The serial numbers of Pumps #1 and #2, respectively, are 1292436 and 1292435. The Pump Control Panel is drawing number D-4-02729, S/N 0-1502-AM. The panel is rated for 240-volt, 3-phase, 3-wire, 60-HZ. The sheaves (pulleys) on the motors are nine inches in diameter, and the sheaves on the pumps are 11 inches in diameter. Note that this data differs from that described in the operations and maintenance manual for the pumps installed in 1994, which was provided by ICDPW.

According to the Gorman-Rupp Pumps factory, the basic pumps were manufactured and shipped to Mexicali, Mexico, in 2004 for assembly with their motors and appurtenances. Further information was not available from the factory. Information regarding the pumps was requested from the Mexican factory in Mexicali, but it was not available. Precise information regarding the pump design point (flow and head) was not available. Further, the exact pump RPM is not known, but it can be estimated from other parameters. These motors and pumps are more powerful than previous units at the site, to the point that they may be contributing to distress and failures of the original force main, which was not upgraded.





The wet well consists of precast concrete manhole sections that are six feet in diameter. The condition of the wet well concrete is good to very good, considering it was originally installed in 1974. Substantial concrete corrosion from sulfuric acid is not evident from a visual inspection, although older embedded steel items are severely corroded. The concrete ground slab surrounding the wet well is in poor condition, and rebar is exposed in at least one location. Fortunately, this does not affect the functioning of the pump station. There is clear evidence of the original corroded metal embedded in the upper concrete slab. There is an opening on the east side of the wet well where the new fiberglass enclosure does not cover the original opening; it may be advisable to cover this opening with screen for safety reasons.

It is possible that the openings at the top of the wet well may be the principal reason that the wet well concrete is not badly corroded. The "natural" ventilation may prevent an accumulation of corrosive fumes, thereby preventing corrosion of the concrete. The other reason is that the sewage is relatively "fresh" and is not yet anaerobic, which reduces the corrosive effect.

The suction pipe of Pump #1 is shorter than the suction pipe of Pump #2. This was confirmed by the operator, who said that Pump #1 had its suction pipe replaced (date unknown). This is the likely reason the level control floats are set much higher than the inlet pipe, and why the sewage is always backed up in the collection system.

Based on the pump curves (Figure 1) it is assumed the motors run at a nominal 1760 RPM. The sheaves on the motors and pumps reduce the pump RPM to approximately 1450 or 1550 RPM (Figure 1).

Field measurements indicate the pump station delivers approximately 75 gallons per minute (gpm). However, inspection of the force main indicates the actual flow may be higher due to a relatively clean force main.




Figure 1: Gorman-Rupp T4A-B-4 Pump Performance Curve. Note the circled point on left side, which represents the operating point for the existing pumps and is outside the manufacturer's preferred operating range. Replacement of the force main with a six-inch pipeline would bring the curve back into the optimum operating range as indicated by the hand drawn curve.

The Sewer Study calculations (dated 3 October 2012, Appendix B) give the Average Dry Weather Flow as 0.02432 mgd (about 17 gpm), and the Peak Dry Weather Flow as 0.09728 mgd (about 68 gpm). Based on these calculations the pumps appear adequate for the flow from the development. This is verified by the fact that sewer overflows have not occurred when the pumps are able to operate.

The pumps are operating to the left side of the pump curve (Figure 1), in an area that is outside the operating range recommended by the manufacturer. This occurrence usually results in discharge cavitation, which can adversely affect the pump impeller and its performance. Cavitation issues can be corrected by increasing the flow rate, which could be accomplished by increasing the force main size, thereby lowering the friction head loss in the pipeline.





ICDPW's operator indicated that Pump #2 functions better than Pump #1. The Gorman-Rupp factory engineers strongly recommend that the pump impellers and wear plates be adjusted by factory technicians at least once a year to assure good performance.

The pump station does not have emergency power at the site and is at risk of overflow if there is an extended power outage.

Photographs from the pump station inspection are included on compact disks in the rear pocket of this report.

Comparison with Previous Pump Station Studies

Previous studies have been prepared to evaluate the Barbara Worth pump station and force main. The following discussion is a comparison of the recommendations of this evaluation with the recommendations of two previous reports, both of which are attached to the *Country Club Sewer Maintenance District Informational Report* (June 2006). The two previous reports are:

- *The Master Plan of Sewer* (1998) by Kennedy Jenks Consultants (KJC)
- *2006 Barbara Worth Wastewater Force Main Installation and Sanitary Sewer Pump Station Replacement Report* by the Holt Group, Inc.

The Master Plan of Sewer (1998) by KJC presents a sewer plan for the year 2020, including future development. The following text is a summary of the KJC report that is in the *District Informational Report*:

"The report concluded that the Barbara Worth Pump Station and its force main are undersized and recommends increasing the 4-inch sewer force main pipe to an 8-inch pipeline to accommodate the existing demands placed on the system within the current boundaries of the CCSMD."

There is no detailed evaluation of the Barbara Worth Pump Station included in the KJC report. The pump station is assumed to have a 400 gpm existing capacity per available information (source not given) and 750 gpm is required for future development.

Immediately after addressing the Barbara Worth pump station deficiencies, the report includes the following disclaimer on page 5.5:

"It should be noted that since actual pump operating capacities and wastewater flows were not provided, these results are based on several assumed or simulated conditions. Although, these results provide an indication of probable deficiencies, actual field measurements and testing should be conducted prior to final remedial design."





The 2006 report by the Holt Group recommended replacing the existing 4-inch sanitary sewer pipeline with a 10-inch force main in order to facilitate future development and expansion. The following excerpt is from pages 6 and 7 of that report:

"In this report the Holt Group, Inc. concluded that during the last 10-years the existing wastewater pump station has continued to deteriorate and periodically fail. The maintenance cost, time and effort devoted to keep the pump station in a working condition is significant and far in excess of what is normally required. It is apparent that the Pump Station has exhausted its useful life and should be replaced as soon as possible. The physical P.C.C. wet well structure is deteriorated and at the point of collapse. The wet well is no longer salvageable. The electrical panels and pumping units are also aged, outdated, inefficient and in a deteriorated condition. The replacement of the existing 4-inch diameter force main with a 10-inch diameter force main would allow for the installation of the wastewater pumps at a lower total dynamic head requiring less energy to operate. The pumps would produce a greater flow at less total dynamic head (and pressure) resulting in less maintenance. The electrical costs associated with the wastewater pump station would decrease even though the flow capability of the pump station would be dramatically increased (from 400-gallons per minute to 750-gallons per minute).

The 10,200 lineal foot wastewater force main extending downstream of the Pump Station has been a source of pipeline ruptures, pipeline clogs, and pump maintenance problems for over 2 decades. The continued rupturing of the 4-inch wastewater force main results in health and safety issues in the vicinity of the Imperial Irrigation District Canal Network. It would be prudent for Imperial County to replace the existing undersized 4-inch diameter force main with a heavy wall 10-inch diameter AWWA C-900, Class 150 PVC wastewater force main as soon as possible."

The 2006 Holt Group report indicates the pump flow rate was not checked in the field or with the operator. Rather, that report took information directly from the 1998 KJC report (which is unsupported). There is no record of pump serial numbers. No contact with the pump manufacturer is mentioned, there is no pump curve in the report, and no system curves are provided.

In conclusion, all the reports recommend the force main be replaced with a larger size force main. We recommend a 6-inch pipe, the KJC report recommended an 8-inch pipe, and the Holt Group recommended a 10-inch pipe to provide for future development. Our analysis indicates that six inches is the optimum pipe size. It provides a large increase in capacity, allows the pumps to function much more efficiently, and will reduce the risk of force main ruptures in the future.

Our report recommends only minor improvements to the pump station, whereas the Holt Group report recommended the installation of a new pump station. Note that the



Holt Group considered additional flow from future development, which our report does not include. The consideration of additional flow is one of the main reasons the Holt Group's report recommends a new pump station. The Holt Group report concluded the wet well was in such poor condition that it should be replaced. Our recommendations are based on a significantly more thorough analysis than those of the Holt Group. It should be noted that although the pump station and the wet well are not in fine or new condition and have some deficiencies, they are adequate for current needs if the force main is upgraded and some other minor improvements are made.

Our recommendations are based a detailed analysis of the present conditions, whereas the previous reports spent little or no effort in researching the actual pump station condition or gathering field data. No detailed analysis was conducted by KJC or by the Holt Group on the pump station, although some head loss calculations were prepared to show that the existing 4-inch force main is inadequate.





Force Main Inspection

Initial inspection and evaluation of the sewer force main was conducted by Philip Kern, PE, with the assistance of Carl Sepponen, PE, and Affordable Pipeline Services staff on September 25, 2012. One of the main challenges of evaluating the condition of the existing force main is, quite simply, accessibility. Without physically excavating and cutting the existing force main there are only four points at which to inspect the interior of this small diameter pipeline: the force main at the pump station, the discharge manhole at Kamm Road and Gowling Road, and two



Initial video inspection of the force main with a push camera. Pump station is on the left and force main is on the right. Note the sharp 90-degree bend in the force main next to the fence.

cleanouts located on either side of the Alamo River. Neither ICDPW nor Bureau Veritas staffs were able to confirm location of the cleanouts at the Alamo River. Further, the four-inch diameter pipeline is too small to admit a tractor camera for inspection.

These conditions limited the initial inspection opportunities to the use of a small specialized "push camera" inserted from either end of the force main. On September 25 a trailer jetter was used at the Kamm Road manhole to drag the push camera into the main, with video data collected as the camera was withdrawn from the main. The crew discovered that the force main was not constructed on a straight grade as indicated on the plans but rather "porpoises" up and down with high and low spots in the profile. These high and low spots prevent full draining of the line as well as clear visibility for inspection. The



Second video inspection of the force main along Barbara Worth Drain, pump station is in the left background. The end of the pipeline can be seen in the trench, one line in the pipe is the video cable, the other is the jetter line used to pull the camera into the pipe.



portions of this section of force main which were visible on the video appeared to be in good condition, and no ruptures have been reported near the north end.

Unfortunately, two sharp 90-degree bends on the pump station discharge line prevented insertion of the push camera and jetter any significant distance into the south portion of the force main during the September 25 inspection, even with removal of a section of the discharge line at the pump station. ICDPW staff has reported three ruptures in recent memory of the force main in this section of the pipeline so it was a priority for inspection. A small washout about 200 feet north of the pump station along Barbara Worth Drain was reportedly the location of the last pipeline failure. The short distance that was able to be inspected showed a fairly thick slime coating on the interior of the pipe, which masked details of the condition of the PVC pipeline.

At the request of the Director of ICDPW, the crew returned to the site on October 25. ICDPW crews excavated and removed an eight foot section of the force main approximately 200 feet north of the pump station and the Affordable Pipeline Services crew inserted a push camera, again using the trailer jetter to draw it into the pipeline. The pipeline was accessed 308 feet to the north and 178 feet to the south toward the pump station. The results were similar to the previous inspection in that the force main was not installed on a grade and would not fully drain. As a result, the camera was submerged for much of the time and the interior of the pipeline could not be seen clearly. The portions that were visible appeared to be in good condition, with some debris noted in the pipeline and the slime coating appearing to diminish as the camera traveled further from the pump station.

The eight-foot portion of the pipe that was excavated and removed was particularly instructive. This section contained a repair coupling where a previous break had been repaired; had a 4-inch to 6-inch lengthwise crack on the spigot end where it would normally be protected by the bell end of the next section of pipe; and also exhibited some splintering from damage incurred by the backhoe when it was removed, which is unusual for PVC pipe. The force main pipe was inscribed with the following description: *4" J-M Ring-Tite PVC 1120 IPS 125 PSI SDR 32.5 ASTM D-2241*. By current standards this is relatively thin-wall, light-duty pressure pipe that would be considered marginally acceptable for this application. No sand bedding, tracer wire, or warning tape was observed within the excavation, which is not consistent with current public works standards. Further, there is no information available regarding compaction of the trench backfill. PVC pipe, being a flexible pipe, is particularly sensitive to the type and compaction of the bedding and backfill as it uses these elements to resist internal forces. Use of uncontrolled and/or poorly compacted native material for bedding can create stress points along the pipeline, which can lead to pipe failures. Stress points can



be even more of a concern on a force main which experiences pressure spikes due to pump operations, as opposed to a gravity-fed water supply main which would normally see consistent pressure levels. PVC pipe is also sensitive to ultraviolet (UV) radiation if installed or stored outdoors for extended periods without protection. Older, above-ground sections of pipe at the pump station had some indications of UV degradation, although it is not known if UV exposure contributed to the cracking or splintering of the force main sections that were inspected. It is more likely that the crack was caused by rough handling of the pipe at the time of installation.



Existing 4-inch force main pipe removed from the trench. Note the splintered section on the left, repair coupling in the middle, and the barely visible chip and crack in the spigot end of the shorter section on the right.

The force main pipe was found to be a JM Eagle brand I.P.S. Pressure PVC Pipe conforming to ASTM D2241 for standard dimension ratios (SDRs). It is available in varying strengths, including SDR 64 (63 psi), SDR 41 (100 psi), SDR 32.5 (125 psi), SDR 26 (160 psi), SDR 21 (200 psi), and SDR 17 (250 psi). This force main is a SDR 32.5 (125 psi pressure rating) pipe with an internal diameter of 4.207 inches. For comparison, 4-inch PVC Schedule 40 has an ID of 4.026 inches (maximum working pressure of 220 psi), and Schedule 80 has an ID of 3.826 inches (maximum working pressure of 320 psi). The 4-inch ductile iron pipe (DIP) inside the Gorman-Rupp pump station has a nominal pressure rating of 350 psi.

There are several reasons why the force main may be breaking and leaking:

- **The line is operating at a pressure higher than the original design.** The pumps installed in 1994 were design for 200 gpm at just 21 feet of head according to the operations and maintenance (O&M) manual. The pumps installed in 2004 have a much high rpm and produce a higher pressure. A higher pressure, combined with any of the factors listed above, can lead to breaks.
- **Pressure surges are occurring when the pumps stop.** Each time the pumps start and stop, but especially when they stop, a pressure surge occurs





that increases the pressure in the pipeline.

- **High temperature of the water and / or soil may be reducing the strength of the PVC.** High temperature decreases the strength and therefore the pressure rating of the pipe as follows:

Temperature (°F)	De-Rating Factor
73	1.00
80	0.88
90	0.75
100	0.62
110	0.51
120	0.40
130	0.31
140	0.22

For example, if the PVC temperature is 90 degrees, the pressure rating is decreased from 125 psi to 94 psi. Given the ambient temperatures in the summer months in the Imperial Valley, the force main pipe could be at 50 to 75 percent of its rated strength.

- **Poor installation may have caused breaks.** Poor installation can stress a PVC pipe and create a weak point and eventually the pipe may break under high pressure.
- **Storage in sunlight prior to installation may have caused the PVC to become brittle.** It is well known that PVC pipe should be stored away from sunlight prior to installation. The UV rays affect the chemical structure of the PVC and it can become brittle and can easily be shattered and broken. PVC pipe is usually stored in bundles, and only some of the pipe lengths are subject to high UV exposure. Those subject to the high UV exposure are the ones most likely to break.

Video data from the force main inspection are included on compact disks in the rear pocket of this report, and inspection logs from the force main inspection are included as Appendix F.





Conclusions and Recommendations

The following recommendations are based on analysis of data collected in the field and through research of available documentation. Although much of this work could be performed by ICDPW forces, the repair cost estimates in Appendix D presume that these tasks would be accomplished by outside contractors. As the entire CCSMD system has not yet been inspected, allowances and contingencies have been made in the estimate. These costs are considered preliminary in nature and suitable for planning purposes only.

Pipelines

The principal issue with the gravity pipelines is their very flat slope, which will require regular long-term maintenance to effectively function. It is not considered economical to replace the entire collection system to remedy this issue. Other than implementation of a long-term regular maintenance plan, the following capital repairs are recommended:

- Locate remaining sewer mains and manholes
- Complete cleaning of all pipelines with Vector truck
- Complete inspection of all pipelines
- Perform spot repairs on root intrusions
- Install grease traps on commercial laterals
- Inform residents of pipeline location and remove trees over pipelines
- Replace sag portions of pipe at the proper grade
- Replace undersized mains with 8-inch pipe
- Replace pipelines with horizontal bends
- Replace drop manhole plumbing

Manholes

The lower portions of existing manholes were found to be in generally good condition. Capital repairs for manholes are focused on providing access for maintenance and repairing or replacing deteriorated items in the upper portions.

- Survey manhole locations, rim, and invert elevations to establish grades
- Adjust to grade and secure manhole frame and covers, replace with standard frame and cover if necessary
- Modify utilities, irrigation lines, paving and structures which are obstructing manhole openings



- Rechannel manhole troughs for proper flow, inspection and maintenance access
- Replace corroded manhole cones with new T-lock or epoxy-coated cones
- Remove steps and coat interior, trough, and shelf of all manholes with T-Lock or epoxy coating

Pump Station

The pump station was found to be in acceptable condition with adequate capacity. The 8-year old pumps do not need to be replaced, although some of the following observations and recommendations are important to improve pump performance and life expectancy.

- The Pump #1 suction pipe should be replaced with a longer pipe to match that of Pump #2, and the level control floats should be set much lower so that the collection system pipes drain during every pumping cycle. The start level can be set several feet above the inlet pipe, but the stop point should be set below the inlet pipe level. These changes will improve the collection system capability and reduce the amount of sediment in the collection system. Although it is best to have both the start and stop levels below the inlet pipe, it is not always possible. In this case the floats are located not much below the inlet pipe, and the suction-lift pumps function better when the start level is not set too low.
- Some of the gauges need to be replaced. Each pump should have two working pressure gauges - one gauge on the discharge side and one gauge on the suction side of the pump. Having two gauges is the best way to quickly evaluate any pump problems that may occur.
- The pump impellers should be inspected and adjusted by a factory technician annually (or at least every two years; the official Gorman-Rupp recommendation is to have the pumps checked every six months). Gorman-Rupp should be contacted to conduct this service.
- The concrete wet well does not need to be replaced, although epoxy lining the wet well for longevity is recommended.
- Although the concrete base slab around the wet well is in poor condition, replacement is not critical. If its condition interferes with the operator's work at the station, it is recommended that the concrete base slab be replaced. The replacement cost is not high and could be easily accomplished.



- The pump station should have some means of functioning during a prolonged power outage. If not already provided, it is recommended that the electric service be configured for connection to a portable generator, and a portable generator be purchased or a standby rental agreement be made with a local company.
- Install screen across wet well opening(s)

Force Main

The force main has been problematic in the past and has had several failures. In addition to being undersized, the pipe strength is marginal for this application and it was not installed to current standards. The following recommendations are suggested:

- Replace the existing 10,000 feet force main with a stronger and larger pipeline. It is recommended the force main be replaced with a 6-inch PVC pipe with a higher pressure rating and to current standards, such as a minimum of AWWA C-900 Class 150. The AWWA C-900 pipe has higher safety factor than the IPS pipe presently installed.

In addition to the higher safety factor, increasing the pipeline size and reducing the friction headloss is recommended to increase the pump flow rate and move the operating point near or into the recommended operating range. This will eliminate impeller cavitation. As shown in Appendix A, the plot on the pump curve shows an operating point of 260 gpm at 60 feet TDH. The pipeline velocity is 2.8 fps, well above the recommended minimum of 2.0 fps.

As an alternative to replacing the entire force main, the section under the Alamo River could be left in place. However, if there is a history of pipeline breaks in this section under or near the Alamo River, this alternate approach is not advisable because it may cause additional pipeline breaks.

- Replace sharp 90 degree bends in force main at pump station with larger radius bends
- Install cleanouts at regular intervals for inspection and maintenance



References

1. *Plans for Interceptor Sewer, City of Holtville*, prepared by Wilsey & Ham, Sheets 1-5, approved May 21, 1974
2. *Plans for Improvements, Tract No. 839*, prepared by The Parker-Riddle Co., sheets 1-4, approved May 23, 1978

Credits

The following personnel contributed to the data collection, field investigations and development of this report:

Imperial County Department of Public Works
John Burnworth
David Krommenhoek
Martin Lang
Affordable Pipeline Services
Duane Johnson, Supervisor
Nick Provencio, Camera Operator
Mark Enrique, Video Assistant
Bureau Veritas
Bill Grigsby, PE, Manhole Evaluation
Carl Sepponen, PE, Pump Station and Force Main Evaluation
Steve Dodge, Graphics
Ruth Licht, Report Preparation
Philip Kern, PE, Project Manager





Appendix A

Pump Station and Force Main Calculations



Pump Station and Force Main Calculations

Pump Speed (RPM)

The Pump RPM can be calculated by knowing the motor RPM and diameter of the sheaves (pulleys):

Motor RPM = approximately 1760 RPM

Motor sheave diameter = 9.0 inches

Pump sheave diameter = 11.0 inches

Pump Speed = Motor RPM x (Motor sheave diameter / Pump sheave diameter)

$$= 1760 \text{ RPM} \times (9.0" / 11.0")$$

$$= 1440 \text{ RPM, say } 1450 \text{ RPM (which is shown on the Gorman-Rupp pump curves)}$$

System Curves (to graph on pump flow vs. head chart)

The force main is mainly 4-inch J-M Ring-Tile PVC 1120 IPS 125 PSI SDR 32.5 ASTM D-2241, and the piping at the pump station is 4-inch Ductile Iron Pipe (DIP). The internal diameter of the PVC pipe is 4.207 inches according to the manufacturer's data. The internal diameter of the DIP is 4.15 inches, but the difference will be ignored. Since the length of the DIP is insignificant compared to the long PVC force main, the entire force main will be assumed to have an internal diameter of 4.207 inches.

The length of the force main is 9,440 feet. Adding 523 feet for station equation equals 9,963 feet.

Equivalent lengths are calculated for the minor losses and added to the actual force main length for the following head loss calculations:

Item	Number	Equivalent Length (Ft) Each	Total Equiv. Length (Ft)
90° bend	5 + 4 = 9	13	117
45° bend (or less than 90°)	6	5	30
Plug valve	1	10	10
Tee (run)	3	8	24
Tee (branch flow)	1	22	22
Total Head Loss Lengths			203





Total Equivalent Length = 9,963 feet + 203 feet = 10,166 feet

Prepare System Curves for C = 140, C = 110, and C = 80 for comparison

Static Head

Ground elevation at pump station from plans is approximately 945.0 feet

The force main discharge elevation is given as 933.70 feet

The distance from the pump station ground elevation to the water levels during pumping varies from approximately 82 to 116 inches (or elevations 938.2 feet to 935.3 feet)

Therefore, the static lift varies from minus 4.5 feet to minus 1.6 feet (the discharge is lower than the wet well level). Alternatively, the static lift is -3 feet, ±1.5 feet.

Calculate Headloss and Total Dynamic Head (TDH) for various flows at 3 "C" values using Hazen-Williams equation

$$\text{Friction loss} = ((0.2083 \times (100/C)^{1.852} \times (\text{flow})^{1.852}) / (\text{diameter})^{4.8655})$$

Diameter = 4.207 inches in all cases

C = 140			
Flow (gpm)	Headloss (ft/100 ft)	Headloss (feet)	Total Dynamic Head (feet)
0	0	0	-3
50	0.144	15	12
100	0.520	53	50
150	1.10	112	109

C = 110			
Flow (gpm)	Headloss (ft/100 ft)	Headloss (feet)	Total Dynamic Head (feet)
0	0	0	-3
50	0.225	23	20
100	0.81	82	79
150	1.72	175	172





C = 80			
Flow (gpm)	Headloss (ft/100 ft)	Headloss (feet)	Total Dynamic Head (feet)
0	0	0	-3
50	0.406	41	38
100	1.466	149	146
150	3.107	316	313

The calculated TDH / flow points are plotted on the pump curve as shown on the next page. The 3-system curves are labeled for each of the "C" values.

Operating Point

During the field investigation the flow and head was estimated as follows:

The wet well was pumped down to below the inlet pipe using Pump #2. The wet well depth was observed and recorded over an 11-minute period and averaged 13.3 gpm. The drawdown was observed for several minutes and recorded after the pump started; the pumping rate was 61.6 gpm. Then the average inflow was added to the observed pumping rate to account for the sewage coming into the wet well while the pump was running.

The pumping rate was = $61.6 \text{ gpm} + 13.3 \text{ gpm} = 74.9 \text{ gpm}$, say 75 gpm

The pumps usually operate at a pressure of 26 to 28 psi (60 to 65 feet), which is taken at the top of the pumps, about 3 feet above the pump station ground slab. To get the TDH the distance from the pressure gauge to the water level below is added to the pressure reading:

$\text{TDH} = 62 \text{ feet} + 3 \text{ feet} + 14 \text{ feet} = 79 \text{ feet}$ at flow of 75 gpm – This point is also plotted on the pump / system curves.

Conclusions from the graph

Looking at the graph it appears the pump is likely running at 1550 rpm (not 1450 rpm as calculated above). But other field readings and / or measurements could be in error, so the actual value of the pump rpm is uncertain.

One can see that the system is running at a "C" value of approximately 90.





Force Main Velocity

The velocity in the force main at different flows is:

At 50 gpm = 1.15 fps

At 100 gpm = 2.31 fps

At 150 gpm = 3.46 fps

The velocity of the sewage in the force main with a flow of 75 gpm is only 1.7 fps, which is below the recommended minimum of 2.0 fps to maintain sewage solids in suspension.

Calculation of Flow and TDH for Proposed 6-Inch Force Main

Assume a new 6-inch PVC force main with ID = 6.13 inches

C = 120

Flow (Gpm)	Headloss (Ft/100 Ft)	Headloss (Feet)	Total Dynamic Head (Feet)
0	0	0	-3
50	0.031	3	0
100	0.111	11.4	8
150	0.235	24	21
200	.40	41	38
300	0.848	86	83

The plot on the pump curve shows an operating point of 260 gpm at 60 feet TDH. The pipeline velocity is 2.8 fps, well above the recommended minimum of 2.0 fps.



Appendix B

CCSMD Sewer Study



Project: 38422.00
 By: D. Isaac

Country Club Sewer Maintenance District
 Sewer Study

Sheet: 3 of 3
 Date: 9-Oct-12

Line	From	To	Popul. per DI	In Svc ODs	Popul. in Line	Popul. Contribution	Average Per Capita/Day (gpd)	Average Dry Weather Flow (mgd)	Peaking Factor	Peak Dry Weather Flow (mgd)	Line Size, D (in)	Design Slope, % (ft/ft)	Normal Depth, dn (ft)	% Full dn/D	Flow Velocity (ft/s)
1	MH 27	MH 25	10	34	19	72	85	0.00176	4.0	0.00304	8	0.25	0.32	17%	0.75
2	MH 22	MH 15	300	34	36	36	90	0.00190	4.0	0.00355	8	0.25	0.55	17%	1.04
3	MH 15	MH 7	10	0	0	175	90	0.01888	4.0	0.00472	8	0.25	0.00	0%	1.43
4	MH 10	MH 7	30	14	43	42	85	0.00134	4.0	0.00244	8	0.25	1.00	17%	0.80
5	MH 7	MH 1	30	0	0	113	90	0.01706	4.0	0.00316	8	0.25	0.26	0%	1.50
6	MH 15	MH 2	10	27	31	31	90	0.00718	4.0	0.01413	8	0.25	1.48	17%	1.01
7	MH 5	MH 1	30	0	0	344	90	0.02422	4.0	0.00718	8	0.25	0.72	14%	1.43

Notes:

1. Assume 50% drop-out on Amdurville Rd., all drop-outs on Country Club Drive, 100% for WACC
2. Line size and design slopes assumed pending completion of survey
3. Generation rate and peaking factors per City of SD Sewer Design Guide
4. Manning's n=0.013 for all lines

23





Appendix C

CCSMD System Map



Regional Water Resources Agency, Inc.
 10000 Central Expressway, Suite 100
 San Jose, CA 95131
 Tel: 408.264.8700 Fax: 408.264.8701
 www.rwra.org





Appendix D

Repair Cost Estimate





**COUNTRY CLUB SEWER MAINTENANCE DISTRICT
PRELIMINARY REPAIR COST OPINION**

Item Description	Quantity	Unit	Unit Cost	Total Cost
PIPELINES				
Locate Sewer Mains and MHs	1	LS	\$5,000	\$5,000
Clean Sewer Mains	5	Days	\$3,000	\$15,000
Inspect Sewer Mains	3	Days	\$2,500	\$7,500
Spot Repairs (Root Intrusions, etc.)	4	Each	\$5,000	\$20,000
Install Grease Trap	1	Each	\$5,000	\$5,000
Inform Residents of Sewer Locations	1	LS	\$5,000	\$5,000
Replace Sag Portions of 8" sewer to grade	2,000	LF	\$100	\$200,000
Replace 4" VCP with 8" PVC	500	LF	\$100	\$50,000
Replace 8" VCP Bends with 8" PVC pipe	200	LF	\$100	\$20,000
Replace drop MH plumbing	1	EA	\$5,000	\$5,000
MANHOLES				
Survey Manhole Locations	1	LS	\$7,500	\$7,500
Adjust MH to grade, replace frame and cover	17	EA	\$2,000	\$34,000
Modify Private Facilities Obstructing Manholes	1	LS	\$100,000	\$100,000
Rechannel MH Troughs	4	EA	\$2,500	\$10,000
Replace MH Cone	30	EA	\$4,000	\$120,000
Line Interior of MH with Epoxy	34	EA	\$2,000	\$68,000
PUMP STATION				
Reset Float Switch Levels	1	LS	\$1,000	\$1,000
Extend Suction Line for Pump #2	1	LS	\$3,000	\$3,000
Install Screen on Wet Well Opening	1	LS	\$1,000	\$1,000
Line Wet Well with Epoxy Coating	1	LS	\$10,000	\$10,000
FORCE MAIN				
Locate Existing Cleanouts	1	LS	\$2,500	\$2,500
Replace Sharp Bends at Pump Station	1	LS	\$5,000	\$5,000
Install Force Main Cleanouts	20	EA	\$2,000	\$40,000
Replace 4" PVC with 6" PVC force main	10,000	LF	\$50	\$500,000
Subtotal Construction				\$1,234,500
Construction Contingency	20%			\$246,900
Administration & Design	15%			\$185,175
GRAND TOTAL				\$1,666,575





Appendix E

Manhole Inspection Logs

MANHOLE INSPECTION REPORT

DATE: 9-25-12

MANHOLE #: 1 STREET: Barbara Worth Drive
 WEATHER: 4 windy hot INSPECTOR(S): ASL

MANHOLE COVER

DIAMETER: 27 INCHES
 NO. OF HOLES IN COVER: 1
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: 3 INCHES

STEPS


CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: 15 INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: 2 GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE	
	FROM MH # <u>2</u>	FROM MH # _____	FROM MH # _____	TO MH # _____	
DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>		
DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT
TYPE					
DIAMETER					
FLOW					

COMMENTS:

manhole cover odd size

MANHOLE INSPECTION REPORT

MANHOLE #: 2 STREET: Barka Worth Blvd DATE: 9-24-12
 WEATHER: Hot sunny INSPECTOR(S): Joe

MANHOLE COVER

DIAMETER: ~~30~~ ³² INCHES
 NO. OF HOLES IN COVER: 1 *Nov*
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: 1" INCHES

STEPS


CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: 4" INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: 2 GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE	
	FROM MH # <u>3</u> DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	TO MH # _____ DISTANCE _____ FT	
TYPE					
DIAMETER					
FLOW					

COMMENTS:

MANHOLE INSPECTION REPORT

MANHOLE #: A STREET: Barbra Worth Drive DATE: 9-24-12
 WEATHER: Hot Sunny INSPECTOR(S): DLB

MANHOLE COVER

DIAMETER: 24 INCHES
 NO. OF HOLES IN COVER: 1
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

25.5" Frame not lined up with rings

Surcharged 6:00 pm 24th

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS


CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: 6" INCHES

STEPS

CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO



TYPICAL MANHOLE

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: 4 INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: Trickle GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE	
	FROM MH # <u>5</u>	FROM MH # _____	FROM MH # _____	TO MH # _____	TO MH # _____
DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>
DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT
TYPE					
DIAMETER					
FLOW					

COMMENTS: 10" pvc in & out



1. The first part of the document discusses the importance of maintaining accurate records of all transactions. This is essential for ensuring the integrity of the financial statements and for providing a clear audit trail.

2. The second part of the document outlines the various methods used to collect and analyze data. These methods include interviews, surveys, and focus groups, each of which has its own strengths and limitations.

3. The third part of the document describes the process of data analysis. This involves identifying patterns and trends in the data, as well as testing hypotheses and drawing conclusions.

4. The fourth part of the document discusses the importance of communication in the research process. This involves sharing findings with stakeholders and presenting results in a clear and concise manner.

5. The fifth part of the document concludes by emphasizing the need for ongoing evaluation and improvement of the research process. This ensures that the research remains relevant and effective over time.

6. The sixth part of the document provides a summary of the key findings and recommendations. This is intended to provide a clear and concise overview of the research results.

7. The seventh part of the document discusses the implications of the research findings. This involves considering the broader context of the research and the potential impact of the findings on practice.

8. The eighth part of the document provides a list of references. This is intended to provide a clear and concise overview of the research results.

Author	Title	Year
Smith, J.	Research Methods in Business	2010
Johnson, M.	Qualitative Research in Organizations	2012
Williams, K.	Quantitative Research in Business	2015
Brown, L.	Research Ethics in Business	2018
Green, P.	Research Design in Business	2020





[Redacted text block]

[Redacted text block]

[Redacted text block]

THE HISTORY OF THE

REIGN OF KING CHARLES THE FIRST



BY JOHN BURNET

IN TWO VOLUMES

LONDON, Printed by J. Sturges, at the Black-Swan in St. Dunstons Church-yard, 1724.


—

The first part of the document discusses the importance of maintaining accurate records of all transactions. It emphasizes that every entry should be supported by a valid receipt or invoice. This ensures transparency and allows for easy verification of the data.

In addition, it is crucial to review the records regularly to identify any discrepancies or errors. This proactive approach helps in catching mistakes early and prevents them from escalating into larger issues. Consistent monitoring also aids in understanding the overall financial health of the organization.

Furthermore, the document highlights the need for secure storage of all financial documents. Implementing robust security measures, such as encryption and access controls, is essential to protect sensitive information from unauthorized access or data breaches.

Finally, the document concludes by stating that maintaining accurate and secure financial records is not just a legal requirement, but also a key to long-term business success and growth.



This section provides a detailed overview of the current market conditions and the impact of recent regulatory changes. It analyzes the trends in consumer behavior and the challenges faced by various industry sectors.

The following table summarizes the key findings:


MANHOLE INSPECTION REPORT

MANHOLE #: 11 STREET: GOLF Course DATE: 9-29
 WEATHER: Sunny Hot INSPECTOR(S): BJB

MANHOLE COVER

DIAMETER: _____ INCHES
 NO. OF HOLES IN COVER: _____
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MH Found & Buried



TYPICAL MANHOLE

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: _____ INCHES

STEPS

CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: _____ INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: _____ GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE
	FROM MH # _____	FROM MH # _____	FROM MH # _____	TO MH # _____
	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	
TYPE	DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT
DIAMETER				
FLOW				

COMMENTS:

MANHOLE INSPECTION REPORT

MANHOLE #: 12 STREET: Golf Course DATE: 9-25
 WEATHER: flat sunny INSPECTOR(S): [Signature]

MANHOLE COVER

DIAMETER: 24 INCHES
 NO. OF HOLES IN COVER: 1
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: 2" INCHES

STEPS


CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: 2" INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: 1 GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE
	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	TO MH # _____ DISTANCE _____ FT
TYPE				
DIAMETER				
FLOW				

COMMENTS: To MH 11

50th

2nd MANHOLE INSPECTION REPORT

DATE: 9-25-12

MANHOLE #: 12 STREET: Golf Course WEATHER: Hot sunny INSPECTOR(S): B/S

MANHOLE COVER

DIAMETER: 24 INCHES NO. OF HOLES IN COVER: 1 CONDITION OF FIT: LOOSE [] TIGHT [x] SEALED [] BOLTED [] EVIDENCE OF LEAKAGE: YES [] NO [x]

MANHOLE FRAME

CONDITION: SOUND [x] BROKEN [] EVIDENCE OF LEAKAGE: YES [] NO [x]

CORBEL AND WALLS

CONSTRUCTION: PRECAST [x] BRICK [] CONDITION: GOOD [] DETERIORATING [x] EVIDENCE OF LEAKAGE: YES [] NO []

BENCH WALLS

CONDITION: GOOD [] DETERIORATING [x] DEPOSITS: MUD [x] DEBRIS [] SLUDGE [] DEPTH OF DEPOSITS: 1.5 INCHES

STEPS


CONDITION: GOOD [] DETERIORATING [x] EVIDENCE OF DEBRIS ON STEPS: YES [] NO [x]

TROUGH

CONDITION: GOOD [] DETERIORATING [x] EVIDENCE OF LEAKAGE: YES [] NO [x]

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES [] NO [x] EVIDENCE OF SURCHARGING: YES [] NO [x] INCHES ABOVE INVERT: 2 INCHES EVIDENCE OF INFILTRATION: YES [] NO [x] ESTIMATED FLOW RATE: 1 GPM LOCATION/DESCRIPTION OF INFILTRATION:



TYPICAL MANHOLE

Table with columns for PIPE ENTRANCE DATA, INCOMING LINES (FROM MH # 13, FROM MH # 12), and OUTGOING LINE (TO MH #). Rows include TYPE, DIAMETER, and FLOW.

COMMENTS:

2nd # 12 found in Field appears to match map for 12

MANHOLE INSPECTION REPORT

MANHOLE #: 13 STREET: Golf Course DATE: 1-25
 WEATHER: sunny INSPECTOR(S): awb

MANHOLE COVER

DIAMETER: 41 INCHES
 NO. OF HOLES IN COVER: 1
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: 1 INCHES

STEPS


CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: 3 INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: 1 GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE	
	FROM MH # <u>14</u>	FROM MH # _____	FROM MH # _____	TO MH # _____	
DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>		
DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT
TYPE _____					
DIAMETER _____					
FLOW _____					

COMMENTS: To 12 south

MANHOLE INSPECTION REPORT

MANHOLE #: 14 STREET: GOLF COURSE DATE: 9-25
 WEATHER: hot sunny INSPECTOR(S): ams

MANHOLE COVER

DIAMETER: 24 INCHES
 NO. OF HOLES IN COVER: 1
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME *corroded*

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO *7*

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: 1 INCHES

STEPS


CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: 2 INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: 2 GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE
	FROM MH # <u>13</u> DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # <u>13</u> DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	TO MH # _____ DISTANCE _____ FT
TYPE				
DIAMETER				
FLOW				

COMMENTS:

MANHOLE INSPECTION REPORT

MANHOLE #: 15 STREET: Fairway DATE: 9-24-12
 WEATHER: evening INSPECTOR(S): AS

MANHOLE COVER

DIAMETER: 24 INCHES
 NO. OF HOLES IN COVER: 1
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO *Corroded*

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: 2 INCHES

STEPS


CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: 4 INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: _____ GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE
	FROM MH # <u>10</u>	FROM MH # <u>27</u>	FROM MH # _____	TO MH # _____
DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	
DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT	DISTANCE _____ FT
TYPE				
DIAMETER				
FLOW				

COMMENTS:

MANHOLE INSPECTION REPORT

DATE: 9-24-12

MANHOLE #: 17 STREET: Vista Verde
 WEATHER: evening INSPECTOR(S): [Signature]

MANHOLE COVER

DIAMETER: 27 INCHES
 NO. OF HOLES IN COVER: 4
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: 2 INCHES

STEPS


CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF BURCHARGING: YES NO
 INCHES ABOVE INVERT: 2 INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: _____ GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE	
	FROM MH # <u>16</u> DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	TO MH # _____	DISTANCE _____ FT
TYPE	<u>Clay</u>				
DIAMETER					
FLOW					

COMMENTS:

MANHOLE INSPECTION REPORT

MANHOLE #: 14 STREET: Vista Verde DATE: 9-24-12
 WEATHER: Evening INSPECTOR(S): M/S

MANHOLE COVER

DIAMETER: 27 INCHES
 NO. OF HOLES IN COVER: 1
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: 3 1/2 INCHES
Heavy deposit blocking

STEPS


CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: .25 INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: Trickle GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE	
	FROM MH #	FROM MH #	FROM MH #	TO MH #	
DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>		
DISTANCE FT	DISTANCE FT	DISTANCE FT	DISTANCE FT	DISTANCE FT	
TYPE					
DIAMETER	TO MH 17 clay pipe				
FLOW					

COMMENTS: Blocking lateral to 1366 Vista Verde

MANHOLE INSPECTION REPORT

DATE: 9-25

MANHOLE #: 22 STREET: Fairway
 WEATHER: Sunny hot INSPECTOR(S): AS

MANHOLE COVER *25.5" odd size*

DIAMETER: 24 INCHES
 NO. OF HOLES IN COVER: 1
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME
 CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO


CORBEL AND WALLS
 CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS
 CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: 6" INCHES *Luged*

STEPS *None*
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION
 EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: _____ INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: _____ GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE	
	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	TO MH # _____ DISTANCE _____ FT	_____ FT
TYPE					
DIAMETER					
FLOW					

COMMENTS:

MANHOLE INSPECTION REPORT

MANHOLE #: 26 STREET: Anderson Parkway DATE: 9-24-12
 WEATHER: SWIRLY INSPECTOR(S): [Signature]

MANHOLE COVER
 DIAMETER: 24 INCHES
 NO. OF HOLES IN COVER: 1
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

*photo taken
irrigation line over cover*


MANHOLE FRAME
 CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORREL AND WALLS
 CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS
 CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: _____ INCHES

STEPS
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO



TYPICAL MANHOLE

INFLOW AND INFILTRATION
 EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: _____ INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: _____ GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE
	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	TO MH # _____ DISTANCE _____ FT
TYPE				
DIAMETER				
FLOW				

COMMENTS:

MANHOLE INSPECTION REPORT

MANHOLE #: 24 STREET: Fairview DATE: 9-24
 WEATHER: Sunny INSPECTOR(S): dyh

MANHOLE COVER

DIAMETER: 27 INCHES
 NO. OF HOLES IN COVER: 1
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: 2 INCHES

STEPS


CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: 1 INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: 1 GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE
	FROM MH # <u>25</u> DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	TO MH # _____ DISTANCE _____ FT
TYPE				
DIAMETER				
FLOW				

COMMENTS:


MANHOLE INSPECTION REPORT

MANHOLE #: 25 STREET: Golf Course DATE: 9-24-12
 WEATHER: Sunny INSPECTOR(S): AB

MANHOLE COVER

DIAMETER: _____ INCHES
 NO. OF HOLES IN COVER: _____
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

Manhole not found



TYPICAL MANHOLE

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: _____ INCHES

STEPS

CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: _____ INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: _____ GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE
	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	TO MH # _____ DISTANCE _____ FT
TYPE				
DIAMETER				
FLOW				

COMMENTS:


MANHOLE INSPECTION REPORT

MANHOLE #: 27 STREET: Golf Course DATE: 9-24
 WEATHER: Sunny INSPECTOR(S): AS

MANHOLE COVER

DIAMETER: _____ INCHES
 NO. OF HOLES IN COVER: _____
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

Manhole in Back Yard not inspected as directed



TYPICAL MANHOLE

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: _____ INCHES

STEPS

CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: _____ INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: _____ GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE
	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	TO MH # _____ DISTANCE _____ FT
TYPE				
DIAMETER				
FLOW				

COMMENTS:

MANHOLE INSPECTION REPORT

MANHOLE #: 28 STREET: Barbra Worth Drive DATE: 9-24-12
 WEATHER: Hot sunny INSPECTOR(S): CS

MANHOLE COVER

DIAMETER: 24 INCHES
 NO. OF HOLES IN COVER: 1
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: 1 INCHES

STEPS None


CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: 1' INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: 1 GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE
	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	TO MH # _____ DISTANCE _____ FT
TYPE				
DIAMETER				
FLOW				

COMMENTS: To MH # 5
Good Flow rate

MANHOLE INSPECTION REPORT

MANHOLE #: 30 STREET: GOLF course Private citizens yard DATE: 9-25
 WEATHER: windy INSPECTOR(S): [Signature]

MANHOLE COVER

DIAMETER: _____ INCHES
 NO. OF HOLES IN COVER: _____
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: _____ INCHES

STEPS


CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: _____ INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: _____ GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE	INCOMING LINES			OUTGOING LINE	
	FROM MH # _____	FROM MH # _____	FROM MH # _____	TO MH # _____	
DATA	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DROP LINE <input type="checkbox"/>	DISTANCE	FT
	DISTANCE	FT	DISTANCE	FT	FT
TYPE					
DIAMETER					
FLOW					

COMMENTS:

MANHOLE INSPECTION REPORT

MANHOLE #: 31 STREET: GOLF COURSE DATE: 9-25
 WEATHER: Sunny INSPECTOR(S): AS

MANHOLE COVER

DIAMETER: _____ INCHES
 NO. OF HOLES IN COVER: _____
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MH not found
 COVER
 FRAME

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS


CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: _____ INCHES

STEPS

CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO



TYPICAL MANHOLE

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: _____ INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: _____ GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE	
	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	TO MH # _____	DISTANCE _____ FT
TYPE					
DIAMETER					
FLOW					

COMMENTS:

MANHOLE INSPECTION REPORT

MANHOLE #: 32 STREET: Behind Hotel near Golf course DATE: 9-25-12
 WEATHER: Sunny Hot INSPECTOR(S): RS

MANHOLE COVER

DIAMETER: 24 INCHES 24
 NO. OF HOLES IN COVER: 1
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: 0 INCHES

STEPS


CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: 1 INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: _____ GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE	
	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE _____ FT	TO MH # _____	DISTANCE _____ FT
TYPE					
DIAMETER					
FLOW					

COMMENTS: 1 in 1 out 1 Drop connection intruding into MH

Photo taken

MANHOLE INSPECTION REPORT

MANHOLE #: 33 STREET: Barbara Worth Drive DATE: 9-24-12
 WEATHER: Hot sunny INSPECTOR(S): W/B

MANHOLE COVER

DIAMETER: _____ INCHES
 NO. OF HOLES IN COVER: _____
 CONDITION OF FIT: LOOSE TIGHT
 SEALED BOLTED
 EVIDENCE OF LEAKAGE: YES NO

MANHOLE FRAME

CONDITION: SOUND BROKEN
 EVIDENCE OF LEAKAGE: YES NO

CORBEL AND WALLS

CONSTRUCTION: PRECAST BRICK
 CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

BENCH WALLS

CONDITION: GOOD DETERIORATING
 DEPOSITS: MUD DEBRIS SLUDGE
 DEPTH OF DEPOSITS: _____ INCHES

STEPS


CONDITION: GOOD DETERIORATING
 EVIDENCE OF DEBRIS ON STEPS: YES NO

TROUGH

CONDITION: GOOD DETERIORATING
 EVIDENCE OF LEAKAGE: YES NO

INFLOW AND INFILTRATION

EVIDENCE OF INFLOW: YES NO EVIDENCE OF SURCHARGING: YES NO
 INCHES ABOVE INVERT: _____ INCHES
 EVIDENCE OF INFILTRATION: YES NO ESTIMATED FLOW RATE: _____ GPM
 LOCATION/DESCRIPTION OF INFILTRATION: _____



TYPICAL MANHOLE

PIPE ENTRANCE DATA	INCOMING LINES			OUTGOING LINE	
	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE FT	FROM MH # _____ DROP LINE <input type="checkbox"/> DISTANCE FT	TO MH # _____	DISTANCE FT
TYPE					
DIAMETER					
FLOW					

COMMENTS:



Appendix F

Pipeline and Force Main Inspection Logs

Tabular Report of PLR 01

X

for Bureau Veritas NA

Work Order Facility	Contract Operator: KJP	Video Van Ref: 10	Setup 25 Surveyed On: 09/29/2012
Street Name Barbara Worth Rd		City Holtville	
Location type Surface			
Survey purpose Random survey of pipes and things		Weather Dry	
Pipe Use Sanitary	Sched length Ft	From 01	Depth Ft
Shape Circular	Size 10 by In	To PUMP STATION	Depth Ft
Material Polyvinyl chloride	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note Line leads across Evan Howes Hwy		Structural	Service
Location note		Miscellaneous	Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.5		MH					01
	0.0		WL				10	
	2.0		DEG	L				10.0 w 1/2 PIPE
	2.0		GO					BLOCKED BY LARGE DEBRIS IN MH
	2.0		SA					Survey abandoned

2.0 Ft Total Length Surveyed

Scores

Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
Service:	Total 150	Mean Defect 75	Peak 150	Mean Pipe 75




PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 01

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	25
Facility	Operator NJP	Van Ref 10	Surveyed On	09/25/2012
Street Name	Barbara Worth Rd	City	Hotville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From 01
Shape	Circular	Size 10	by	ins
Material	Polyvinyl chloride	Joint spacing	Ft	To PUMP STATION
Lining		Year laid		Direction Downstream
				Pre-clean N Last cleaned
General note	Line leaks across Evan Hewes Hwy	Structural	Service	Constructional
Location note		Miscellaneous	Hydraulic	



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Work Order	Video	Surveyed On 05/25/2012	Direction Overhead	Setup 25
Street Name Barbara Worth Rd	City Name Houston	Weather Dry		
Location	From Manhole 01	To Manhole PUMP STATION		

Date: 05/25/2012
Distance: 2.0 Ft
Obs: Debris (Grease)



Comments:
17 in 1/2 PPS

Date: 05/25/2012
Distance: 2.0 Ft
Obs: General observation



Comments:
BLOCKED BY LARGE
DEBRIS IN MH AND PPS

Tabular Report of PLR 02

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJF	Video Van Ref 10	Setup 23 Surveyed On: 09/25/2012
Street Name: Barbours Worth Rd		City: Fortville	
Location type Surface			
Survey purpose: Random survey of pipes and things		Weather: Dry	
Pipe Use: Sanitary	Sched length: Ft	From: 02	Depth: Ft
Shape: Circular	Size: 8 by 1/2	To: 01	Depth: Ft
Material: Polyvinyl chloride	Joint Spacing: Ft	Direction: Down	
Lining:	Year laid:	Pre-clean: N	Last Cleaned:
General note:		Structural	Service
Location note:		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Dev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					Mannhole/Node
	0.0		WL				10	Water level
	8.0		DE		L			Debris
	12.0		DE		L			Debris
	24.6		DE		L			CONTINUING
	25.3		GO					General observation BLOCKED BY DEBRIS
	25.3		GO					General observation DEBRIS TOO HEAVY FOR US ATTEM.
	25.6		SA					Survey abandoned

25.6 Ft Total Length Surveyed

Scores	Structural:	Total: 0	Mean Defect: 0	Peak: 0	Mean Pipe: 0
	Service:	Total: 450	Mean Defect: 112.5	Peak: 150	Mean Pipe: 17.8



X


PipeLogix Inc.
Phone: 866-298-3150
Fax: 760-405-8023

Pipe Graphic Report of PLR 02

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	23
Facility	Operator NIP	Van Ref 10	Surveyed On	09/25/2012
Street Name	Barbara Worth Rd	City	Holvile	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	From 02	Depth Ft
Shape	Circular	Size 8 by	To 01	Depth Ft
Material	Polyvinyl chloride	Joint spacing	Direction Downstream	
Lining		Year laid	Pre-clean N	Last cleaned
General note			Structural	Service
Location note			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
Phone: 866-299-3150
Fax: 780-406-6023

Work Order	Video	Surveyed On 09/25/2012	Direction Downstream	Setup 23
Street Name Barbera Worth Rd	City Name Holvile	Weather Dry		
Location	From Manhole 02	To Manhole 01		

Date: 09/25/2012
 Distance: 8.0 Ft
 Obs: Debris



Comments:

Date: 09/25/2012
 Distance: 12.0 Ft
 Obs: Debris



Comments:

Date: 09/25/2012
 Distance: 24.0 Ft
 Obs: Debris



Comments:
 CONTINUING

Tabular Report of PLR 03

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup 24
Facility	Operator NUP	Van Ref 10	Surveyed On 09/25/2012
Street Name	Barbara Worth Rd	City	Holtville
Location type	Surface	Weather	Dry
Survey purpose	Random survey of pipes and things		
Pipe Use	Sanitary	Sched length	Ft
Shape	Circular	Size #	by ins
Material	Polyvinyl chloride	Joint Spacing	Ft
Lining		Year laid	
From 03	Depth	Ft	
To 02	Depth	Ft	
Direction	Down		
Pre-clean N	Last Cleaned		
General note	CREATED SURVEY. HEAVY GREASE IN MH	Structural	Service
Location note		Miscellaneous	Constructional
			Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					Manhole/Node
	0.0		WL				10	Water level
	0.0		GO					General observation
	0.0		GO					General observation
	0.0		GO					General observation
	0.0		GO					General observation
	0.0		GO					General observation
	0.0		SA					Survey abandoned
0.0 Ft		Total Length Surveyed						

Scores

Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
Service:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Tabular Report of PLR 04


X

for Bureau Veritas NA

Work Order	Contract	Video	Setup 22
Facility	Operator NJP	Van Ref 10	Surveyed On 09/25/2012
Street Name Barbara Worth Rd		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and fittings			
Pipe Use Sanitary	Sched length Ft	From 04	Depth Ft
Shape Circular	Size 8 by 1/2 in	To 03	Depth Ft
Material Polyvinyl chloride	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Macrolenses	Hydraulic
Video	Count	CD	Code
			Sev Fr To Value Remarks
	0.0		MH Manhole
	0.0		WL Water level
	0.0		DE Debris
	1.0		GO General observation
	1.2		GO General observation
	1.2		SA Survey abandoned

1.2 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 150	Mean Defect 75	Peak 150	Mean Pipe 125



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Pipe Graphic Report of PLR 04

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	22
Facility	Operator NJP	Van Ref 10	Surveyed On	09/25/2012
Street Name	Barbara Worth Rd	City	Holiville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From 04
Shape	Circular	Size 8 by	Ins	To 03
Material	Polyvinyl chloride	Joint spacing	Ft	Direction
Lining		Year laid		Downstream
General note			Pre-clean	N
Location note			Last cleaned	
			Structural	Service
			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

CCTV pictures of 04

X

for Bureau Veritas NA

Work Order	Video	Surveyed On 03/05/2012	Direction Downstream	Setup 22
Street Name Suters North Rd	City Name Hobbs	Weather Dry		
Location	From Manhole 04	To Manhole 03		

Date: 03/05/12

Distance: 0.1 MI

Obs: Seters

Comments:

LARGE DEBRIS IN MH



Tabular Report of PLR 05

A


for Bureau Veritas NA

Work Order		Contract		Video		Setup 34	
Facility		Operator NJP		Van Ref 10		Surveyed On 08/27/2012	
Street Name Barbara Worth Rd				City Holtville			
Location type Surface				Weather Dry			
Survey purpose Random survey of pipes and things							
Pipe Use Sanitary		Sched length		Ft		From 05	
Shape Circular		Size 6 by		ins		To 06	
Material Vitrified clay		Joint Spacing		Ft		Direction Down	
Lining		Year laid				Pre-clean N Last Cleaned	
General note Created survey. Could not attempt line.				Structural		Service	
Location note				Miscellaneous		Hydraulic	
Video		Count		CD		Code	
		0.0				ST Start of Survey	
		0.0				MH Manhole/Node	
		0.0				WL Water level	
		0.0				GO General observation	
		0.0				GO General observation	
		0.0				GO General observation	
		0.0				GO General observation	
		0.0				GO General observation	
		0.0				GO General observation	

0.0 Ft Total Length Surveyed

Scores

Structural:	Total	Mean Defect	Peak	Mean Pipe
Service:	Total	Mean Defect	Peak	Mean Pipe



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Tabular Report of PLR 05

A

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 33 Surveyed On 09/27/2012
Street Name Barbara Worth Rd		City Hollyville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 06	Depth Ft
Shape Circular	Size by ins	To 04	Depth Ft
Material Verified clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note Created survey. Could not attempt line.		Structural	Service
Location note		Conspirational	Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					06
	0.0		WL					0
	0.0		GC					BOTH US AND DS MYS SURCHARGE
	0.0		GC					NO ACCESS OR VISIBILITY
	0.0		GC					LINE POSSIBLY SURCHARGED DUE
	0.0		GC					MAPS INCORRECT. MH 06 LEADS D...

0.0 Ft Total Length Surveyed

Scores	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-8023

Tabular Report of PLR 07

A

for Bureau Veritas NA

Work Order Facility	Contract Operator NUP	Video Van Ref 10	Setup 32 Surveyed On 09/27/2012
Street Name Barbara Worth Rd		City Holtville	
Location type Surface			
Survey purpose Random survey of pipes and things		Weather Dry	
Pipe Use Sanitary	Sched length Ft	From 07	Depth Ft
Shape Circular	Size $\frac{1}{2}$ by $\frac{1}{2}$ Ins	To 08	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note Created survey. Could not attempt line.		Structural	Service
Location note		Miscellaneous	Constructional
		Hydraulic	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					Manhole/Node
	0.0		WL				0	Water level
	0.0		GO					General observation
	0.0		GO					General observation
	0.0		GO					General observation
	0.0		GO					General observation
	0.0		GO					General observation

0.0 Ft Total Length Surveyed

Scores	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Tabular Report of PLR 08

A

for Bureau Veritas NA

Work Order Facility	Contract Operator NIP	Video Van Ref 10	Setup 31 Surveyed On 09/27/2012
Street Name Barbara Worth Rd		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 00	Depth Ft
Shape Circular	Size 8 by ins	To 07	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note Created survey. Could not attempt line.		Structural	Service
Location note		Miscellaneous	Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MN					Oil
	0.0		WL				0	Water level
	0.0		GO					LIE MH BEND TOO TIGHT IN TRAILG.
	0.0		GD					DS MH NOT FOUND
	0.0		GO					COULD NOT ATTEMPT LINE

0.0 Ft Total Length Surveyed

Scores	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe



10

PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Tabular Report of PLR 09

X


for Bureau Veritas NA

Work Order Facility	Contract Operator N/P	Video Van Ref 10	Setup 28 Surveyed On 09/28/2012
Street Name Barbera Worth Rd		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 09	Depth Ft
Shape Circular	Size 8 by Ins	To 08	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Down	
Lining	Year Inst	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Constructional
			Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					Manhole/Node
	0.0		WL					Water level
	6.0		CB			09		Break in Connection
	8.0		DE					Defect
	41.8		CN			09		Service Connection
	51.9		DE					Defect
	84.8		CN			10		Service Connection
	128.1		CN			09		Service Connection
	146.3		MH					Manhole/Node
	146.3		FT					Finish of Survey

146.3 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 225	Mean Defect 75	Peak 150	Mean Pipe 1.5




PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-8023

Pipe Graphic Report of **PLR 09**

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	28
Facility	Operator: NJP	Van Ref: 10	Surveyed On	09/28/2012
Street Name	Barbara Worth Rd	City	Holville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Fl	From 08
Shape	Circular	Size 8 by	Ins	To 08
Material	Vitrified clay	Joint spacing	Fl	Direction
Lining		Year laid		Downstream
General note			Pre-clean	N
Location note			Last cleaned	
			Structural	Service
			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Work Order	Video	Surveyed On	Direction	Setup
Street Name: Garbars Wirth Rd	City Name: Holtville	09/26/2012	Downstream	29
Location		From Manhole 06	Weather: Dry	To Manhole 09

Date: 09/26/2012
 Distance: 8.0 Ft
 Obs: Break in Connection

Comments:



Date: 09/26/2012
 Distance: 8.0 Ft
 Obs: Debris

Comments:



Date: 09/26/2012
 Distance: 41.8 Ft
 Obs: Service Connection

Comments:



Date: 09/26/2012
 Distance: 51.5 Ft
 Obs: Debris

Comments:
 CONTINUING



Date: 09/26/2012
 Distance: 84.8 Ft
 Obs: Service Connection

Comments:



Date: 09/26/2012
 Distance: 120.1 Ft
 Obs: Service Connection

Comments:



Tabular Report of PLR 10

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 27 Surveyed On 09/26/2012
Street Name Barbara Worth Rd		City Holtville	
Location type Surface			
Survey purpose Random survey of pipes and things		Weather Dry	
Pipe Use Sanitary	Sched length Ft	From 09	Depth Ft
Shape Circular	Size 8 by ine	To 10	Depth Ft
Material Vitrifed clay	Joint Spacing Ft	Direction Up	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					Manhole/Node
	0.0		WL				3	Water level
	5.0		DE	S				Debris
	11.6		CN			10		Service Connection
	20.1		CN			02		Service Connection
	56.9		DEG	S				Debris (Grease)
	89.5		CRA	S		03		Roots around Lateral
	66.7		CB			03		Break in Connection
	73.8		CN			10		Service Connection
	84.4		CB			02		Break in Connection
	87.0		CN			02		Service Connection
	87.8		DEG	M				Debris (Grease)
	115.6		DEG	M				Debris (Grease)
	139.2		CN			10		Service Connection
	152.4		CN			02		Service Connection
	166.5		DEG	L				Debris (Grease)
	196.6		CP			03		Plugged Connection
	201.4		GO					General observation
	201.4		MH					Manhole/Node
	201.4		FH					Finish of Surveys


201.4 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 420	Mean Defect 60	Peak 150	Mean Pipe 2.1



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-405-6023

Work Order	Contract	Video	Setup 27
Facility	Operator NJP	Van Ref 13	Surveyed On 06/26/2012
Street Name	Barbara Worth Rd	City	Holville
Location type			
Surface			
Survey purpose	Random survey of pipes and things	Weather	Dry
Pipe Use Sanitary	Schedule length Ft	From 09	Depth Ft
Shape Circular	Size 8 by ins	To 10	Depth Ft
Material Vitified clay	Joint spacing Ft	Direction Upstream	
Lining	Year laid	Pre-clean N	Last cleaned
General note		Structural	Service
Location note		Miscellaneous	Constructional
			Hydraulic




PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 10

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	27
Facility	Operator N/P	Van Ref 10	Surveyed On	09/20/2012
Street Name	Barbara Worth Rd	City	Holville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From 09
Shape	Circular	Size 8 by	ins	To 10
Material	Verified clay	Joint spacing	Ft	Direction Upstream
Lining		Year laid		Pre-clean N Last cleaned
General note	Structural		Service	Constructional
Location note	Miscellaneous		Hydraulic	



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Work Order	Video	Surveyed On	Direction	Setup
Barbours Worth Rd		09/26/2012	Upstream	27
City Name	Hobbs		Weather	Dry
Location		From Manhole	30	To Manhole

Date: 09/26/2012
 Distance: 5.0 Ft
 Obs: Debris



Comments:

Date: 09/26/2012
 Distance: 11.5 Ft
 Obs: Service Connection



Comments:

Date: 09/26/2012
 Distance: 20.1 Ft
 Obs: Service Connection



Comments:

Date: 09/26/2012
 Distance: 56.6 Ft
 Obs: Debris (CR9846)




Comments:

Date: 09/26/2012
 Distance: 68.5 Ft
 Obs: Roots around Lateral



Comments:

Date: 09/26/2012
 Distance: 99.7 Ft
 Obs: Break in Connection



Comments:

Work Order	Video	Surveyed On 08/26/2012	Direction Upstream	Setup 27
Street Name Barbara Worth Rd	City Name Indio	Weather Dry		
Location	From Manhole 08	To Manhole 10		

Date: 08/26/12
 Distance: 75.8 Ft
 Obs: Service Connection



Comments:

Date: 08/26/12
 Distance: 84.8 Ft
 Obs: Break in Connection



Comments:

Date: 08/26/12
 Distance: 87.0 Ft
 Obs: Service Connection



Comments:

Date: 08/26/12
 Distance: 87.8 Ft
 Obs: Debris (Grease)



Comments:
 CONTINUING

Date: 08/26/12
 Distance: 118.8 Ft
 Obs: Debris (Grease)



Comments:
 CONTINUING

Date: 08/26/12
 Distance: 139.7 Ft
 Obs: Service Connection



Comments:

Work Order	Video	Surveyed On 05/29/2012	Direction Upstream	Setup 27
Street Name: Barbara Worth Rd	City Name: Hoboken	Weather: Dry		
Location	From Manhole: 00	To Manhole: 10		

Date: 05/29/2012
Distance: 152.4 Ft
Obs: Service Connection

Comments:



Date: 05/29/2012
Distance: 160.5 Ft
Obs: Catch (Gross)

Comments:
CONTINUING



Date: 05/29/2012
Distance: 196.5 Ft
Obs: Plugged Connection

Comments:



Tabular Report of PLR 11

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 30 Surveyed On 09/27/2012
Street Name Barbara Worth Dr		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 11	Depth Ft
Shape Circular	Size 8 by ins	To 07	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note Created Survey. Could not attempt line		Structural	Service
Location note		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					11
	0.0		WL				0	
	0.0		GD					US AND DS MHS BURIED/NOT FOU...
	0.0		GD					COULD NOT ATTEMPT LINE

0.0 Ft Total Length Surveyed

Scores	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Tabular Report of PLR 12

X

for Bureau Veritas NA

Work Order Facility		Contract Operator NUP		Video Van Ref 10		Setup 16 Surveyed On 09/24/2012		
Street Name Fairway Dr (Golf Course)				City Hoiville				
Location type Surface				Weather Dry				
Survey purpose Random survey of pipes and things								
Pipe Use Sanitary		Sched length Ft		From 12		Depth Ft		
Shape Circular		Size 8 by ins		To 11		Depth Ft		
Material Vitrified clay		Joint Spacing Ft		Direction Down				
Lining		Year laid		Pre-clean N		Last Cleaned		
General note				Structural		Service		
Location note				Miscellaneous		Hydraulic		
Structural		Service		Constructional				
Miscellaneous		Hydraulic						
Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					12
	0.0		WL				5	
	1.0		DE					
	1.0		GO					BLOCKED BY DEBRIS
	1.0		GO					DE MH IS BURIED/NOT FOUND
	1.0		SA					Survey abandoned


1.0 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 100	Mean Defect 75	Peak 100	Mean Pipe 70.0



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-8023

Work Order	Contract	Video	Setup	18
Facility	Operator NJP	Van Ref 10	Surveyed On	09/24/2012
Street Name	Fairway Dr (Golf Course)	City	Hotville	
Location type				
Surface				
Survey purpose	Random survey of pipes and fittings		Weather	Dry
Pipe Use	Sanitary	Schedule length	Ft	From 12
Shape	Circular	Size # by	in	To 11
Material	Vitrified clay	Joint spacing	Ft	Depth
Lining		Year laid		Depth Ft
General note		Pre-clean	N	Last cleaned
Location note		Structural	Service	Constructional
		Miscellaneous	Hydraulic	



CCTV pictures of 12

X

for Bureau Veritas NA

Work Order	Video	Surveyed On 03/04/2012	Direction Downstream	Setup 18
Street Name Fairway Dr (Golf Course)	City Name Hobbs	Weather Dry		
Location	From Manhole 12	To Manhole 11		

Date: 03/04/2012

Distance: 1.9 Ft

Obs: Clear

Comments:



Tabular Report of PLR 13

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 14 Surveyed On 09/24/2012
Street Name Fairway Dr (Golf Course)		City Hoboken	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length	Ft	From 13
Shape Circular	Size 8 by	in	To 12
Material Vitrified clay	Joint Spacing	Ft	Direction Down
Lining	Year laid		Pre-clean N Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					Manhole/Node 13
	0.0		WL					Water level 13
	1.1		DEG		L			Debris (Grease)
	1.1		GO					General observation
	1.1		SA					Survey abandoned

1.1 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe D:
	Service:	Total 190	Mean Defect 75	Peak 150	Mean Pipe 139.4




PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-496-6023

Pipe Graphic Report of PLR 13

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	14
Facility	Operator NJP	Van Ref 10	Surveyed On	09/24/2012
Street Name	Fairway Dr (Golf Course)	City	HotMile	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From: 13
Shape	Circular	Size 8" by	ins	To: 12
Material	Vitrified clay	Joint spacing	Ft	Direction: Downstream
Lining		Year laid		Pre-clean: N Last cleaned
General note			Structural	Service
Location note			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Tabular Report of PLR 13

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 15 Surveyed On 09/24/2012
Street Name Fairway Dr (Golf Course)		City Hallville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 12	Depth Ft
Shape Circular	Size 8 by ins	To 13	Depth Ft
Material Verified clay	Joint Spacing Ft	Direction Up	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Hydraulic

Video	Count	CD	Code	Sav	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					Manhole/Node 12
	0.0		WL				5	Water level
	2.0		DE	L				Debris
	2.0		GO					General observation
	2.0		SA					Survey abandoned

2.0 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 150	Mean Defect 75	Peak 150	Mean Pipe 75



26

PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

CCTV pictures of 13

X

for Bureau Veritas NA

Work Order	Video	Surveyed On 09/24/2012	Direction Downstream	Setup 14
Street Name Fairy Dr (Golf Course)	City Name Huber	Weather Dry		
Location	From Manhole 13		To Manhole 12	

Date: 09/24/2012
Distance: 1.1 ft
Obs: Dark (Grease)

Comments:



Tabular Report of PLR 14

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NIP	Video Van Ref 10	Setup 13 Surveyed On 09/24/2012
Street Name Fairway Dr (Golf Course)		City Holtville	
Location type Surface			
Survey purpose Random survey of pipes and things		Weather Dry	
Pipe Use Sanitary	Sched length	Ft	From 13
Shape Circular	Size 8	by	To 14
Material Vitrifed clay	Joint Spacing	ft	Direction Up
Lining	Year laid		Pre-clean N Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0	BT	Start of Survey					
	0.0	MH	Manhole/Node					13
	0.0	WL	Water level				5	
	1.1	CEG	Count (Grease)	L				in MH
	4.9	GO	General observation					BLOCKED IN MH BY DEBRIS
	4.9	SA	Survey abandoned					

4.9 ft Total Length surveyed


Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 150	Mean Defect 75	Peak 150	Mean Pipe 30.0



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 14 X for Bureau Veritas NA

Work Order	Contract	Video	Setup	13
Facility	Operator NJP	Van Ref 10	Surveyed On	09/24/2012
Street Name	Fairway Dr (Golf Course)	City	Hobville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	From 13	Depth
Shape	Circular	Size 6 by	To 14	Depth
Material	Vitrified clay	Joint spacing	Direction	Upstream
Lining		Year laid	Pre-clean	N
General note			Last cleaned	
Location note		Structural	Service	Construction
		Miscellaneous	Hydraulic	



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-408-6023

Tabular Report of PLR 14

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Rai 10	Setup 12 Surveyed On 09/24/2012
Street Name: Fairway Dr (Golf Course)		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 14	Depth Ft
Shape Circular	Size 8 by ins	To 13	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					Manhole/Node
	0.0		WL				5	Water level
	1.1		DE	L				Debris
	1.1		GD					General observation
	1.1		SA					Survey abandoned

1.1 Ft Total Length Surveyed

Scores


Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
Service:	Total 100	Mean Defect 75	Peak 100	Mean Pipe 135.4



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-408-6023

Pipe Graphic Report of PLR 14 X for Bureau Veritas NA

Work Order	Contract	Video	Setup	12
Facility	Operator NJP	Van Ref 10	Surveyed On	09/24/2012
Street Name	Fairway Dr (Golf Course)	City	Holmdel	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	From 14	Depth Ft
Shape	Circular	Size ϕ by in	To 73	Depth Ft
Material	Vitrified clay	Joint spacing	Direction	Downstream
Lining		Year laid	Pre-clean	N
General note			Last cleaned	
Location note			Structural	Service
			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
 Phone: 866-298-3150
 Fax: 760-408-6023

CCTV pictures of 14

X

for Bureau Veritas NA

Work Order	Video	Surveyed On 08/24/2012	Direction Downstream	Setup 17
Street Name Fairway Dr (Golf Course)	City Name Nashville	Weather Dry		
Location	From Manhole 14	To Manhole 13		

Date: 08/24/2012

Distance: 1.191

Site: Dents

Comments:



Tabular Report of PLR 15

X


for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 11 Surveyed On 09/24/2012
Street Name: Fairway Dr (Golf Course)		City: Holmdel	
Location type Surface			
Survey purpose: Random survey of pipes and things		Weather: Dry	
Pipe Use: Sanitary	Sched length: Ft	From 14	Depth: Ft
Shape: Circular	Size: # by ins	To 15	Depth: Ft
Material: Vitrified clay	Joint Spacing: Ft	Direction: Up	
Lining:	Year laid:	Pre-clean: N	Last Cleaned:
General note:		Structural	Service
Location note:		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					14
	0.0		WL				3	
	1.0		DE	L				IN MH
	1.0		GO					BLOCKED BY DEBRIS IN MH
	1.0		SA					Survey abandoned

1.0 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 150	Mean Defect 75	Peak 150	Mean Pipe 150



PipeLogix Inc.
Phone: 856-299-3150
Fax: 760-406-6023

Tabular Report of PLR 15

X


for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 10 Surveyed On 06/24/2012
Street Name: Fairway Dr (Golf Course)		City: Holtville	
Location type: Surface		Weather: Dry	
Survey purpose: Random survey of pipes and things			
Pipe Use: Sanitary	Sched length: Ft	From 15	Depth: Ft
Shape: Circular	Size 8 by Ins	To 14	Depth: Ft
Material: Vitified clay	Joint Spacing: Ft	Direction: Down	
Lining:	Year laid:	Pre-clean: N	Last Cleaned:
General note:		Structural	Service
Location note:		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					Manhole/Node
	0.0		WL					Water level
	2.0		DEG					Debris (Grease)
	4.0		DEG					Debris (Grease)
	4.0		GD					General observation
	4.0		SA					Survey abandoned


4.0 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 300	Mean Defect 100	Peak 150	Mean Pipe 75



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Work Order	Contract	Video	Setup	10
Facility	Operator NJP	Van Ref 10	Surveyed On	08/24/2012
Street Name	Fairway Dr (Golf Course)	City	Holville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From 15
Shape	Circular	Size 8 by	ins	To 14
Material	Vitrified clay	Joint spacing	Ft	Direction Downstream
Lining		Year laid		Pre-clean N Last cleaned
General note		Structural	Service	Constructional
Location note		Miscellaneous	Hydraulic	



Work Order	Video	Surveyed On	Description	Downstream	Setup
Street Name Fairway Dr (Golf Course)	City Name Hittville	09/24/2012	Weather Dry		
Location		From Manhole 13		To Manhole 14	

Date: 09/24/2012
 Distance: 28 FT
 Obs: Debris (Grease)



Comments:

Date: 09/24/2012
 Distance: 40 FT
 Obs: Debris (Grease)



Comments:
 50% OF PIPE FULL OF GREASE

Date: 09/24/2012
 Distance: 40 FT
 Obs: General observation



Comments:
 BLOCKED BY GREASE

Tabular Report of PLR 16

X

for Bureau Veritas NA

Work Order		Contract		Video		Setup 9	
Facility		Operator NJP		Van Raf 10		Surveyed On 09/24/2012	
Street Name Fairway Dr				City Hoboken			
Location type							
Surface							
Survey purpose Random survey of pipes and things				Weather Dry			
Pipe Use Sanitary		Sched length		Ft		From 15	
Shape Circular		Size 6 by		ins		To 16	
Material Vitrified clay		Joint Spacing		Ft		Direction Up	
Lining		Year laid				Pre-clean N Last Cleaned	
General note				Structural		Service	
Location note				Miscellaneous		Hydraulic	
Video		Count		CD		Code	
		Sev		Fr		To Value Remarks	
		0.0		ST		Start of Survey	
		0.0		MH		Manhole/Node 15	
		0.0		WL		Water level 3	
		1.0		GO		General observation US MH IS SURCHARGED NO ACCESS	
		1.1		DEG		Debris (Grease)	
		1.1		GO		General observation AT ENTRANCE TO PIPE	
		1.1		GO		General observation BLOCKED IN MH BY TIGHT BEND A...	
		1.1		SA		Survey abandoned	

1.1 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 150	Mean Defect 75	Peak 150	Mean Pipe 133.4



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Tabular Report of PLR 17

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup # Surveyed On 09/24/2012
Street Name Vista Verde Dr		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 17	Depth Ft
Shape Circular	Size 6 by Ins	To 16	Depth Ft
Material Vitrifed clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0	MH	Manhole/Node					17
	0.0	WL	Water level				3	
	14.9	DEG	Debris (Grease)	L				
	23.3	DEG	Debris (Grease)	L				CONTINUING
	35.1	DEG	Debris (Grease)	L				CONTINUING
	41.1	GO	General observation					DS MH SURCHARGED. DID NOT ATT...
	41.2	GO	General observation					BLOCKED BY GREASE
	41.2	SA	Survey abandoned					

41.2 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 450	Mean Defect 112.5	Peak 150	Mean Pipe 10.9




PipeLogix Inc.
Phone: 888-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 17

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	8
Facility	Operator NJP	Van Ref 10	Surveyed On	09/24/2012
Street Name	Vista Verde Dr	City	Hotville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things		Weather	Dry
Pipe Use	Sanitary	Schedule length	Ft	From 17
Shape	Circular	Size 6 by	ins	To 18
Material	Vitrified clay	Joint spacing	Ft	Direction
Lining		Year laid		Downstream
				Pre-clean N Last cleaned
General note		Structural	Service	Construction
Location note		Miscellaneous	Hydraulic	



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Work Order	Video	Surveyed On	Direction	Downstream	Setup
Street Name: Vista Verde Dr	City Name: Hillsville	09/24/2012	Weather: Dry		
Location:		From Manhole: 17		To Manhole: 16	

Date: 09/24/2012
 Distance: 14.8 Ft
 Obs: Debris (Gravel)



Comments:

Date: 09/24/2012
 Distance: 23.3 Ft
 Obs: Debris (Gravel)



Comments:
 CONTINUING

Date: 09/24/2012
 Distance: 26.1 Ft
 Obs: Debris (Gravel)



Comments:
 CONTINUING

Tabular Report of PLR 18

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 7 Surveyed On 09/24/2012
Street Name Vista Verde Dr		City Holtsville	
Location type Surface			
Survey purpose Random survey of pipes and things		Weather Dry	
Pipe Use Sanitary	Sched length Ft	From 18	Depth Ft
Shape Circular	Size 6 by ins	To 17	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Constructional
		Hydraulic	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Service
	0.0		MH					Mandrel/Node 18
	0.0		WL					Water level 3
	2.0		CC	5	12	12		Circular Crack
	17.0		CN				03	Service Connection
	19.1		DEG					Debris (Grease)
	88.1		C	M	01	06		Corrosion of CI
	77.5		CN				03	Service Connection
	79.4		CN				06	Service Connection
	140.8		DS					Begin Pipe Sag
	147.5		CN				03	Service Connection
	169.3		CN				09	Service Connection
	151.0		DF					End pipe sag
	197.7		DS					Begin Pipe Sag
	213.1		CN				09	Service Connection
	214.7		CN				03	Service Connection
	220.8		GO					General observation LARGE DEBRIS IN DS MH
	220.8		GO					General observation SAG CONTINUES THROUGH MH
	221.8		MH					Mandrel/Node 17
	221.8		PH					Finish of Survey

221.8 Ft Total Length Surveyed

Scores	Structural:	Total 300	Mean Defect 60	Peak 200	Mean Pipe 1.4
	Service:	Total 150	Mean Defect 75	Peak 150	Mean Pipe 0.7





PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 18

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	7
Facility	Operator NJP	Van Ref 10	Surveyed On	06/24/2012
Street Name	Vista Verde Dr	City	Hotville	
Location type				
Surface				
Survey purpose	Random survey of pipes and fittings	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From 16
Shape	Circular	Size 6 by	ins	To 17
Material	Vitrified clay	Joint spacing	Ft	Direction
Lining		Year laid		Downstream
General note				Pre-clean
Location note				M
				Least cleaned
				Structural
				Service
				Constructional
				Miscellaneous
				Hydraulic





PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 780-406-6023

Pipe Graphic Report of PLR 16

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	7
Facility	Operator NJP	Van Ref 10	Surveyed On	09/24/2012
Street Name	Mata Verde Dr	City	Hobville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	From 16	Depth
Shape	Circular	Size 6 by	To 17	Depth
Material	Vitrified clay	Joint spacing	Direction	Downstream
Lining		Year laid	Pre-clean	N Last cleaned
General note			Structural	Service
Location note			Macelaneous	Hydraulic
			Constructional	



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Work Order	Video	Surveyed On 09/24/2012	Direction Downstream	Setup 7
Street Name Vista Verde Dr	City Name Hutchins	Weather Dry		
Location	From Manhole 13	To Manhole 17		

Date: 08/24/2012
 Distance: 2.0 Ft
 Obs: Circle Crack

Comments:



Date: 08/24/2012
 Distance: 17.0 Ft
 Obs: Service Connector

Comments:



Date: 08/24/2012
 Distance: 16.1 Ft
 Obs: Debris (Discol)

Comments:



Date: 09/04/2012
 Distance: 68.1 Ft
 Obs: Concrete of C

Comments:



Date: 09/04/2012
 Distance: 77.6 Ft
 Obs: Service Connector

Comments:



Date: 08/24/2012
 Distance: 70.4 Ft
 Obs: Service Connector

Comments:



Work Order	Video	Surveyed On 09/24/2012	Direction Downstream	Setup 7
Street Name Vista Verde Dr	City Name Hutchins	Weather Dry		
Location	From Manhole 16	To Manhole 17		

Date: 09/24/2012
 Distance: 140.6 Ft
 Obs: High Pipe Sag



Comments:

Date: 09/24/2012
 Distance: 147.5 Ft
 Obs: Service Connection




Comments:

Date: 09/24/2012
 Distance: 149.3 Ft
 Obs: Service Connection



Comments:

Date: 09/24/2012
 Distance: 151.8 Ft
 Obs: End pipe sag



Comments:

Date: 09/24/2012
 Distance: 157.7 Ft
 Obs: High Pipe Sag



Comments:

Date: 09/24/2012
 Distance: 163.1 Ft
 Obs: Service Connection



Comments:

Work Order	Video	Surveyed On 08/04/2012	Direction Downstream	Setup 7
Street Name Vista Verde Dr	City Name Hobbs	Weather Dry		
Location	From Manhole 10	To Manhole 12		

Date: 08/04/2012
Distance: 214.7 Ft
Obs: Barbed Connection

Comments:



Date: 08/04/2012
Distance: 220.3 Ft
Obs: General observation

Comments:
LARGE DEBRIS IN CS MH



Tabular Report of PLR 19

X

for Bureau Veritas NA

Work Order		Contract		Video		Setup 5	
Facility		Operator NUP		Van Ref 10		Surveyed On 09/24/2012	
Street Name Fairway Dr				City Holtville			
Location type				Surface			
Survey purpose Random survey of pipes and things				Weather Dry			
Pipe Use Sanitary		Sched length		Ft		From 19	
Shape Circular		Size 3 by		In		To 16	
Material Vitrified clay		Joint Spacing		Ft		Direction Down	
Lining		Year laid				Pre-clean N Last Cleaned	
General note				Structural		Service	
Location note				Miscellaneous		Hydraulic	
Video		Count		CD		Code	
		Sev		Fr		To Value Remarks	
		0.0				MI Manhole/lyote 10	
		0.0				WL Water level 3	
		2.0				DEG Debris (Grease) 1	
		28.9				DEG Debris (Grease) 1 CONTINUING	
		68.6				DEG Debris (Grease) 1 CONTINUING	
		78.9				CB Break in Connection 12	
		81.2				GD General observation 05 MH SURCHARGED DID NOT ATT.	
		81.3				GD General observation 100% BLOCKED BY GREASE	
		81.3				SA Survey abandoned	


81.3 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 450	Mean Defect 112.5	Peak 150	Mean Pipe 5.5



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Work Order	Contract	Video	Setup	S
Facility	Operator NJP	Van Ref 10	Surveyed On	08/24/2012
Street Name	Fairway Dr	City	Hotville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From 19
Shape	Circular	Size #	by	ins
Material	Verified clay	Joint spacing	Ft	To 16
Lining		Year laid		Direction Downstream
General note		Pre-clean	N	Last cleaned
Location note		Structural	Service	Constructional
		Macellaneous	Hydraulic	



Work Order	Video	Surveyed On 08/24/2012	Direction Downstream	Setup E
Street Name Farway Dr	City Name Hoboken	Weather Dry		
Location	From Manhole 10	To Manhole 10		

Date: 08/24/2012
 Distance: 2.0 Ft
 Obs: Debris (Grease)

Comments:



Date: 08/24/2012
 Distance: 25.9 Ft
 Obs: (white) (Grease)

Comments:
 CONTINUING



Date: 08/24/2012
 Distance: 34.5 Ft
 Obs: Debris (Grease)

Comments:
 CONTINUING



Date: 08/24/2012
 Distance: 30.0 Ft
 Obs: Break in Connection

Comments:



Tabular Report of PLR 20

X


for Bureau Veritas NA

Work Order Facility		Contract Operator NJP		Video Van Ref 10		Setup # Surveyed On 09/26/2012			
Street Name Camino Verde Dr				City Holtville					
Location type Surface									
Survey purpose Random survey of pipes and things				Weather Dry					
Pipe Use Sanitary		Sched length Ft		From 20		Depth Ft			
Shape Circular		Size 6 by ins		To 19		Depth Ft			
Material vitrified clay		Joint Spacing Ft		Direction Down					
Lining		Year laid		Pre-clean N		Last Cleaned			
General note				Structural		Service			
Location note				Miscellaneous		Hydraulic			
Video	Count	CD	Code	Sev	Fr	To	Value	Remarks	
	0.0		ST Start of Survey						
	0.0		MH Manhole/Node					20	
	0.0		WL Water level					3	
	1.0		DC Debris	L				PIPE 30% FULL OF DIRT	
	1.1		GO General observation					0.8 MH BEND TOO TIGHT IN TRAJ...	
	1.1		GO General observation					BLOCKED BY DEBRIS	
	1.1		SA Survey abandoned						
1.1 Ft		Total Length Surveyed							
Scores	Structural:		Total 0	Mean Defect 0		Peak 0		Mean Pipe 0	
	Service:		Total 150	Mean Defect 75		Peak 150		Mean Pipe 136.4	



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Work Order	Contract		Video	Setup 5
Facility	Operator NJP		Van Ref 10	Surveyed On 08/24/2012
Street Name	Camino Verde Dr	City	Holtville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things		Weather	Dry
Pipe Use	Sanitary	Schedule length	Ft	From 20
Shape	Circular	Size 8	by	in
Material	Vitrified clay	Joint spacing	Ft	To 15
Lining		Year laid		Direction Downstream
General note				Pre-clean N Last cleaned
Location note				Structural Service Construction
				Miscellaneous Hydraulic



Work Order	Video	Surveyed On 09/04/2012	Direction Downstream	Setup 5
Street Name Captoy Verde Dr	City Name Hoboken	Weather Dry		
Location	From Manhole 20	To Manhole 19		

Date: 09/04/2012
Distance: 1.0 Ft
Dir: Down



Comments:
PPE 80% FULL OF DIRT

Tabular Report of PLR 21

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 3 Surveyed On 09/24/2012
Street Name Fairway Dr		City Holtville	
Location type Surface			
Survey purpose Random survey of pipes and things		Weather Dry	
Pipe Use Sanitary	Sched length Ft	From 21	Depth Ft
Shape Circular	Size 8 by ins	To 19	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note			Constructional
		Miscellaneous	Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST Start of Survey					
	0.0		MH Manhole/Node					21
	0.0		WL Water level				3	
	8.1		DEG Debris (Grease)	L				
	30.2		CB Break in Connection		02			
	40.7		CN Service Connection		03			
	43.6		CN Service Connection		09			
	65.6		DEG Debris (Grease)	L				CONTINUING
	101.6		CRA Roots around Lateral	L	12			
	102.1		CB Break in Connection		12			
	112.4		CN Service Connection		03			
	115.3		CN Service Connection		09			
	117.2		DEG Debris (Grease)	L				CONTINUING
	134.2		OO General observation					BLOCKED BY HEAVY GREASE
	134.2		SA Survey abandoned					

134.2 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 570	Mean Defect 105	Peak 150	Mean Pipe 3.8





PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 21

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	3
Facility	Operator NIP	Van Ref 10	Surveyed On	09/24/2012
Street Name	Fairway Dr	City	Holtsville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	From 21	Depth Ft
Shape	Circular	Size 8 by ins	To 19	Depth Ft
Material	Vitrified clay	Joint spacing	Direction Downstream	
Lining		Year laid	Pre-clean N	Last cleaned
General note			Structural	Service
Location note			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Work Order	Video	Surveyed On	Direction	Setup
Street Name Fairway Dr	City Name Holtville	08/24/2012	Downstream	3
Location		From Manhole 21		To Manhole 19
			Weather Dry	

Date: 08/24/2012
 Distance: 3.1 Ft
 Obs: Debris (Grease)



Comments:

Date: 08/24/2012
 Distance: 20.2 Ft
 Obs: Break in Connection



Comments:

Date: 08/24/2012
 Distance: 45.7 Ft
 Obs: Service Connection



Comments:

Date: 08/24/2012
 Distance: 45.8 Ft
 Obs: Service Connection



Comments:

Date: 08/24/2012
 Distance: 65.8 Ft
 Obs: Debris (Grease)



Comments:
 CONTINUING


Date: 08/24/2012
 Distance: 101.8 Ft
 Obs: Hydrofracture Lateral



Comments:

Work Order	Video	Surveyed On 09/24/2012	Direction Downstream	Setup 3
Street Name Fairway Cr	City Name Holyoke	Weather Dry		
Location		From Manhole 21	To Manhole 19	

Date: 09/24/2012
 Distance: 122.1 Ft
 Obs: Break in Connection



Comments:

Date: 09/24/2012
 Distance: 112.4 Ft
 Obs: Service Connection




Comments:

Date: 09/24/2012
 Distance: 115.3 Ft
 Obs: Service Connection



Comments:

Date: 09/24/2012
 Distance: 117.2 Ft
 Obs: Debris (Grease)



Comments:
 CONTINUING

Date: 09/24/2012
 Distance: 134.2 Ft
 Obs: General observation



Comments:
 BLOCKED BY HEAVY GREASE

Tabular Report of PLR 21

X


for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 4 Surveyed On 08/24/2012
Street Name Fairway Dr		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 19	Depth Ft
Shape Circular	Size 8 by ins	To 21	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Up	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST Start of Survey					
	0.0		MH Manhole/Node					19
	0.0		WL Water level					3
	6.1		CN Service Connection		03			
	6.0		DEG Debris (Gross)	L				
	33.8		DEG Debris (Grease)	L				
	33.8		GD General observation					BLOCKED BY GREASE
	33.8		SA Survey abandoned					

33.8 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 300	Mean Defect 100	Peak 150	Mean Pipe 8.9





PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 21

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	4
Facility	Operator NJP	Van Ref 10	Surveyed On	09/24/2012
Street Name	Fairway Dr	City	Holvile	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From 19
Shape	Circular	Size 8 by	ins	To 21
Material	Verified clay	Joint spacing	Ft	Direction Upstream
Lining		Year laid		Pre-clean N Last cleaned
General note			Structural	Service
Location note			Miscellaneous	Constructional
				Hydraulic



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Work Order	Video	Surveyed On 06/24/2012	Direction Upstream	Setup 4
Street Name Falmacy Dr	City Name Ithaca	Weather Dry		
Location	From Manhole 19	To Manhole 21		

Date: 06/24/2012

Distance: 6.1 Ft

Obs: Service Connection

Comments:



Date: 06/24/2012

Distance: 8.0 Ft

Obs: Debris (Grease)

Comments:



Date: 06/24/2012

Distance: 33.8 Ft

Obs: Debris (Grease)

Comments:



Date: 06/24/2012

Distance: 33.8 Ft

Obs: General observation

Comments:
BLOCKED BY GREASE

Tabular Report of PLR 22

X


for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 1 Surveyed On 09/24/2012
Street Name Fairway Dr		City Holvile	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 22	Depth Ft
Shape Circular	Size 8 by Ins	To 21	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note US MH has no lid. MH as large amount of dirt		Structural	Service
Location note		Constructural	Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					22
	0.0		WL				0	
	0.0		DE	M				N MH
	1.0		DE	L				90% OF PIPE AT MH
	1.0		GO					BLOCKED BY DEBRIS
	1.0		SA					Survey abandoned

1.0 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 225	Mean Defect 75	Peak 150	Mean Pipe 225




PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 22

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	1
Facility	Operator NJP	Van Ref 10	Surveyed On	09/24/2012
Street Name	Fairway Dr	City	Holville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	From 22	Depth Ft
Shape	Circular	Size 8 by ins	To 21	Depth Ft
Material	Vitrified clay	Joint spacing	Direction Downstream	
Lining		Year laid	Pre-clean N	Last cleaned
General note	US MH has no lid. MH as large amount of dirt		Standard	Service Constructional
Location note			Miscellaneous	Hydraulic



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

CCTV pictures of 22

X

for Bureau Veritas NA

Work Order	Video	Surveyed On 08/24/2012	Direction Downstream	Setup 1
Street Name Fairway Dr	City Name Hotville		Weather Dry	
Location		From Manhole 22	To Manhole 21	

Date: 08/24/2012

Distance: 1.0 FT

Obs: Debris

Comments:

90% OF PIPE AT MH



Tabular Report of PLR 22

X


for Bureau Veritas NA

Work Order	Contract	Video	Setup 2
Facility	Operator N/P	Van Ref 10	Surveyed On 09/24/2012
Street Name Fairway Dr		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 21	Depth Ft
Shape Circular	Size 8 by in	To 22	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Up	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Construction

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					Manhole/Node 2'
	0.0		WL					Water level 0'
	5.0		DEG		M			Debris (Grease)
	9.4		CB			10		Break in Connection
	11.7		DEG		L			Debris (Grease)
	26.6		CN			03		Service Connection
	34.5		CN			09		Service Connection
	45.0		CP			09		Plugged Connection
	47.8		CP			03		Plugged Connection
	53.1		DEG		L			Debris (Grease)
	74.3		CC		M	12	12	Circular Crack
	74.6		CL		M	10		Crack longitudinal
	75.3		CB			10		Break in Connection
	76.0		CL		S	12		Crack longitudinal
	97.9		DEG		L			Debris (Grease)
	103.2		CN			03		Service Connection
	111.1		CN			09		Service Connection
	113.4		CP			02		Plugged Connection
	179.3		CN			09		Service Connection
	197.1		CN			09		Service Connection
	197.1		DE		L			Debris
	197.1		GO					General observation
	197.1		SA					Survey abandoned

197.1 Ft Total Length Surveyed

Scores	Structural:	Total 400	Mean Defect 50	Peak 150	Mean Pipe 2
	Service:	Total 675	Mean Defect 112.5	Peak 180	Mean Pipe 3.4




PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Pipe Graphic Report of PLR 22

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	2
Facility	Operator N/P	Van Ref 10	Surveyed On	08/24/2012
Street Name	Fairway Dr	City	Holville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From 21
Shape	Circular	Size 8 by	ins	To 22
Material	Vitrified clay	Joint spacing	Ft	Direction Upstream
Lining		Year laid		Pre-clean N Last cleaned
General note		Structural	Service	Constructional
Location note		Miscellaneous	Hydraulic	




PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Pipe Graphic Report of PLR 22

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	2
Facility	Operator NLP	Van Ref 10	Surveyed On	09/24/2012
Street Name	Fairway Dr	City	Holville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	From 21	Depth Ft
Shape	Circular	Size 8 by	To 22	Depth Ft
Material	Vitrified clay	Joint spacing	Direction Upstream	
Lining		Year laid	Pre-clean N	Last cleaned
General note			Structural	Service
Location note			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-408-6023

Work Order	Video	Surveyed On 09/24/2012	Direction Upstream	Setup 2
Street Name Fairway Dr	City Name Holtville	Weather Dry		
Location		From Manhole 21	To Manhole 22	

Date: 09/24/2012
 Distance: 5.0 Ft
 Obs: Debris (Ground)



Comments:

Date: 09/24/2012
 Distance: 9.4 Ft
 Obs: Break In Connection




Comments:

Date: 09/24/2012
 Distance: 11.7 Ft
 Obs: Debris (Ground)



Comments:

Date: 09/24/2012
 Distance: 26.6 Ft
 Obs: Service Connection



Comments:

Date: 09/24/2012
 Distance: 34.3 Ft
 Obs: Service Connection



Comments:
 LARGE DEBRIS IN
 LATERAL

Date: 09/24/2012
 Distance: 45.0 Ft
 Obs: Plugged Connection



Comments:

Work Order	Video	Surveyed On	Direction	Upstream	Setup
Street Name Fairway Dr	City Name Hobbs	09/24/2012	Weather	Dry	
Location		From Manhole 21		To Manhole 22	

Date: 09/24/2012
 Distance: 47.5 Ft
 Obs: Plugged Connection



Comments:

Date: 09/24/2012
 Distance: 74.2 Ft
 Obs: Circular Crack



Comments:

Date: 09/24/2012
 Distance: 75.3 Ft
 Obs: Break in Connection



Comments:

Date: 09/24/2012
 Distance: 53.1 Ft
 Obs: Cracks (Grass)



Comments:
 CONTINUE

Date: 09/24/2012
 Distance: 74.8 Ft
 Obs: Crack longitudinal



Comments:

Date: 09/24/2012
 Distance: 76.0 Ft
 Obs: Crack longitudinal



Comments:

Work Order	Video	Surveyed On	Direction	Setup
Street Name Fairway Dr	City Name Vicksburg	08/24/2012	Upstream	2
Location		From Manhole 21		To Manhole 22

Date: 08/24/2012
 Distance: 87.9 Ft
 Obs: Debris (Grease)

Comments:
 CONTINUING



Date: 08/24/2012
 Distance: 103.2 Ft
 Obs: Service Connection

Comments:



Date: 08/24/2012
 Distance: 111.1 Ft
 Obs: Service Connection

Comments:



Date: 08/24/2012
 Distance: 113.4 Ft
 Obs: Plugged Connection

Comments:



Date: 08/24/2012
 Distance: 179.3 Ft
 Obs: Service Connection

Comments:



Date: 08/24/2012
 Distance: 187.1 Ft
 Obs: Service Connection

Comments:



Work Order	Video	Surveyed On 05/24/2012	Direction Upstream	Setup 2
Street Name Fairway Dr	City Name Hobbs	Weather Dry		
Location		From Manhole 21	To Manhole 22	

Date: 05/24/2012

Distance: 187.1 Ft

Obs: Debris

Comments:

PIPE 80% FULL OF DEBT



Tabular Report of PLR 23


X

for Bureau Veritas NA

Work Order		Contract		Video		Setup 17	
Facility		Operator NJP		Van Ref 10		Surveyed On 09/25/2012	
Street Name Fairway Dr				City HolMile			
Location type				Surface			
Survey purpose Random survey of pipes and things				Weather Dry			
Pipe Use Sanitary		Sched length		Ft		From 23	
Shape Circular		Size # by		Ins		To 15	
Material Vitrified clay		Joint Spacing		Ft		Direction Down	
Lining		Year laid		Pre-clean N		Last Cleaned	
General note				Structural		Service	
Location note				Miscellaneous		Hydraulic	
Video		Count		CD		Code	
		0.0				ST Start of Survey	
		0.0				MH Manhole/Node	
		0.0				WL Water level	
		2.0				DEG Depth (Down)	
		2.0				GO General observation	
		2.0				SA Survey abandoned	

2.0 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 150	Mean Defect 75	Peak 100	Mean Pipe 75




PipeLogix Inc.
 Phone: 856-299-3150
 Fax: 760-406-6023

Pipe Graphic Report of PLR 23

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	17
Facility	Operator NJP	Van Ref 10	Surveyed On	09/25/2012
Street Name	Fairway Dr	City	Holville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From 25
Shape	Circular	Size 6 by	ins	To 15
Material	Vitrified clay	Joint spacing	Ft	Direction
Lining		Year laid		Downstream
General note			Pre-clean	N Last cleaned
Location note			Structural	Service
			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Tabular Report of PLR 24

X


for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 16 Surveyed On 09/25/2012
Street Name Fairway Dr		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 24	Depth Ft
Shape Circular	Size 6 by 12	To 23	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		BT					Start of Survey
	0.0		MH					Manhole/Node
	0.0		WL				5	Water level
	18.1		DEG		S			Debris (Grease)
	45.0		DE		L			Debris
	103.3		DE		M			Debris
	126.0		DE		L			Debris
	159.5		CUB					Camera Submerged Begin
	159.9		GO					General observation
	159.9		SA					Survey abandoned

159.9 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 425	Mean Defect 70.8	Peak 150	Mean Pipe 2.7




PipeLogix Inc.
Phone: 888-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 24

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	18
Facility	Operator NJP	Van Ref 10	Surveyed On	09/25/2012
Street Name	Fairway Dr	City	Holville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From 24
Shape	Circular	Size 8 by	Ins	To 23
Material	Vitrified clay	Joint spacing	Ft	Direction Downstream
Lining		Year laid		Pre-clean N Last cleaned
General note			Structural	Service
Location note			Macellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Work Order	Video	Surveyed On 09/25/2012	Direction Downstream	Setup 18
Street Name Fairway Dr	City Name Hoboken	Weather Dry		
Location	From Manhole 24	To Manhole 23		

Date: 09/25/2012
 Distance: 12.1 Ft
 Obs: Debris (Ground)



Comments:

Date: 09/25/2012
 Distance: 45.0 Ft
 Obs: Debris



Comments:

Date: 09/25/2012
 Distance: 103.3 Ft
 Obs: Debris



Comments:
 CONTINUING

Date: 09/25/2012
 Distance: 125.0 Ft
 Obs: Debris



Comments:
 CONTINUING

Tabular Report of PLR 25

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NIP	Video Van Ref 10	Setup 19 Surveyed On 09/26/2012
Street Name Fairway Dr		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and fittings			
Pipe Use Sanitary	Sched length Ft	From 24	Depth Ft
Shape Circular	Size 8 by Ins	To 25	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Up	Last Cleaned
Lining	Year laid	Pre-clean N	
General note		Structural	Service
Location note		Miscellaneous	Constructional
		Hydraulic	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					Manhole/Node
	0.0		WL					Water level
	21.1		DEG		M			Debris / Debris
	41.1		CB		09			BREAK IN CONNECTION
	72.3		CB		12			BREAK IN CONNECTION
	104.5		CB		12			BREAK IN CONNECTION
	122.0		CXC		L	09		CONNECTION DEFECTIVE
	122.0		CB		09			BREAK IN CONNECTION
	187.7		CNI		S	12	0010	INTRUDING LATERAL
	187.8		CB		12			BREAK IN CONNECTION
	192.8		CP		10			PLUGGED CONNECTION
	272.8		CP		09			PLUGGED CONNECTION
	283.8		CL		S	12		CRACK LONGITUDINAL
	283.8		CNI		S	12	0005	INTRUDING LATERAL
	283.8		CB		12			BREAK IN CONNECTION
	348.8		RU		L			ROOTS AT JOINT
	350.1		CR		L	12		ROOTS FROM LATERAL
	350.1		CB		12			BREAK IN CONNECTION
	350.1		OO					GENERAL OBSERVATION
	350.1		SA					SURVEY ABANDONED

350.1 Ft Total Length Surveyed

Scores	Structural:	Total 400	Mean Defect 30.5	Peak 150	Mean Pipe 1.1
	Service:	Total 350	Mean Defect 82.5	Peak 100	Mean Pipe 0.7




PipeLogix Inc.
 Phone: 866-289-3150
 Fax: 760-406-8023

Pipe Graphic Report of PLR 25

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	19
Facility	Operator NJP	Van Ref 10	Surveyed On	09/26/2012
Street Name	Fairway Dr	City	Holtville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things		Weather	Dry
Pipe Use	Sanitary	Schedule length	From	24
Shape	Circular	Size 6 by	To	25
Material	Vitrified clay	Joint spacing	Direction	Upstream
Lining		Year laid	Pre-clean	N
			Last cleaned	
General note		Structural	Service	Constructional
Location note		Miscellaneous	Hydraulic	




PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Pipe Graphic Report of PLR 25

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	28
Facility	Operator NJP	Van Ref 10	Surveyed On	09/25/2012
Street Name	Andeholt Rd	City	Hotville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Fl	From 25
Shape	Circular	Size 8 by	ins	To 24
Material	Vitrified clay	Joint spacing	Fl	Direction Downstream
Lining		Year laid		Pre-clean N Last cleaned
General note			Structural	Service
Location note			Miscellaneous	Hydraulic
			Construction	



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-8023

Work Order	Video	Surveyed On 09/25/2012	Direction Upstream	Setup 10
Street Name Fairway Dr	City Name Hobbs		Weather Dry	
Location		From Manhole 24	To Manhole 25	

Date: 09/25/2012
 Distance: 31.1 Ft
 Obs: Debris (Onwall)



Comments:

Date: 09/25/2012
 Distance: 41.1 Ft
 Obs: Break in Connection



Comments:
 LATERAL HAS DEBRIS

Date: 09/25/2012
 Distance: 72.3 Ft
 Obs: Break in Connection



Comments:

Date: 09/25/2012
 Distance: 104.5 Ft
 Obs: Break in Connection



Comments:

Date: 09/25/2012
 Distance: 122.0 Ft
 Obs: Connector Defective



Comments:
 LARGE DEBRIS FROM
 LATERAL

Date: 09/25/2012
 Distance: 122.0 Ft
 Obs: Break in Connection



Comments:

Work Order	Video	Surveyed On 08/25/2012	Direction Upstream	Setup 10
Street Name Fairway Dr	City Name Hoboken	Weather Dry		
Location	From Manhole 24	To Manhole 25		

Date: 08/25/2012
 Distance: 157.7 Ft
 Obs: Intruding Lateral



Comments:

Date: 08/25/2012
 Distance: 187.9 Ft
 Obs: Plugged Connection



Comments:

Date: 08/25/2012
 Distance: 283.8 Ft
 Obs: Crack longitudinal



Comments:

Date: 08/25/2012
 Distance: 157.8 Ft
 Obs: Break in Connection



Comments:

Date: 08/25/2012
 Distance: 272.0 Ft
 Obs: Plugged Connection



Comments:

Date: 08/25/2012
 Distance: 283.9 Ft
 Obs: Intruding Lateral




Comments:

Work Order	Video	Surveyed On 06/25/2012	Direction Upstream	Setup 10
Street Name Fairway Dr	City Name Indio	Weather Dry		
Location	From Manhole 24	To Manhole 25		

Date: 06/25/2012
 Distance: 263.6 Ft
 Obs: Break in Connection

Comments:



Date: 06/25/2012
 Distance: 348.6 Ft
 Obs: Roots at joint

Comments:
 TAP ROOTS



Date: 06/25/2012
 Distance: 320.1 Ft
 Obs: Roots both internal

Comments:
 LARGE TAP ROOTS



Date: 06/25/2012
 Distance: 320.1 Ft
 Obs: Break in Connection

Comments:



Tabular Report of PLR 25

X

for Bureau Veritas NA

Work Order Facility	Contract Operator: NJP	Video Van Ref 10	Setup 25 Surveyed On 08/25/2012
Street Name Anterholt Rd		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 25	Depth Ft
Shape Circular	Size e ty ins	To 24	Depth Ft
Material Vitrifed clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					Manhole/Node
	0.0		WL					Water level
	29.8		RJ	L				Roots at joint
	31.3		CP		03			Plugged Connection
	31.9		GO					General observation
	31.9		GO					General observation
	31.9		SA					Survey abandoned

31.9 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 100	Mean Defect 50	Peak 100	Mean Pipe 3.1




PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-8023

Pipe Graphic Report of PLR 25

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	26
Facility	Operator NJP	Ven Ref 10	Surveyed On	08/25/2012
Street Name	Anderholt Rd	City	Holmdel	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	From 25	Depth Ft
Shape	Circular	Size 8 by	To 24	Depth Ft
Material	Vitrified clay	Joint spacing	Direction	Downstream
Lining		Year laid	Pre-clean	N Last cleaned
General note			Structural	Service
Location note			Miscellaneous	Hydraulic
			Constructional	



Work Order	Video	Surveyed On	Direction	Setup
Street Name: Archerd Rd	City Name: Hotville	06/05/2012	Downstream	08
Location:		From Manhole: 25	Weather: Dry	To Manhole: 24

Date: 06/05/2012
Distance: 29.8 Ft
Obs: Roots at joint



Comments:
LARGE TAP ROOT

Date: 06/05/2012
Distance: 31.3 Ft
Obs: Pugged Connection



Comments:

Tabular Report of PLR 26

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 21 Surveyed On 09/25/2012
Street Name Anderholt Rd		City Holtville	
Location type Surface			
Survey purpose Random survey of pipes and fittings		Weather Dry	
Pipe Use Sanitary	Sched length	Ft	From 20
Shape Circular	Size 8 by	ins	To 25
Material Vitrified clay	Joint Spacing	Ft	Direction Down
Lining	Year laid		Pre-clean N Last Cleaned
General note			Structural Service Constructional
Location note			Miscellaneous Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST Start of Survey					
	0.0		MH Manhole/Node					26
	0.0		WL Water level					3
	10.4		DEG Debris (Grease)	S				
	20.4		CP Plugged Connection		03			
	63.3		CB Break in Connection		03			
	92.7		CP Plugged Connection		03			
	111.0		CL Crack longitudinal	M	02			
	112.4		CB Break in Connection		02			
	146.4		DEG Debris (Grease)	S				CONTINUING
	156.4		RJ Roots at joint	S				
	186.3		CR Roots from lateral	M	03			
	186.3		CN Service Connection		03			
	217.5		CB Break in Connection		03			
	217.5		CRA Roots around Lateral	S	03			
	245.1		CP Plugged Connection		03			
	293.0		DEG Debris (Grease)	S				CONTINUING
	324.2		CP Plugged Connection		03			
	355.3		CB Break in Connection		02			
	355.3		CRA Roots around Lateral	M	03			
	355.3		RJ Roots at joint	S				TAP ROOTS
	391.5		MH Manhole/Node					35
	361.5		PH Finish of Survey					

361.5 Ft Total Length Surveyed

Scores	Structural:	Total 150	Mean Defect 16.7	Peak 150	Mean Pipe 0.4
	Service:	Total 365	Mean Defect 43.9	Peak 150	Mean Pipe 1.1





PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 26

X

for Bureau Veritas NA

Work Order		Contract		Video		Setup 21			
Facility		Operator NJP		Van Ref 10		Surveyed On 09/25/2012			
Street Name		Anderholt Rd		City		Hobbs			
Location type									
Surface									
Survey purpose Random survey of pipes and fittings				Weather Dry					
Pipe Use	Sanitary	Schedule length	Ft		From	25	Depth	Ft	
Shape	Circular	Size	6	by	ins	To	25	Depth	Ft
Material	Unfired clay	Joint spacing	Ft		Direction	Downstream			
Lining		Year laid			Pre-clean	N	Last cleaned		
General note					Structural	Service	Constructional		
Location note					Miscellaneous	Hydraulic			




PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Pipe Graphic Report of PLR 26

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	21
Facility	Operator NJP	Van Ref 10	Surveyed On	09/25/2012
Street Name	Anderholt Rd	City	Holville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	From 26	Depth Ft
Shape	Circular	Size 8 by	To 25	Depth Ft
Material	Vitrified clay	Joint spacing	Direction	Downstream
Lining		Year laid	Pre-clean	N Last cleaned
General note			Structural	Service
Location note			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Work Order	Video	Surveyed On	Direction	Setup
Street Name Amsterdam Rd	City Name Hoboken	09/25/2012	Downstream	21
Location	From Manhole 25		To Manhole 26	

Date: 09/25/2012
 Distance: 10.4 Ft
 Obs: Sinks (Grease)

Comments:



Date: 09/25/2012
 Distance: 20.4 Ft
 Obs: Plugged Connection

Comments:



Date: 09/25/2012
 Distance: 63.3 Ft
 Obs: Break in Connector

Comments:



Date: 09/25/2012
 Distance: 92.7 Ft
 Obs: Plugged Connection

Comments:



Date: 09/25/2012
 Distance: 111.9 Ft
 Obs: Crack longitudinal

Comments:



Date: 09/25/2012
 Distance: 112.9 Ft
 Obs: Break in Connector

Comments:



Work Order	Video	Surveyed On 09/25/2012	Direction Downstream	Setup 21
Street Name Andover Rd	City Name Hillsdale		Weather Dry	
Location		From Manhole 26	To Manhole 25	


Date: 09/25/2012
 Distance: 150.3 Ft
 Obs: Roots at joint

Comments:



Date: 09/25/2012
 Distance: 188.3 Ft
 Obs: (2) roots from joint

Comments:



Date: 09/25/2012
 Distance: 106.3 Ft
 Obs: Service Connector

Comments:



Date: 09/25/2012
 Distance: 217.3 Ft
 Obs: Break in contraction

Comments:



Date: 09/25/2012
 Distance: 217.5 Ft
 Obs: Roots around
 lateral

Comments:



Date: 09/25/2012
 Distance: 245.1 Ft
 Obs: Plugged Connector

Comments:



Work Order	Video	Surveyed On	Direction	Setup
Street Name Anderholt Rd	City Name Hoboken	09/25/2012	Downstream	21
Location		From Manhole 20		To Manhole 25
			Weather Dry	

Date: 09/25/2012
 Distance: 263.0 Ft
 Obs: Debris (Grease)

Comments:
 CONTAMINATED



Date: 09/25/2012
 Distance: 304.2 Ft
 Obs: Plugged Connection

Comments:



Date: 09/25/2012
 Distance: 355.3 Ft
 Obs: Break in Connection

Comments:



Date: 09/25/2012
 Distance: 355.3 Ft
 Obs: Roots around
 Laterals

Comments:



Date: 09/25/2012
 Distance: 355.3 Ft
 Obs: Roots at joint

Comments:
 TAP ROOTS



Tabular Report of PLR 27

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup 20
Facility	Operator NJP	Van Ref 10	Surveyed On 09/25/2012
Street Name Anteholt Rd		City Holtville	
Location type Surface			
Survey purpose Random survey of pipes and things		Weather Dry	
Pipe Use Sanitary	Sched length	Ft	From 26
Shape Circular	Size ft by	ins	To 27
Material vitrified clay	Joint Spacing	Ft	Direction Up
Lining	Year laid		Pre-clean N Last Cleaned
General notes		Structural	Service
Location note		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					Manhole/Node
	0.0		WL					Water level
	14.7		DEG					Debris (Debris)
	17.8		CL			10		Crack longitudinal
	18.2		CB			10		Break in Connection
	54.5		CP			10		Plugged Connection
	61.3		DEG					Debris (Debris)
	105.8		CB			10		Break in Connection
	128.2		CB			10		Break in Connection
	164.2		CB			10		Break in Connection
	164.3		RJ			M		Roots in joint
	207.4		CP			10		Plugged Connection
	281.1		CP			09		Plugged Connection
	281.8		CL			10		Crack longitudinal
	282.4		CM			12	12	Cracks multiple
	282.8		CB			10		Break in Connection
	303.1		CL			10		Crack longitudinal
	303.5		CB			10		Break in Connection
	302.3		MH					Manhole/Node
	362.3		FH					Finish of Survey

362.3 Ft Total Length Surveyed

Scores	Structural:	Total 400	Mean Defect 30.6	Peak 100	Mean Pipe 1.1
	Service:	Total 175	Mean Defect 43.8	Peak 75	Mean Pipe 0.5





PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-408-6023

Pipe Graphic Report of PLR 27

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	20
Facility	Operator N.P	Van Ref 10	Surveyed On	09/26/2012
Street Name	Anderholt Rd	City	Hotville	
Location type	Surface			
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From 25
Shape	Circular	Size & by	ins	To 27
Material	Vitrified clay	Joint spacing	Ft	Direction
Lining		Year laid		Upstream
General note			Pre-clean	N
Location note			Last cleaned	
			Structural	Servins
			Miscellaneous	Constructional
				Hydraulic




PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-8023

Pipe Graphic Report of PLR 27

X

for Bureau Veritas NA


Work Order	Contract	Video	Setup	20	
Facility	Operator: N.J.P.	Van Ref: 10	Surveyed On	08/26/2012	
Street Name	Anderholt Rd	City	Hobbsville		
Location type					
Surface					
Survey purpose	Random survey of pipes and things	Weather	Dry		
Pipe Use	Sanitary	Schedule length	From 25	Depth	ft
Shape	Circular	Size 8 by	To 27	Depth	ft
Material	Verified clay	Joint spacing	Direction	Upstream	
Lining		Year laid	Pre-clean	N	Last cleaned
General note			Structural	Service	Constructional
Location note			Miscellaneous	Hydraulic	



PipeLogix Inc.
Phone: 866-298-3150
Fax: 760-406-6023

Work Order	Video	Surveyed On 09/25/2012	Direction Upstream	Setup 20
Street Name Ardchot Rd	City Name Inghite	Weather Dry		
Location	From Manhole 26	To Manhole 27		

Date: 09/25/2012
 Distance: 14.7 Ft
 Obs: Debris (Grease)



Comments:

Date: 09/25/2012
 Distance: 17.8 Ft
 Obs: Crack longitudinal



Comments:

Date: 09/25/2012
 Distance: 16.2 Ft
 Obs: Break in Connection



Comments:

Date: 09/25/2012
 Distance: 54.5 Ft
 Obs: Plugged Connector



Comments:

Date: 09/25/2012
 Distance: 61.3 Ft
 Obs: Debris (Sewer)



Comments:
CONTINUING

Date: 09/25/2012
 Distance: 105.6 Ft
 Obs: Break in Connection



Comments:

Work Order	Video	Surveyed On 08/25/2012	Direction Upstream	Setup 20
Street Name Anderson Rd	City Name Hollyville		Weather Dry	
Location		From Manhole 26	To Manhole 27	

Date: 08/25/2012
 Distance: 128.2 Ft
 Obs: Break in Connector



Comments:

Date: 08/25/2012
 Distance: 164.2 Ft
 Obs: Rocks at joint



Comments:

Date: 08/25/2012
 Distance: 251.1 Ft
 Obs: Plugged Connector



Comments:

Date: 08/25/2012
 Distance: 164.2 Ft
 Obs: Break in Connector



Comments:

Date: 08/25/2012
 Distance: 207.4 Ft
 Obs: Plugged Connector



Comments:

Date: 08/25/2012
 Distance: 281.2 Ft
 Obs: Crack longitudinal



Comments:

Work Order	Video	Surveyed On 09/25/2012	Direction Upstream	Setup 20
Street Name Anderson Rd	City Name Hillsville		Weather Dry	
Location		From Manhole 26	To Manhole 27	

Date: 09/25/2012
 Distance: 202.4 Ft
 Obs: Cracks multiple

Comments:




Date: 09/25/2012
 Distance: 323.1 Ft
 Obs: Crack longitudinal

Comments:



Date: 09/25/2012
 Distance: 202.4 Ft
 Obs: Break in Connection

Comments:



Date: 09/25/2012
 Distance: 303.6 Ft
 Obs: Break in Connection

Comments:



Tabular Report of PLR 28

A


for Bureau Veritas NA

Work Order	Contract	Video	Setup 35
Facility	Operator NLP	Ven Ref 10	Surveyed On: 09/27/2012
Street Name	Bartons Worth Rd	City	Huntsville
Location type	Surface		
Survey purpose	Random survey of pipes and things	Weather	Dry
Pipe Use	Sanitary	Sched length	Ft
Shape	Circular	From 28	Depth Ft
Material	Vitrified clay	To 05	Depth Ft
Lining		Joint Spacing	Ft
		Year laid	
General note	Greater survey. Could not attempt line.	Direction	Down
Location note		Pre-clean	N
		Last Cleaned	
		Structural	Service
		Miscellaneous	hydraulic
		Constructional	

Video	Count	CD	Code	Seq	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MI					Manhole/Node 20
	0.0		WS					Water level 0
	0.0		GO					General observation US AND DS MH'S SURCHARGED CO.
	0.0		GO					General observation LINES POSSIBLY SURCHARGED DUE

0.0 Ft Total Length Surveyed

Scores	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe



PipeLogix Inc.
 Phone: 866-295-3150
 Fax: 760-406-6023

Tabular Report of PLR 29

A


for Bureau Veritas NA

Work Order	Contract	Video	Setup 37
Facility	Operator NUP	Van Ref 10	Surveyed On 09/27/2012
Street Name Barbara Worth Rd		City Holtville	
Location type			
Surface			
Survey purpose Random survey of pipes and things		Weather Dry	
Pipe Use Sanitary	Sched length	Ft	From 29
Shape Circular	Size 8	by 12	To 28
Material Vitrifed clay	Joint Spacing	Ft	Depth Ft
Lining	Year laid		Direction Down
General note Created survey. Could not attempt line.		Pre-clean N	Last Cleaned
Location note		Structural	Service
		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					29
	0.0		WL				0	Water level
	0.0		GO					US MH NOT FOUND
	0.0		GO					OS MH SURCHARGED - COULD NOT A...
	0.0		GO					OS MH POSSIBLY SURCHARGED DUE

0.0 Ft Total Length Surveyed

Scores	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Tabular Report of PLR 30

A

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 38 Surveyed On 09/27/2012
Street Name Location type Surface	Barbara Worth Rd City Nashville		
Survey purpose	Random survey of pipes and things		Weather Dry
Pipe Use Shape Material Lining	Sched length Size # by Joint Spacing Year laid	Ft ins Ft	From 30 To 29 Depth Ft Depth Ft Direction Down Pre-clean N Last Cleaned
General note Location note	Created survey. Could not attempt line.		Structural Service Construction Miscellaneous Hydraulic
Video	Count	CD	Code
	0.0		BT Start of Survey
	0.0		MH Manhole/Note
	0.0		WL Water level
	0.0		GO General observation
	0.0		GO General observation
	0.0		0
	0.0		30
	0.0		USE MH IN PRIVATE PROPERTY, NO...
	0.0		DS MH NOT FOUND, COULD NOT AT...

0.0 Ft Total Length Surveyed

Scores

Structural:	Total	Mean Defect	Peak	Mean Pipe
Service:	Total	Mean Defect	Peak	Mean Pipe



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-8023

Tabular Report of PLR 31

A


for Bureau Veritas NA

Work Order Facility	Contract Operator NIP	Video Van Ref 10	Setup 36 Surveyed On 06/27/2012
Street Name Barbara Worth Rd		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 31	Depth Ft
Shape Circular	Size by Ins	To 30	Depth Ft
Material Vitrifed clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note Created survey. Could not attempt line.		Structural	Service
Location note		Miscellaneous	Hydraulic
Video	Count	CD	Code
			Sev Fr To Value Remarks
	0.0		ST Start of Survey
	0.0		MH Manhole/Node
	0.0		WL Water level
	0.0		GD General observation
	0.0		GD General observation

0.0 Ft Total Length Surveyed

Scores

Structural:	Total	Mean Defect	Peak	Mean Pipe
Service:	Total	Mean Defect	Peak	Mean Pipe



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Tabular Report of PLR 32

X


for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 29 Surveyed On 08/26/2012
Street Name Country Club Dr		City Hallsville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 32	Depth Ft
Shape Circular	Size 0 by 16	To 31	Depth Ft
Material Vitrifed clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		MH Manhole/Node					32
	0.0		WL Water level					5
	2.1		RJ Roots at joint		1			
	50.1		RJ Roots at joint		5			
	50.1		CN Service Connection			12		
	90.7		RJ Roots at joint		5			
	105.9		RJ Roots at joint		5			
	118.1		RJ Roots at joint		5			
	124.2		RJ Roots at joint		0			CONTINUING
	144.2		CN Service Connection			01		
	170.8		DEG Debris (Grease)		5			
	231.3		CN Service Connection			12		
	297.2		DS Begin Pipe Sag					
	307.0		DF End pipe sag					
	328.9		CN Service Connection			12		
	329.9		LS Bend in pipe left					
	330.4		GO General observation					BEND TOO TIGHT FOR TRACTOR
	330.5		GO General observation					DS MH NOT FOUND. NO ACCESS FO...
	330.6		SA Survey abandoned					

330.6 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 275	Mean Defect 31.4	Peak 100	Mean Pipe 0.8





PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-8023

Pipe Graphic Report of PLR 32

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	29
Facility	Operator NIP	Van Ref 10	Surveyed On	09/26/2012
Street Name	Country Club Dr	City	Holville	
Location type				
Surface				
Survey purpose	Random survey of pipes and fittings	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From 32
Shape	Circular	Size 6 by	ins	To 31
Material	Verified clay	Joint spacing	Ft	Direction Downstream
Lining		Year laid		Pre-clean N Last cleaned
General note			Structural	Service
Location note			Miscellaneous	Hydraulic
				Constructional




PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Pipe Graphic Report of PLR 32

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	20
Facility	Operator NJP	Van Ref 10	Surveyed On	08/26/2012
Street Name	Country Club Dr	City	Mobile	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	ft	From 32
Shape	Circular	Size	in	by
Material	Vitrified clay	Joint spacing	ft	To 28
Lining		Year laid		Direction
General note				Downstream
Location note				Pre-clean If Last cleaned
				Structural Service Constructional
				Miscellaneous Hydraulic



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Work Order	Video	Surveyed On 09/05/2012	Direction Downstream	Setup 29
Street Name County Club Dr	City Name Hillsville	Weather Dry		
Location	From Manhole 30	To Manhole 31		

Date: 09/05/2012
 Distance: 2.1 Ft
 Obs: Roots at joint

Comments:



Date: 09/05/2012
 Distance: 50.1 Ft
 Obs: Roots at joint

Comments:




Date: 09/05/2012
 Distance: 83.1 Ft
 Obs: Service Connection

Comments:




Date: 09/05/2012
 Distance: 99.7 Ft
 Obs: Roots at joint

Comments:



Date: 09/05/2012
 Distance: 105.9 Ft
 Obs: Roots at joint

Comments:



Date: 09/05/2012
 Distance: 116.1 Ft
 Obs: Roots at joint


Comments:



Work Order	Video	Surveyed On: 09/06/2012	Direction: Downstream	Setup: 20
Street Name: Country Club Dr	City Name: Hoboken	Weather: Dry		
Location:	From Manhole: 32	To Manhole: 31		

Date: 09/06/2012
 Distance: 124.2 Ft
 Obs: Roots at joint

Comments:
 CONTINUING



Date: 09/06/2012
 Distance: 170.8 Ft
 Obs: Debris (Greases)

Comments:



Date: 09/06/2012
 Distance: 207.2 Ft
 Obs: Soft Pipe Sag

Comments:



Date: 09/06/2012
 Distance: 144.2 Ft
 Obs: Service Connection

Comments:



Date: 09/06/2012
 Distance: 251.3 Ft
 Obs: Service Connection

Comments:



Date: 09/06/2012
 Distance: 328.8 Ft
 Obs: Service Connection

Comments:



CCTV pictures of 32

X

for Bureau Veritas NA

Work Order	Video	Surveyed On 09/28/2012	Direction Downstream	Setup 32
Street Name Country Club Dr	City Name Hollyds	Weather Dry		
Location	From Manhole 32	To Manhole 31		

Date: 09/28/2012

Distance: 326.3 ft

Dir: West in pipe left

Comments:



Tabular Report of PLR 33

A


for Bureau Veritas NA

Work Order Facility	Contract Operator NIP	Video Van Ref 10	Setup 36 Surveyed On 09/27/2012
Street Name Barbara Worth Rd		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 33	Depth Ft
Shape Circular	Size \pm by Ina	To 29	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Down	
Lining	Year laid	Pre-clean N	Last Cleaned
General note Coated survey. Could not attempt line.		Structural	Service
Location note		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	00		ST					Start of Survey
	00		MH					33
	00		WL				0	
	00		GD					US MH NOT FOUND, DS MH SURCHA,
	00		GD					LINE POSSIBLY SURCHARGED DUE

0.0 Ft Total Length Surveyed

Scores	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Tabular Report of PLR 06

X


for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 42 Surveyed On: 10/25/2012
Street Name Barbara Worth Rd		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length	From 04	Depth Ft
Shape Circular	Size 10 by Ina	To 06	Depth Ft
Material Polyvinyl chloride	Joint Spacing Ft	Direction Up	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Constructional	
		Macrolithic	Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		MH	Manhole/Node				04
	0.0		WL	Water level				5
	0.0		DS	Begin Pipe Seg				
	0.0		CSB	Camera Submerged Begin				
	1.1		ST	Start of Survey				
	5.1		DE	Defect	L			
	20.0		CSB	Camera Submerged Begin				
	56.6		DF	End pipe seg				
	91.2		LR	Bend in pipe right				
	91.5		GD	General observation				BLOCKED BY TIGHT BEND
	91.5		SA	Survey abandoned				

91.5 Ft Total Length Surveyed

Scores	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe




PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 06

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	42
Facility	Operator N/P	Van Ref 10	Surveyed On	10/25/2012
Street Name	Barbara Worth Rd	City	Hobbs	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	From 04	Depth
Shape	Circular	Size 10 by	To 06	Depth
Material	Polyvinyl chloride	Joint spacing	Direction	Upstream
Lining		Year laid	Pre-clean	N Last cleaned
General note			Structural	Service
Location note			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Tabular Report of PLR 07


X

for Bureau Veritas NA

Work Order Facility	Contract Operator N/P	Video Van Ref 10	Setup 43 Surveyed On 10/25/2012
Street Name Country Club Dr		City Rutledge	
Location type Surface			
Survey purpose Random survey of pipes and things		Weather Dry	
Pipe Use Sanitary	Sched length Ft	From 06	Depth Ft
Shape Circular	Size 10 by In	To 07	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Up	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Microcracks	Hydraulic
Video	Count	CD	Code
			Sev Fr To Value Remarks
	0.0		ST Start of Survey
	0.0		MH Manhole/Node
	0.0		WL Water level
	75.7		OS Begin Pipe Sag
	105.3		CUB Camera Submerged Begin
	174.6		CUE Camera Submerged End
	197.4		OF End pipe sag
	268.4		MH Manhole/Node
	268.4		PH Finish of survey
268.4 Ft Total Length Surveyed			

Scores


Structural:	Total	Mean Defect	Peak	Mean Pipe
Service:	Total	Mean Defect	Peak	Mean Pipe



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 07 X for Bureau Veritas NA

Work Order	Contract	Video	Setup	43		
Facility	Operator NJP	Van Ref 10	Surveyed On	10/25/2012		
Street Name	County Club Dr	City	Holville			
Location type						
Surface						
Survey purpose	Random survey of pipes and things	Weather	Dry			
Pipe Use	Sanitary	Schedule length	Ft	From 06	Depth	Ft
Shape	Circular	Size 10 by	ins	To 07	Depth	Ft
Material	Vitrified clay	Joint spacing	Ft	Direction	Upstream	
Lining	Year laid		Pre-clean	N	Last cleaned	
General note			Structural	Service	Constructional	
Location note			Miscellaneous	Hydraulic		



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Tabular Report of PLR 07

X

for Bureau Veritas NA

Work Order Facility		Contract Operator NJP		Video Van Ref 10		Setup 44 Surveyed On 10/25/2012		
Street Name Country Club Dr				City Holmdel				
Location type Surface				Weather Dry				
Survey purpose Random survey of pipes and things								
Pipe Use Sanitary		Sched length Ft		From 07		Depth Ft		
Shape Circular		Size 10 by ins		To 06		Depth Ft		
Material Vitified clay		Joint Spacing Ft		Direction Down				
Lining		Year laid		Pre-clean N		Last Cleaned		
General note				Structural		Service		
Location note				Macrolonodus		Hydraulic		
Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		BT Start of Survey					
	0.0		MH Manhole/Node					07
	0.0		WL Water level				5	
	88.1		DEG Debris (Grease)	II	12			
	88.6		DS Begin Pipe Sag					
	88.8		GO General observation					Camera going submerged. end of
	88.8		SA Survey abandoned					

88.8 Ft Total Length Surveyed

Scores	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe




PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 07

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup
Facility	Operator NLP	Van Ref 10	44
Street Name	Country Club Dr	City	Holtville
Location type			
Surface			
Survey purpose	Random survey of pipes and things	Weather	Dry
Pipe Use	Sanitary	Schedule length	Ft
Shape	Circular	From	07
Material	Vitrified clay	To	08
Lining		Joint spacing	Ft
		Year laid	
		Direction	Downstream
		Pre-clean	N
		Last cleaned	
General note		Structural	Service
Location note		Miscellaneous	Hydraulic
		Construction	M



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-8023

Tabular Report of PLR 11

X

for Bureau Veritan NA

Work Order Facility	Contract Operator NLP	Video Van Ref 10	Setup 45 Surveyed On 10/25/2012
Street Name: Barbara Worth Dr		City: Hillville	
Location type Surface			
Survey purpose: Random survey of pipes and things		Weather: Dry	
Pipe Use: Sanitary	Sched length: Ft	From 07	Depth: Ft
Shape: Circular	Size 8 by ins	To 11	Depth: Ft
Material: Vitrified clay	Joint Spacing: Ft	Direction: Up	
Lining	Year laid	Pre-clean: N	Last Cleaned
General note		Structural	Service
Location note		Nonstructural	Hydraulic

Video	Count	CB	Code	Seq	Fr	To	Value	Remarks
	0.0		BT					Start of Survey
	0.0		MH					07
	0.0		WL					5
	7.0		JD		N			
	103.4		CC		L			1/2 Pipe full of grease
	103.4		DFG		L			
	103.4		GC					Blocked by grease
	103.4		SA					Survey ended

103.4 Ft Total Length Surveyed


Scores	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Pipe Graphic Report of PLR 11 X for Bureau Veritas NA

Work Order	Contract	Video	Setup	45
Facility	Operator N.J.F	Van Ref 10	Surveyed On	10/25/2012
Street Name	Barbara Worth Dr	City	Holtville	
Location type				
Surface				
Survey purpose	Random survey of pipes and fittings	Weather	Dry	
Pipe Use	Sanitary	Schedule length	From 07	Depth Ft
Shape	Circular	Size 8 by	Tu 11	Depth Ft
Material	Vitrified clay	Joint spacing	Direction Upstream	
Lining		Year laid	Pre-clean N	Last cleaned
General note			Structural	Service
Location note			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
Phone: 866-289-3150
Fax: 760-406-6023

Tabular Report of PLR 11

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Vsn Ref 10	Setup 46 Surveyed On 10/25/2012
Street Name Barbara Worth Dr		City Holtsville	
Location type Surface			
Survey purpose Random survey of pipes and things		Weather Dry	
Pipe Use Sanitary	Sched length	Ft	From 07
Shape Circular	Size 8 by	ins	To 11
Material Vertified clay	Joint Spacing	Ft	Direction Up
Lining	Year laid		Pre-clean N Last Cleaned
General note			Structural Service Constructional
Location note			steep/sloped Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		WC	Water level			5	
	0.0		BT	Begin of Survey				
	0.0		MH	Manhole/Node			07	
	7.0		JD	Joint Displaced	M			
	64.2		CC	Circular Crack	S	12	12	
	64.7		H	Hole in sewer	S	02		
	140.3		GO	General observation				LARGE DEBRIS/GREASE IN US MH
	140.3		MH	Manhole/Node			11	
	140.3		FI	Finish of Survey				

140.3 Ft Total Length Surveyed


SCORES	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 11 X for Bureau Veritas NA

Work Order	Contract	Video	Setup	45				
Facility	Operator	Van Ref	Surveyed On	10/25/2012				
Street Name	Barbara Worth Dr	City	Holtville					
Location type								
Surface								
Survey purpose	Random survey of pipes and things	Weather	Dry					
Pipe Use	Sanitary	Schedule length	Ft	From	07	Depth	Ft	
Shape	Circular	Size	6 by	Inch	To	11	Depth	Ft
Material	Vitrified clay	Joint spacing	Ft		Direction	Upstream		
Lining	Year installed				Pre-clean	N	Last cleaned	
General note			Structural	Service	Constructional			
Location note			Miscellaneous	Hydraulic				



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Tabular Report of PLR 08

X

for Bureau Veritas NA

Work Order		Contract		Video		Setup 47		
Facility		Operator N.P		Van Ref 10		Surveyed On 10/25/2012		
Street Name Barbara Worth Rd				City Hobbs				
Location type				Surface				
Survey purpose Random survey of pipes and fittings				Weather Dry				
Pipe Use Sanitary		Sched length		Ft		From 07		
Shape Circular		Size 8 by		Ins		To 08		
Material Vitrified clay		Joint Spacing		Ft		Direction Up		
Lining		Year laid				Pre-clean N		
General note						Last Cleaned		
Location note						Structural Service Constructional		
						sewerage Hydraulic		
Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		BT					Start of Survey
	0.0		SH					Manhole Node
	0.0		WL					Water level
	1.0		DEG		L			Debris (Grease)
	4.0		OB		L			Debris
	4.0		GD					General observation
	4.0		SA					Survey abandoned

4.0 Ft Total Length Surveyed



Scores	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Pipe Graphic Report of PLR 08 X for Bureau Veritas NA

Work Order	Contract	Video	Setup	47
Facility	Operator NJP	Van Ref 10	Surveyed On	10/25/2012
Street Name	Barbara Worth Rd	City	Holbille	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	From 07	Depth
Shape	Circular	Size 8 by	To 08	Depth
Material	Vitrified clay	Joint spacing	Direction	Upstream
Lining		Year laid	Pra-clean	N Last cleaned
General note			Structural	Service
Location note			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
 Phone: 866-299-3150
 Fax: 760-406-6023

Tabular Report of PLR 08

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 48 Surveyed On: 10/25/2012
Street Name: Barbara Worth Rd		City: Holtville	
Location type Surface		Weather: Dry	
Survey purpose: Random survey of pipes and things			
Pipe Use: Sanitary	Sched length	Fi	From 07
Shape: Circular	Size 0 by	Ins	To 08
Material: Vitified clay	Joint Spacing	Ft	Direction: Up
Lining	Year laid		Pre-clean: N Last Cleaned
General note		Structural	Service Constructional
Location note		Miscellaneous	Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		BT					Start of Survey
	0.0		MH					Manhole/Node 07
	0.0		WL					Water level 3
	8.0		DS					Begin Pipe Sag
	13.7		DF					End pipe sag
	114.1		ON			02		Service Connection
	146.1		CC	M	12	12		Circular Crack
	146.7		CB			12		Break in Connection
	146.7		CL	M	01			Crack longitudinal
	147.3		B	L	12	12		Broken Pipe
	151.3		MH					Manhole/Node 08
	151.3		PH					Finish of Surveys

101.3 FT Total Length Surveyed

Scores	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe




PipeLogix Inc.
Phone: 866-299-3150
Fax: 780-406-6023

Pipe Graphic Report of PLR 08

X

for Bureau Veritas NA

Work Order	Contract		Video	Setup 45
Facility	Operator NJP		Van Ref 10	Surveyed On 10/25/2012
Street Name	Barbara Worth Rd	City	Hotville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things		Weather	Dry
Pipe Use	Sanitary	Schedule length	Fl	From 07
Shape	Circular	Size 8 by	ins	To 05
Material	Vitrified clay	Joint spacing	Fl	Direction Upstream
Lining		Year laid		Pre-clean N Last cleaned
General notes			Structural	Service
Location note			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Tabular Report of PLR 29

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 49 Surveyed On 10/25/2012
Street Name Barbara Worth Rd		City Holmdel	
Location type Surface			
Survey purpose Random survey of pipes and things		Weather Dry	
Pipe Use Sanitary	Sched length	Ft	From 28
Shape Circular	Size 8 by	Ins	To 29
Material Vitrified clay	Joint Spacing	Ft	Direction Up
Lining	Year laid		Pre-clean N Last Cleaned
General note		Structural	Service
Location note		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Seq	Fr	To	Value	Remarks
	0.0		BT					Start of Survey
	0.0		MH					Manhole/Node 28
	0.0		WL				3	Water level
	105.6		CP			03		Plugged Connection
	192.6		CP			03		Plugged Connection
	202.4		CB			02		Break in Connection
	247.3		CC		M	12	12	Circular Crack
	248.1		CB			12		Break in Connection
	248.1		CL		M	01		Crack longitudinal
	253.5		JD		M			Joint Displaced
	288.0		CP			03		Plugged Connection
	318.8		DE		L			Debris
	325.0		CB			02		Break in Connection
	330.6		CP			03		Plugged Connection
	365.8		MH					Manhole/Node 29
	365.8		FH					Finish of Survey

365.6 Ft Total Length Surveyed

Scores

Structural:	Total	Mean Defect	Peak	Mean Pipe
Service:	Total	Mean Defect	Peak	Mean Pipe





PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 29

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	49
Facility	Operator	NIP	Van Ref	10
Street Name	Barbara Worth Rd	City	HolMile	
Location type	Surface			
Survey purpose	Random survey of pipes and things		Weather	Dry
Pipe Use	Sanitary	Schedule length	From	28
Shape	Circular	Size	To	29
Material	Vitrified clay	Joint spacing	Direction	Upstream
Lining		Year/aid	Pre-clean	N
General note			Last cleaned	
Location note			Structural	Service
			Miscellaneous	Hydraulic
			Constructional	



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-408-6023

Tabular Report of PLR 30

X


for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 50 Surveyed On 10/25/2012
Street Name Barbara Worth Rd		City Mobile	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From 28	Depth Ft
Shape Circular	Size 8 by Ins	To 30	Depth Ft
Material Vitrified clay	Joint Spacing Ft	Direction Up	
Lining	Year laid	Pre-clean N	Last Cleaned
General note		Structural	Service
Location note		Constructional	Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST					Start of Survey
	0.0		MH					28
	0.0		WL					1
	35.8		CB			02		
	50.2		CP			03		
	61.4		CB			03		
	124.1		CP			02		
	157.0		CB			03		
	197.6		CP			03		
	270.7		CB			02		
	276.7		CP			03		
	327.6		CN			02		
	339.7		CN			02		
	359.3		MH					30
	359.3		PK					Finish of surveys

359.3 Ft Total Length Surveyed

Scores	Structural:	Total	Mean Defect	Peak	Mean Pipe
	Service:	Total	Mean Defect	Peak	Mean Pipe




PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR 30

X

for Bureau Veritas NA

Work Order		Contract		Video		Setup 50	
Facility		Operator NJP		Var Ref 10		Surveyed On 10/25/2012	
Street Name Barbara Worth Rd		City		Holtville			
Location type							
Surface							
Survey purpose Random survey of pipes and fittings				Weather Dry			
Pipe Use Sanitary		Schedule length Ft		From 29		Depth Ft	
Shape Circular		Size 6 by Ins		To 30		Depth Ft	
Material Vitrified clay		Joint spacing Ft		Direction Upstream			
Lining		Year laid		Pre-clean N Last cleaned			
General note				Structural		Service	
Location note				Miscellaneous		Hydraulic	



PipeLogix Inc.
Phone: 888-299-3150
Fax: 760-408-8023

Tabular Report of PLR 33

X

for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 51 Surveyed On 10/29/2012
Street Name Barbara Worth Rd		City Hotville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Size 4 by Joint Spacing Year laid	Ft Inch Ft	From 28 To 33 Direction Up Pre-clean N Last Cleaned
Shape Circular			Depth Depth Ft
Material Vitified clay			
Lining			
General note RAN WITH PUSH CAMERA		Structural	Service Constructional
Location note		Mechanical	Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		BT					Start of Survey
	0.0		MH					28
	0.0		WL					5
	58.0		CN		10			
	176.0		DE	M				DEBRIS AND GREASE
	150.0		GO					CAMERA STOPPED PUSHING
	160.0		GO					PULL CAMERA BACK TO START
	180.0		BA					END AT 0 FOOT

180.0 Ft Total Length Surveyed

Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 75	Mean Defect 37.5	Peak 75	Mean Pipe 0.4





PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-466-6023

Pipe Graphic Report of PLR 33

X

for Bureau Veritas NA

Work Order	Contract	Video	Setup	51	
Facility	Operator NJP	Van Ref 10	Surveyed On	10/29/2012	
Street Name	Barbara Worth Rd	City	Holtville		
Location type					
Surface					
Survey purpose	Random survey of pipes and things	Weather	Dry		
Pipe Use	Sanitary	Schedule length	From 20	Depth	Ft
Shape	Circular	Size 4 by	To 33	Depth	Ft
Material	Vitrified clay	Joint spacing	Direction	Upstream	
Lining		Year laid	Pre-clean	N	Last cleaned
General note	RAN WITH PUSH CAMERA		Structural	Service	Constructional
Location note			Metallic	Hydraulic	



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

FORCE MAIN

Tabular Report of PLR PUMP STATION 01 A for Bureau Veritas NA

Work Order Facility	Contract Operator NUP	Video Van Ref 10	Setup 40 Surveyed On 09/27/2012
Street Name Even Howes Hwy		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and fittings			
Pipe Use Sanitary	Sched length	Ft.	From PUMP STATION 01
Shape Circular	Size 4	by ins	To NORTH
Material Polyvinyl chloride	Joint Spacing	Ft.	Direction Down
Lining	Year laid		Pre-clean N Last Cleaned
General note Valve removed for camera access			Structural Service Constructional
Location note Line is a force main			Miscellaneous Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		BT					Start of Survey
	0.0		MH					PUMP STATION 01
	0.0		WL				0	Water level
	2.0		LD					Bend in pipe down
	8.0		CUB					Camera Submerged Begin
	43.0		CUE					Camera Submerged End
	68.0		CUB					Camera Submerged Begin
	95.0		CUE					Camera Submerged End
	95.0		GO					General observation
	100.0		GO					General observation
	100.0		SA					Survey abandoned

100.0 Ft Total Length Surveyed


Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0



PipeLogix Inc.
Phone: 866-289-3150
Fax: 780-406-6023

Pipe Graphic Report of PLR PUMP STATION 01 A for Bureau Veritas NA

Work Order	Contract	Video	Setup	40
Facility	Operator NJP	Van Ref 10	Surveyed On	09/27/2012
Street Name	Evan Hewes Hwy	City	Holville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From PUMP STATION 01 Depth Ft
Shape	Circular	Size 4 by	ins	To NORTH Depth Ft
Material	Polyvinyl chloride	Joint spacing	Ft	Direction Downstream
Lining		Year laid		Pre-clean N Last cleaned
General note	Valve removed for camera access	Structural	Service	Construction
Location note	Line is a force main	Miscellaneous	Hydraulic	



Tabular Report of PLR PUMP STATION 01 Y for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 41 Surveyed On 08/27/2012
Street Name Even Hewes Hwy		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From NORTH	Depth Ft
Shape Circular	Size 4 by in	To PUMP STATION 01	Depth Ft
Material Polyvinyl chloride	Joint Spacing Ft	Direction Up	
Lining	Year laid	Pre-clean Y	Last Cleaned 9/25/2012
General note Reverse setup attempted for maximum length of		Structural	Service
Location note inspection		Miscellaneous	Constructional
			Hydraulic

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		ST Start of Survey					
	0.0		MH Manhole/node					NORTH
	0.0		WL Water level				50	
	21.0		CLB Camera Submerged Begin					
	33.0		CLE Camera Submerged End					
	89.0		CLB Camera Submerged Begin					
	132.0		CLE Camera Submerged End					
	315.0		GO General observation					Started video at 3:15B
	315.0		SA Survey abandoned					Completed video at 06 at 06 ...

315.0 Ft Total Length Surveyed


Scores

Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
Service:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0



Pipe Graphic Report of PLR PUMP STATION 01 Y for Bureau Veritas NA

Work Order	Contract	Video	Setup	41
Facility	Operator NJP	Van Ref 10	Surveyed On	09/27/2012
Street Name	Even Hewes Hwy	City	Hotville	
Location type				
Surface				
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	From	NORTH
Shape	Circular	Size 4 by	To	PUMP STATION 01
Material	Polyvinyl chloride	Joint spacing	Direction	Upstream
Lining		Year laid	Pre-clean	Y
			Last cleaned	9/25/2012
General note	Reverse setup attempted for maximum length of	Structural	Service	Constructional
Location note	inspection	Miscellaneous	Hydraulic	



FORCE MAIN

Tabular Report of PLR OPEN PIT X for Bureau Veritas NA

Work Order Facility	Contract Operator NJP	Video Van Ref 10	Setup 52 Surveyed On: 10/29/2012
Street Name: Barbara Worth Rd		City: Holville	
Location type Surface		Weather: Dry	
Survey purpose: Random survey of pipes and things			
Pipe Use: Sanitary	Sched length: Ft	From: OPEN PIT	Depth: Ft
Shape: Circular	Size 4 by Ins	To: TO NORTH	Depth: Ft
Material: Cast-iron PVC	Joint Spacing: Ft	Direction: Down	
Lining:	Year laid:	Pre-clean: N	Last Cleaned:
General note: RAM WITH PUSH CAMERA		Structural	Service
Location note:		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		BT					Start of Survey
	0.0		MH					Manhole/Node
	0.0		WL				0	Water level
	0.0		GO					General observation
	64.0		CUE					Camera Submerged End
	165.0		CUE					Camera Submerged End
	196.0		CUE					Camera Submerged End
	196.0		DE	M				DEBRIS AND GREASE
	218.0		DE	M				UNDER FLOW
	298.0		LL					Band in pipe left
	298.0		CUB					Camera Submerged Begin
	308.0		GO					General observation
	308.0		GO					General observation
	308.0		BA					Survey abandoned

308.0 Ft Total Length Surveyed


Scores	Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
	Service:	Total 158	Mean Defect 21.4	Peak 75	Mean Pipe 0.5



PipeLogix Inc.
Phone: 866-299-3150
Fax: 760-406-6023

Pipe Graphic Report of PLR OPEN PIT X for Bureau Veritas NA

Work Order	Contract	Video	Setup	52		
Facility	Operator NJP	Van Ref 10	Surveyed On	10/29/2012		
Street Name	Barbara Worth Rd	City	Holtville			
Location type						
Surface						
Survey purpose	Random survey of pipes and things		Weather Dry			
Pipe Use	Sanitary	Schedule length	Ft	From OPEN PIT	Depth	Ft
Shape	Circular	Size 4 by	ins	To TO NORTH	Depth	Ft
Material	Vitrified clay	Joint spacing	Ft	Direction	Downstream	
Lining		Year laid		Pre-clean	N	Last cleaned
General note	RAN WITH PUSH CAMERA			Structural	Service	Constructional
Location note				Miscellaneous	Hydraulic	



PipeLogix Inc.
Phone: 888-299-3150
Fax: 760-406-8023

FORCE MAIN

Tabular Report of PLR TO PUMP STATION X for Bureau Veritas NA

Work Order Facility	Contract Operator N/P	Video Van Ref 10	Setup 53 Surveyed On 10/28/2012
Street Name Barbara Worth Rd		City Holtville	
Location type Surface		Weather Dry	
Survey purpose Random survey of pipes and things			
Pipe Use Sanitary	Sched length Ft	From OPEN PIT	Depth Ft
Shape Circular	Size 4 by Ins	To TO PUMP STATION	Depth Ft
Material Cast Iron PVC	Joint Spacing Ft	Direction Up	
Lining	Year laid	Pre-clean N	Last Cleaned
General note RAN WITH PUSH CAMERA		Structural	Service
Location note		Miscellaneous	Hydraulic
		Constructional	

Video	Count	CD	Code	Sev	Fr	To	Value	Remarks
	0.0		BT					Start of Survey
	0.0		MPI					OPEN PIT
	0.0		WS				0	Water level
	24.0		CUE					Camera Submerged End
	59.0		CUB					Camera Submerged Begin
	72.0		CUE					Camera Submerged End
	179.0		GD					General observation
	178.0		CUB					Camera Submerged Begin
	178.0		GD					General observation
	178.0		SA					Survey abandoned

178.0 Ft Total Length Surveyed

Scores


Structural:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0
Service:	Total 0	Mean Defect 0	Peak 0	Mean Pipe 0



PipeLogix Inc.
Phone: 866-299-3160
Fax: 760-406-6023

Pipe Graphic Report of PLR TO PUMP STATION X for Bureau Veritas NA

Work Order	Contract	Video	Setup	63
Facility	Operator: NJP	Van Ref: 10	Surveyed On	10/29/2012
Street Name	Barbara Worth Rd	City	Holtsville	
Location type	Surface			
Survey purpose	Random survey of pipes and things	Weather	Dry	
Pipe Use	Sanitary	Schedule length	Ft	From OPEN PIT
Shape	Circular	Size 4 by	ins	To TO PUMP STATION
Material	Vitrified clay	Joint spacing	Ft	Depth
Lining		Year laid		Depth
General note	RAN WITH PUSH CAMERA		Pre-clean	N
Location note			Last cleaned	
		Structural	Service	Constructional
		Miscellaneous	Hydraulic	



PipeLogix Inc.
Phone: 866-289-3150
Fax: 760-408-6023

*Exhibit B – Colorado River Basin Regional Water Quality Control Board –
NOTICE OF VIOLATION, Barbara Worth Country Club Collection System,
October 5, 2021*



Colorado River Basin Regional Water Quality Control Board

Certified Mail: 7018 1830 0001 0265 0484

October 5, 2021

John Gay
Director of Public Works
Imperial County
155 S. 11th Street
El Centro, CA 92243
JohnGay@co.imperial.ca.us

**SUBJECT: NOTICE OF VIOLATION, BARBARA WORTH COUNTRY CLUB
COLLECTION SYSTEM, HOLTVILLE, IMPERIAL COUNTY**

Dear Mr. Gay:

The California Regional Water Quality Control Board, Colorado River Basin Region (Regional Water Board), is the public agency with primary responsibility for the protection of ground and surface water quality for all beneficial uses within Imperial County (County) as well as portions of Riverside, San Diego and San Bernardino County, including the referenced property above.

On February 1, 2021 at approximately 1:30 p.m., Joseph Lechuga of Percwater notified the Regional Water Board of a Sanitary Sewer Overflow (SSO) event at Barbara Worth Country Club Force Main south of Zen Drive near 2050 Country Club Drive, Holtville, CA 92250. The total volume of the spill was reported to be 36,000 gallons, with all the sewage percolating into the ground.

On a separate event, April 21, 2021 at approximately 12:34 p.m. Joseph Lechuga of Percwater notified the Regional Water Board of a SSO event at Barbara Worth Country Club Force Main south of Zen Drive near 2050 Country Club Drive, Holtville, CA 92250. The total volume of the spill was reported to be 30,000 gallons, with all the sewage washed away into the drain ditch.

YOU ARE HEREBY NOTIFIED that the discharge violated the California Water Code (CWC) section 13350 as follows:

NANCY WRIGHT, CHAIR | PAULA RASMUSSEN, EXECUTIVE OFFICER

- Discharge of untreated sewage into Waters of the United States


The County is required to comply with the following tasks:

1. Immediately implement corrective and preventive actions to prevent further discharge of untreated sewage from the collection system, and
2. In accordance to Order No. 2006-0003-DWQ, the enrollee must develop and implement a system-specific Sewer System Management Plan (SSMP). Please provide the SSMP for the Barbara Worth sewer system to the Regional Water Board by November 1, 2021.

Pursuant to CWC section 13350(e), you are subject to penalties of up to \$5,000 for each day in which the violation occurs or \$10 for each gallon of waste discharged, but not both, for the violation listed above. These administrative civil liabilities may be assessed by the Regional Water Board beginning with the date that the violations first occurred and without further warning. This matter may be referred to the Office of the Attorney General for further enforcement. The Regional Water Board reserves its right to take any further enforcement action authorized by law.

If you have any questions concerning this matter, please contact Reggie Tan at (760) 776-8944 (reginald.tan@waterboards.ca.gov), or Jose Cortez at (760) 776-8963 (jose.cortez@waterboards.ca.gov)

Sincerely,



Cassandra Owens
Assistant Executive Officer
Colorado River Basin
Regional Water Quality Control Board

RT/jc

Enclosure: General Order 2006-0003-DWQ

cc: Joseph Lechuga, Percwater, jlechuga@percwater.com
Frank Cornejo, City of Holtville, fcornejo@holtville.ca.gov
Jeff Lamoure, Imperial County Department of Environmental Health, jefflamoure@co.imperial.ca.us
Alphonso Andrade, Imperial County Department of Environmental Health, AlphonsoAndrade@co.imperial.ca.us
Afrooz Farsimadan, State Water Board, Afrooz.Farsimadan@waterboards.ca.gov